TV & VIDEO ✲ AUDIO ✲ COMPUTERS ✲ AUTO ELECTRONICS!

WIN A HIGH-TECH NIGHT VIEWER WORTH 999!

NDD

Electronics

AUSTRALIA WITH Professional Electron

JUNE 1996 $5.50
NZ $7.20 incl GST

DRAGON DICTATE 2.0 FOR WINDOWS: TALK TO YOUR PC!


LOW COST 50W PER CHANNEL STEREO AMPLIFIER TO BUILD


HOW CHIP MAKERS USE FAINT LIGHT TO TRACK DOWN ELUSIVE FAULTS



06
9 312966 123633

What if a scope's REAL ability to solve your problems could be found in a spec sheet?





HP 54615B

- 500 MHz bandwidth
- 1 GSa/s sampling rate
- 1 ns peak detect

READER INFO NO. 1

All scopes look wonderful on paper.

The real questions come when you try to use one on the job. Is it catching narrow glitches? Am I really protected from aliasing problems? Why doesn't it respond faster when I turn a knob? And what am I missing while it's struggling to process old data?

Beyond the numbers, to real-world performance.

It's not that the new HP 54615B digital scope doesn't look great on paper, too. Check out the the 1 GSa/s sampling, 500 MHz bandwidth, 1 ns peak detect (at all sweep speeds) and display updates of up to 0.5 million points/second. But it's how this performance works for you that makes all the difference.

With not one but three micro-processors working on your data, the HP 54615B responds instantly and dramatically reduces dead time between data blocks (so it doesn't struggle to keep up with the input signal). And patented alias reduction minimises the false signals that show up on other scopes.

So call HP to try the new HP 54615B and discover the difference between paper performance and real performance.

Get a scope that'll get the job done. Call Tassia on 1800 629 485 (Aust-wide) or 9272 2902 (Melbourne callers).

There is a better way.

HEWLETT® PACKARD


Electronics

AUSTRALIA with Professional Electronics & ETI

Volume 58, No.6
June 1996


AUSTRALIA'S LARGEST SELLING ELECTRONICS MAGAZINE — ESTABLISHED IN 1922

See in the (almost) dark!



Graham Cattley has been evaluating the new Apple Nighteyes night viewer, which uses 'starlight' technology. His review starts on page 16. You also have the chance to win one for yourself — for details see page 19.

Building our RF oscillator



As well as being low in cost, our new RF Test Oscillator is particularly easy to build as virtually all of the internal wiring is performed by two PCBs which connect directly together via terminal pins. Full details on its construction and setting up are in the article starting on page 60...

On the cover

Federal advertising production coordinator Magdaline Youssef tries out the new DragonDictate for Windows Version 2.0, which allows PC users to dictate and control Windows applications — using very close to normal continuous speech. It's reviewed this month, starting on page 116. (Photo by Phil Aynsley.)

Video and Audio

8 **WHAT'S NEW IN VIDEO & AUDIO** *Yamaha DSP amp includes Dolby AC-3*
10 **THE CHALLIS REPORT** *Battery blues, and new battery technology*
14 **SONIQUE'S 4.5 SPEAKER SYSTEM** *Compact, but very high quality*

Features

6 **MOFFAT'S MADHOUSE** *In defence of the Internet...*
16 **APPLE NIGHTEYES NIGHT VISION SCOPE** *Uses 'starlight technology'*
19 **WIN YOUR OWN APPLE NIGHTEYES!** *From Dick Smith Electronics...*
20 **END OF AN ERA FOR SILICON VALLEY** *David Packard's remarkable life*
26 **USING THE FAINT GLOW FROM IC DEFECTS** *Emission microscopy*
30 **LOCAL FIRM DEVELOPS SPEAKING WEATHER ROBOT** *Call it up!*
32 **DART: USING ISDN TO DELIVER RADIO ADS** *Much faster than couriers*
36 **WHEN I THINK BACK...** *Arthur Spring, a true 'hands on' engineer (1)*
80 **CAPTURING THE WARM GLOW OF HEAVENLY BODIES** *ANU's CASPIR*

Projects and Technical

46 **THE SERVICEMAN** *The serviceman who made a temporary repair to an IC!*
50 **CIRCUIT & DESIGN IDEAS** *Frequency metering for 'Vernus' sweeper, more*
54 **50W/CHANNEL STEREO AMPLIFIER - 1** *Upgrade of a very popular design*
60 **LOW COST RF TEST OSCILLATOR - 2** *Construction and setting it up*
72 **'STEAM WHISTLE' FOR MODEL BOATS, TRAINS** *Low cost, very flexible*
84 **AUTOMOTIVE ELECTRONICS** *Bosch EST in the VK Commodore, XF Falcon*
88 **PORTABLE AMATEUR RADIO REVISITED - 3** *A higher power transmatch*
98 **VINTAGE RADIO** *RF gain control and variable-mu valves*

Columns and Comments

4 **LETTERS TO THE EDITOR** *Cache checker update, Dr Ernest Benson*
5 **EDITORIAL VIEWPOINT** *The importance of servicing information for EMC*
25 **SHORTWAVE LISTENING** *Bouganville's radio war continues*
42 **FORUM** *Should electronics technicians be paid more than street sweepers?*
94 **INFORMATION CENTRE** *Fidonet, class A amplifiers, Flexitimers and more*

Departments


18 **BOOK REVIEWS**
102 **MARKETPLACE**
104 **EA HISTORY, CROSSWORD**
130 **DIRECTORY OF SUPPLIERS**
130 **ADVERTISING INDEX**
115 **EA SUBSCRIPTIONS OFFER**
35 **NOTES & ERRATA**

Professional Electronics

106 **NEWS HIGHLIGHTS** *Official opening for upgraded QSA's chip foundry*
110 **SOLID STATE UPDATE** *AMD claims micro outperforms Pentium 75*
112 **NEW PRODUCTS** *'Smart' electronic security clips, three-phase EMC filter*
116 **SPOTLIGHT ON SOFTWARE** *DragonDictate for Windows, Version 2.0*
120 **FEATURE: NEW T&M PRODUCTS** *DMM computer interface card, RF meter*
124 **SILICON VALLEY NEWSLETTER** *Israel moves on Intel chip plant*
126 **COMPUTER NEWS & NEW PRODUCTS** *PC based audio analyser*

MANAGING EDITOR
Jamieson Rowe, B.A., B.Sc., SMIREE, VK2ZLO
TECHNICAL EDITOR
Rob Evans, CET (RMIT)
PROJECT DESIGNER/WRITER
Graham Cattley
PRODUCTION EDITOR
Witold Budzynski, B.Sc.
CONTRIBUTORS
Louis Challis
Arthur Cushen, MBE
Peter Lankshear
Jim Lawler, MTETIA
Tom Moffat, VK7TM
Peter Phillips, B.Ed., Dip Ed., ECC
Nick de Vries, MIAME, AMSAE
Neville Williams, FIREE, VK2XV
READER SERVICES CO-ORDINATOR
Ana Marie Zamora; phone (02) 353 0620
DRAFTING
Drawquick Computer Graphics
COVER DESIGNER
Clive Davis
ADVERTISING MANAGER
Selwyn Sayers
Phone (02) 353 0734; fax (02) 353 0613
ADVERTISING PRODUCTION
Tim Cooney; phone (02) 353 0740
PRODUCTION
Ray Eirth
CIRCULATION MANAGER
Michael Prior
PUBLISHER
Michael Hannan
HEAD OFFICE - EDITORIAL
PO Box 199, Alexandria 2015.
180 Bourke Road, Alexandria 2015.
Phone (02) 353 0620; fax (02) 353 0613
Subscriptions Enquiries:
phone (02) 353 9992; fax (02) 353 0967.
Book Shop Enquiries: phone (02) 353 9944
Computer Bulletin Board: phone (02) 353 0627
INTERSTATE ADVERTISING SALES
MELBOURNE: Pilar Misa, 504 Princes Highway, Noble Park, 3174.
Phone (03) 9213 3222; fax (03) 9701 1534.
BRISBANE: Graham Smith, 26 Chermside Street, Newstead 4006.
Phone (07) 3854 1119; fax (07) 3252 3692.
ADELAIDE: Sue Bowshall, 98 Jervois Street, Torrensville, 5031.
Phone (08) 352 7937; fax (08) 352 6033.
PERTH: Greg Winning, Allen & Associates, 54 Havelock Street, West Perth, 6005.
Phone (09) 321 2998; fax (09) 321 2940.
ELECTRONICS AUSTRALIA is published by Federal Publishing Company, a division of Eastern Suburbs Newspapers Partnership, which is owned by
General Newspapers Pty Ltd.
A.C.N.000 117 322,
Double Bay Newspapers Pty Ltd.
A.C.N.000 237 598, and
Brehmer Fairfax Pty Ltd.
A.C.N.008 629 767,
180 Bourke Road, Alexandria, NSW 2015.
Copyright © 1996 by Federal Publishing Company, Sydney. All rights reserved. No part of this publication may be reproduced in any way without written permission from the Publisher or the Managing Editor.
Printed by Macquarie Print, 51 - 59 Wheelers Lane, Dubbo 2830. Phone (068) 843 444.
Distributed by Newsagents Direct Distribution Pty Ltd, 150 Bourke Rd, Alexandria 2015; phone (02) 353 9911.
ISSN 1036-0212
*Recommended and maximum Australian retail price.
The Australian Publication emblem on the front of this magazine is there to signify that the editorial content in this publication is largely produced and edited in Australia, and that most of the advertisements herein are for products and services available within Australia.

LETTERS TO THE EDITOR



Software, or data?

Please excuse me for being pedantic but as a reader of EA for some years now, I can no longer resist...

A number of your excellent contributors on audio gear, most prominently Louis Challis, refer to the contents of their audio CDs, digital audio tapes etc., as 'software'. Surely it is *data*?

I think the term software is more appropriately used for the algorithms and code that process raw data, to produce desired outputs. I would liken the contents of an audio CD to a text document, with the CD player being the 'word processor' which manipulates and 'displays' the CD contents. In this analogy, most people would agree the text document is data and the word processor is the software.

By the way, I don't intend this as a significant criticism of Mr Challis or others. The content of their columns is generally very interesting reading and first class.

Glenn Pure,
Kambah, ACT

Point taken, Glenn. Strictly speaking I'm sure you're right, although the term 'software' seems to have acquired a broader meaning, to include data as well as programs. I guess that's because inside the systems concerned, both are simply patterns of bits. It's all a matter of how they're interpreted and used, isn't it?

Cache checker update

Following your editorial Jan 96 regarding the cache ram scare, I downloaded the CACHCHK2.ZIP program from your BBS as you suggested. However on running the program I got results I didn't really believe.

I sent Mr van Tassle a copy of the program output and the information I had about my motherboard, a Micronics Pentium 75MHz unit in an Osborne computer. He has now replied, basically advising that CACHCHK2.ZIP has bugs in it. He suggested that I download CACHCHK4.ZIP and the problems should be solved.

I am writing this letter to you because on April 4, your BBS still had CACHCHK2.ZIP in its download file directory. The problem free version CACHCHK4.ZIP is available from the Internet at the following address, using file transfer protocol:

ftp://ftp.coast.net/SimTel/msdos/sysinfo/cachchk4.zip

I am sure I am not the only person that would have encountered problems with version 2, so you may consider replacing the version on your BBS with the new version.

Many thanks for all the effort in producing *EA*. I am a long time purchaser and in the recent years, a subscriber to this informative mag.

Barry O'Connor,
Ballina, NSW

Thanks for the update, Barry. As soon as your message arrived, we obtained a copy of the revised version of Mr van Tassle's program from the ftp address you supplied, and it's already on our BBS instead of the earlier version.

Dr Ernest Benson

Having recently read the very fine articles on Dr Ernest Benson in the January and February issues of your magazine, I felt the urge to write one or two comments.

Firstly, I found them very enjoyable as I knew Ernie for quite a few years. One of our highlights was the system in the old Music Hall Restaurant. The owner, George Miller, talked me into 'building an amplifier" for him as previous systems were not satisfactory. Ernie and I designed the new system using three five-foot tapered columns plus woofers, for a three-channel stereo set up.

I made five amplifiers rather than one, and sub-contracted AWA to make the control console and power supply. (John Hooke had been a student of mine). All in three weeks!

Proscenium shotgun microphones plus foot-light short ones were used. On opening night of *The Specter Of Wickham Manor*, some of the media guests asked George "We noticed the tip of a few microphones — when do you use them?" I think we had only 2 or 3dB variation over the whole theatre and excellent directivity.

However, a couple of points in the second article are not correct. The sound

system in St Andrews cathedral was done by Ernie and myself, as was the Bondi Church In The Market Place; AWA had nothing to do with it. Also, after retiring from Sydney University I, plus manager wife formed Murray Amplifiers P/L and we won the contract for the new Parliament House. Again AWA had no part in the audio.

I sub-contracted Ernie for help with the speaker design and placement. (If one includes the rear connector units there were five and half thousand items.)

As a point of interest, when finalising column design we sat facing the column about three metres away and if we could hear the speaker it was not passed.

It would be very good if the record on Ernie could be put straight.

Cyril Murray,
Ninderry, Qld.

RF radiation concerns

I was recently given a copy of *Electronics Australia* (Sept 1995) and may I say how refreshing it was to read your editorial on the radio frequency radiation health issue highlighted in the ABC *Four Corners* programme.

Our Electromagnetic Field Radiation (EMF) Committee members are concerned and committed people endeavouring to make available to the public information on the issue of electromagnetic field (EMF) exposure and health. Given the state of the scientific research we see the EMF health issue as yet another environmental factor demanding serious attention, long overdue.


There are an increasing number of people reporting that continuous or repeated experience from exposure to EMFs has convinced them that their health and wellbeing is compromised by such exposure. Often anecdotal evidence correlates with scientific research findings, again reinforcing the conviction that artificial EMFs from all sources are biological stressors. The trite remark of 'not proven' made by authorities and those with vested interests regarding EMF causing adverse health effects, give no comfort at all.

One prominent researcher in the USA, Dr William Ross Adey, has strongly criticised Governments and industry for the lack of attention to the EMF health issue. We are in complete agreement with his criticism.

Thank you for your intelligent and thoughtful comment. We believe readers will be the richer for the editorial.

Betty Venables, Research Officer
(Coordinator EMF Committee)
Sutherland Shire Environment Centre
Sutherland, NSW. ❖

EDITORIAL VIEWPOINT



The importance of servicing information for EM compatibility

As we reported in the October 1995 issue, Australia's Spectrum Management Authority last year set up the EMC Framework, a system of regulations designed to begin managing the growing problems of electromagnetic compatibility. This is in line with similar moves in many other countries.

The basic idea of the EMC Framework is that firms marketing new electrical and electronic products are being required to have them tested for compliance with various standards for both EMI radiation and susceptibility to interference from radiation, before being offered for sale. And this is fine, as far as it goes — but of course it doesn't address the matter of compliance during the working life of the products...

With this in mind I was very interested to see a copy of a letter sent recently to the SMA, commenting on the EMC Framework, by Jim Lawler. Many readers of *EA* would know Mr Lawler as a regular contributor to the magazine; however currently he's also Federal President of TETIA, The Electronic Technicians' Institute of Australia, and his letter was written in this capacity.

In the letter, Mr Lawler generally supported the EMC Framework. However he also pointed out the need to ensure that equipment was maintained properly during its working life, so that it *continued* to conform to the required level of electromagnetic compatibility. And he drew the SMA's attention to an ongoing obstacle in this regard: the restricted availability (or at times non-availability) of adequate servicing information, from many manufacturers and distributors.

This is a situation that I've complained about myself, on various occasions. Quite a few manufacturers and importers either refuse to provide service manuals, circuit diagrams, adjustment information (and sometimes even the correct replacement parts) to anyone other than their own appointed 'service agents'; others set arbitrary price levels, below which products are deemed 'disposable' and not worth servicing — so they refuse to make service information available at all. Clearly these sorts of policies not only make it much harder than it should be for the customer to keep the equipment working at all, but as Jim Lawler points out they are also going to make it even harder to ensure that it continues to comply with the EMC Framework...


I know I've been at odds with TETIA at various times in the past, but this is one area where I believe they're quite right. If you think so too, can I suggest that you help both them and yourself (in the long run) by writing a letter supporting the need for adequate servicing information, to the Manager, Radiocommunications Standards, Spectrum Management Authority, PO Box 78, Belconnen ACT 2616.

By the way, during a phone discussion with Jim Lawler I gather that TETIA is attempting to gather documentary evidence on some of the above restrictive practices by manufacturers and distributors, regarding servicing information, to submit to the SMA. So if you have such evidence, please send it to TETIA's Tasmanian Division, at 16 Adina Street, Geilston Bay 7015.

Jim Rowe

Moffat's Madhouse...

by TOM MOFFAT



In defence of the Internet...

"Securite, Securite. I have been run down by passing freighter and dismasted. I am not taking on water and am not in need of immediate assistance. I am not in immediate danger."

"Hull is intact. Not yet underway, but hope to be in near future via diesel aux. I do not require assistance at this time."

"I have not yet determined which way to go. Current & wind against me to N/E. Hawaii? I must evaluate distances, currents, wind, fuel consumption, sail options."

That dramatic transmission came from John Oman, skipper of the yacht *Northwest Spirit*, which left Seattle just before Christmas on a single-handed round the world voyage. Oman carried a computer and a satellite link, so he could write of his adventures on a day-to-day basis and post them on the Internet. School students all over the world would then be able to log on and follow the yacht's progress.

Unfortunately, about three weeks into the voyage, it came to a sudden stop when the yacht had its untimely rendezvous with the freighter. But up until then it provided a mighty 'armchair adventure', live as it happened, to students all over the world — courtesy of the Internet.

Does that sound like a valid use of school resources, spending time on the Internet? Well, lots of people are questioning the Internet nowadays, saying it is just a waste of time. The popular term — 'surfing' the Internet — conjures images of frolicking on a warm beach, wandering aimlessly, letting the fun simply wash over you as a passive participant...

A few weeks ago in Seattle an entire half-hour television program was devoted to the uselessness of the Internet, with 'experts' pointing out how Net users, mostly kids, prowl around downloading games and piles of porn and very little else. The thought of schools actually sanctioning such behaviour was shocking!

Yet in a high school where I've been teaching part-time lately, every computer is connected to the Net and students are encouraged to use it whenever they are working on a school project, or whenever they just get curious about something. Several of the machines physically reside in the school library, so students can jump back and forth between real books and the on-line world with maximum convenience.

This is a system I have adopted in my own work, researching articles for *Electronics Australia*. I have Internet access at home, and I live just a few steps from the public library. If I didn't have my own Net hookup, the library has a Power Mac sitting in a room adjacent to the main reading room. This computer provides Internet access for library patrons, in two-hour blocks, free of charge.

Research pre-Internet

In the 'old days', pre-Internet, researching articles was a real drudge. I usually started with a raid on the State Library of Tasmania card catalog, to find any books on the subject in question. Magazines weren't catalogued, so research involved having the librarian get for me bound copies of magazines over many years. Then I settled down at a long table to go through them one by one. This took hours...

Sometimes it was possible to dig up further information from the library at the University of Tasmania. Later on the State Library made things somewhat easier by installing their card catalog on computer and providing a dial-in service so readers could access the computer from home via modem.

To see how the system works nowadays, let's use as an example a recent article I did on electromagnetic fields and their relationship with cancer. I began with a search of the Internet, using one of the marvelous 'search engines' thoughtfully provided free of charge on the Net. Here a little logical thinking is required to produce the goods. I wanted to know about 'electromagnetic fields' AND cancer. The search request asked for names and locations of any documents containing both the term 'electromagnetic fields' and the word 'cancer'.

What came forth was a long list of documents meeting the criteria. I selected a few likely ones based on their titles, and came up with some writings by Dr Louis Slesin, publisher of a newsletter called *Microwave News*. Dr Slesin was warning of the dangers of cancer as a result of electromagnetic fields, or EMF's. 'EMF' was a term I hadn't used previously, so a launched another Internet search for anything with EMF in it. This produced another flood of documents.

Amongst all this material I also found a research paper written by Dr David Hafemeister, debunking the fears of Dr Slesin, backed up with his own warnings about vested interests and sensational journalism. So now, conveniently sitting on the hard drive of my computer, I had material covering both sides of the story about EMF's and cancer.

Not in the library

The *Microwave News* publications sounded like they might be interesting, so I wandered over to the public library and sat down in front of their 'magazine index' computer. A search for *Microwave News* revealed that the library did not carry it, nor did any other libraries within inter-library lending range (this goes right up to Anchorage, Alaska). But the term 'Microwave News' did produce a 'hit' within an article in *Business Week* magazine — a non-technical article about cellular phones and cancer, quoting Dr Slesin and *Microwave News*.

This suggested another search path, cellphones AND cancer, which produced some 'hits' within other magazines such as *Newsweek*.

Soon, after a session on the photo-

copier, I had a nice pile of papers about EMF's and cancer to add to my collection. But I still really wanted to see what *Microwave News* was on about, so I got on the Internet again and e-mailed Dr Slesin, asking if he could help out. A few days later I had three recent issues of *Microwave News*, provided personally by Dr Slesin by snail-mail. Having contacted him, I thought it only fair that I should e-mail Dr Hafemeister as well, telling him what I was up to and asking if I could use his material.

So, thanks almost entirely to the Internet, I was able to launch into a rather difficult magazine writing job armed with heaps of information from both sides of a debate, along with personal messages of good wishes from its main participants.

Just imagine how difficult this would have been, pre-Internet. I would have been up for phone calls and faxes clear across the country, if I even knew who to contact. Dr Slesin and *Microwave News* might have been revealed via the public library search of its magazine files, but I'm sure I would have missed out on Dr Hafemeister completely, and with him the other half of the story.

Search engines

You've probably realized by now that the key to this whole research process is the 'search engine'. That conjures up visions of a big machine with an enormous flywheel, clanking and hissing steam and spewing information out a chute in the front. But as usual, it's just another big computer. Anyone using the Netscape Web Browser can make contact with one of these search engines by clicking on the 'net search' button near the top of the screen. This produces a list of various search engines.

They all do a good job, but my favorite at the moment is a system called Alta Vista run by the Digital Equipment Company, one of the computer giants which has been around since the earliest days. DEC provides Alta Vista mainly to show off the capabilities of its AlphaServer Internet server machine. And a fine demo it is; within the briefest few seconds after being handed the search criteria, a flood of stuff comes spewing out the chute and onto your screen.

The Alta Vista screen gives as an example a search to find a holiday destination: sailing kayaking 'San Juan Islands'. The San Juan Islands are just a few kilometres from here, so I though Alta Vista must be in Seattle, thus explaining its blazing speed. But no, it looks like it is down Silicon Valley way somewhere, in California. It should be pretty easy to access Alta Vista from Australia, since the site is on the west side of the country.

I've been using Alta Vista to dig up everything I can find about desktop video, for the work I've been doing at the local high school. One short session on Alta Vista resulted in 83 pages of useful information, which then had to be printed out for distribution to students. The lady in the school library wasn't very happy with me...

On the other hand...

Well, that's one side of the Internet. What about the other side? Yes, the Net isn't all goodness and innocence. I have had, sitting in my computer, complete and very detailed instructions for making a working atomic bomb (that's providing you can get some plutonium, of course). I know the instructions are accurate, because they tally with information I gained while preparing some articles on Los Alamos a couple of years ago.

On a smaller scale: on the Internet you can find information on how to make your own nitroglycerin, and from it dynamite; and to set it off, homemade blasting caps. Or you can find out about the explosive used to blow up the Federal Building in Oklahoma City. You can blow up cars, make letter bombs, napalm...

Another document I found on the Internet tells how to rip off the VisaNet, the on-line system that lets a shop debit your Visa account in Australia while you wait patiently at a check-out in Europe. I also found information on how to crack into an ATM machine, making it spew out free money.

It's true, all this stuff is available on the Net, and I have seen it personally. There are those who will say this kind of information must be banned and destroyed forthwith. But, is it really a great danger? How many people, even terrorists, have made use of information, gleaned from the Internet, for criminal purposes? Very few, I would say. People who use the information in anger would have had access to it long before the Internet ever came into existence.

Now that this article is written, all that bomb stuff has been purged from my computer, as has all the guff on EMF/cancer, computer upgrades, and all the other writing projects I've been working on. On a given hard disk, you just can't store everything. There's just too much information in the world, and by its very nature most of it is outdated almost immediately. So why save it? Go back to the Net again when you need it...

From my point of view here near Seattle, the Internet research thing has now gone full circle. Sometimes when I'm working on a project, I want to know how much information about it is already available in Australia. So I go back to where I started — the State Library of Tasmania or the University library — via the Internet. Both these facilities can be accessed by Telnet, which produces a screen display exactly like the computer terminals right there in the library itself.


The library catalog and database computer system is called Dynix, and it just happens that both the State Library of Tasmania and the Port Townsend Public Library are using it.

One day I was on the Power Mac at this end, browsing around in the Tasmanian Dynix system via the Net. A librarian came up and said, "Just tell me — how did you get our Dynix system up on that Mac computer? They're not even connected." So I had to tell her, "That's not here, that's TASMANIA!".

"Ooohh!" she said. "Is there really such a place? Are there really Tasmanian Devils? And libraries?" ❖



What's New in VIDEO and AUDIO



7-channel DSP amp includes Dolby AC-3

Yamaha Music Australia has introduced a new seven-channel Digital Sound Field Processor Amplifier incorporating Dolby's latest surround sound home cinema format, AC-3.

The new DSP-A3090 provides the 5.1 channels of AC-3 surround as well as the seven channels of Yamaha's Cinema DSP surround settings for Dolby Pro Logic sources — plus five new modes that combine AC-3 with Yamaha DSP to deliver what is claimed to be the most spectacular home cinema experience possible today.

In order to provide the massive amount of programme memory required to deliver that kind of impact, Yamaha designed and incorporated a sophisticated and powerful new VLSI chip, the YSS-214. This supplies 33% more processing power than those used in the company's previous model, the DSP-A2070.

With 80W each to five channels and 25W apiece to the effects channels, the DSP-A3090 provides more power than either of its predecessors. A built-in test tone generator provides a sequential sweep of the channels to establish proper balance. A subwoofer test tone generator also provides a level for adjusting the subwoofer output so that a listener can match the room and the rest of the system.

Dolby's AC-3 format represents the next logical step in realistic and dramatic home cinema reproduction. AC-3 is the domestic version of Dolby Digital, found in movie theatres. AC-3 encoded Laserdiscs require players and processors specifically designed to handle the new system. At the commencement of 1996, there were more than 40 movies out on Laserdisc in AC-3 format, including such recent hits as *Forrest Gump*, *The Lion King* and *Outbreak*, as well as new AC-3 mixes of classics such as *Doctor Zhivago* and *Guys and Dolls*. AC-3 is also expected to be the system used by the new DVD discs; it has five discrete full-bandwidth channels, plus a sixth subwoofer channel. All '5.1' channels are extracted from a single digital data stream.

Other technical advances incorporated in the DSP-A3090 include newly developed A/D and D/A converters. The A/D processing is handled by a 64x oversampling 20-bit chip, and the D/A conversion achieved by an 8x oversampling 20-bit chip.



The Yamaha DSP-A3090 has a suggested retail price of $3499. For further information circle 143 or contact Yamaha Music Australia on (03) 9699 2388 or 1800 805 413.

VCRs offer time-lapse recording

Sanyo Australia have released two new Time Lapse Video Cassette Recorders, designed for use in the security industry. Both VCRs will connect easily to any CCD camera for use in banks, hotels, casinos, service stations, restaurants, jewellery stores or anywhere cash or valuables need monitoring.



The TLS-924P is capable of up to 24 hours of time lapse recording, with improved field recording and field advance playback that can show every field. With a horizontal resolution of 350 lines (B&W), this four-head unit gives excellent VHS picture quality.

Timer recording can be used on a daily or weekly basis and for ease of use, the timer settings are made and confirmed on the monitor.When an externally connected alarm sensor is triggered, the unit switches to alarm recording in the three-hour mode and commences a complete recording of the event that triggered the alarm. The alarm scan function lets you play back every five seconds of an alarm recording.

A feature of the Sanyo units is that, for added security, the alarm function locks all buttons on the VCR.


The TLS-S2500P has all the attributes of the TLS-924P but comes in a Super VHS format, which has more than 400 lines of resolution in recording and playback, even in time-lapse mode. As well as 2, 12 and 24 hour recording, with the TLS-S2500, it is also possible to record in various multiples of hours, right up to 960 hours (40 days).

For further information circle 142 on the Reader Service Coupon or contact Javelin Electronics which has offices in Sydney, Melbourne, Brisbane and Perth.

'CD Receiver' released by Onkyo

The Onkyo CR-70R CD Receiver is a new-concept model that offers high-quality home entertainment performance and easy operation in the one package. It integrates a powerful amplifier, audiophile quality CD player and high sensitivity tuner into a single compact component.

No larger than a conventional hifi component, the CR-70R delivers a serious 50W per channel into 4Ω loads, with very low distortion. The output stages employ high-grade discrete circuitry rather than the inexpensive 'package ICs' found in many conventional amplifiers.



The CD player section is equipped with Onkyo's Fine Pulse Conversion System (FPCS), with a single-bit D/A converter and eight-times digital oversampling filter to provide an accurate, natural sound.

The FM receiver section includes the Radio Data System (RDS), which enables the receiver to display a variety of information when tuned to an RDS station. It can automatically scan for the strongest stations in a reception area, storing up to 30 stations in three groups for scanning at the touch of a button.

The CR-70R is finished in brushed aluminium, measures 455 x 110 x 330mm and has a weight of 7.8kg. It has an RRP of $1099 and is available from selected dealers.

For further information circle 141 on the Reader Service Coupon or contact Amber Technology, Unit B, 5 Skyline Place, Frenchs Forest 2086; phone (02) 9975-1211 or fax (02) 9975-1368.

New large screen CTVs from Sony

Sony has released two new additions to its Kirara Basso range of rear-projection large screen colour TV receivers.

The new wide screen KPW41 allows the viewer to recreate cinema style viewing in a lounge room setting. It has a 103cm diagonal screen in the 16:9 aspect ratio, giving high impact and involving the viewer in the action.


The KPW41 uses a short focal length lens and is only 39cm deep — as slim as a conventional 34cm CRT receiver. This allows it to be incorporated in virtually any living area. The projection lens is colour calibrated and is claimed to expand the reproducible range of colours by 30%, for more vivid colours (especially reds and greens).

The receiver also features a 100Hz/120Hz double scan system which doubles the scanning rate, making flicker almost undetectable and producing an image which causes less eye fatigue.

The KPW41 receiver will be available through a limited network of Sony retailers, at a suggested RRP of $8999.

The other new receiver is the KPRS53MK2, an enhancement of the previous model KPRS53. The new version features an improved 'thin film Fresnel' screen, designed to improve contrast and increase the black level for more vivid colour reproduction. The new screen is also more resistant to marking and scratching.

The KPRS53MK2 carries a suggested retail price of $13,199.



A/V Receiver offers Dolby Pro Logic

Kenwood Electronics has released the KR-V7070 Pro-Logic surround sound receiver, which features an AM/FM stereo 40 preset tuner, four DSP modes, Dolby Pro-Logic Surround Sound and three-channel surround sound, five channel amplifier and universal remote control — all for a very competitive RRP of $999.



The KR-V7070 supports two hifi VCRs, two audio tape decks, CD player and phono input, making possible dubbing between two VCRs or two cassettes. The front amplifier channels (front left, centre and right) all produce 100 watts while the rear surround channels are driven by a 28W/channel amplifier. To allow creation of a full home theatre environment, a line-level subwoofer output is provided for use with an active subwoofer such as Kenwood's SW-500 system.

The KR-V7070 also incorporates a cooling fan which automatically switches into play when the amplifier gets hot.

Pro-Logic features include wide, normal and phantom centre channel modes, plus rear channel delay adjustable in 5ms steps between 15 and 30ms.

The KR-V7070 is covered by a two year warranty and is available at selected Kenwood dealers. For further information circle 140 on the Reader Service Card or contact Kenwood on (02) 746 1888. ❖

BATTERY BLUES, & NEW TECHNOLOGY

Louis Challis decided to devote this month's column to a review of new battery technology, and initially it was going to be based on information he found at the recent Las Vegas Consumer Electronics Show. However then he had a very embarrassing experience when some nickel-cadmium batteries let him down during a critical recording session — providing a much more practical way to introduce this topic. As most of us are using more batteries than ever, nowadays, it makes very relevant reading...

Two weeks ago, I was invited to produce an archival recording of the Australian Brandenburg Orchestra's 'Archibald Concert' at the Art Gallery of NSW. On the opening night I had been entranced by the 'Musical Portraits from the Baroque' which coincided with the Archibald Prize Exhibition.

Before the audience arrived, I quietly set up two laboratory microphones on stands, supplemented by a new pair of battery operated microphone preamplifier power supplies. I decided to use my Sony PCM 2000 two channel DAT recorder, as it provides exceptional linearity over the frequency range 2Hz to 22kHz. I had already convinced myself that battery power would be preferable to an external mains supply, as that would preclude earth loop problems. I had already charged up three nickel-cadmium batteries (Sony type NP-1As), in the belief that it would only be necessary to change one battery at the interval.

On the basis of my memories of the first concert I attended, I estimated that the typical average sound pressure level would be close to 94dB at the two microphone positions. With clear memories of how loud the trumpet had been on the first night, I felt that I would need at least 16dB of 'headroom' to accommodate the trumpeter's peaks. Accordingly, I adjusted the OdB peak recording level to conform to a level of 118dB, and patiently waited for the concert to start.

Now the concert was truly outstanding. The acoustical characteristics of the gallery were equally outstanding, and I was gratified to find that the average peak levels during the first half of the concert were 2dB less than I had estimated. Everything appeared to be conforming to plan and with the rest of the audience, I was quietly enjoying the performance.

The interval came and went, and a few minutes into the second half of the concert, I watched in utter disbelief as the low battery warning signal suddenly appeared on the DAT's LCD display. Before I even had time to respond, the recorder had stopped DEAD!

With my heart in my mouth, I quickly changed the battery. But at least 40 seconds of critical recording was lost, and



In the USA, Toshiba has released this 10-hour charger to suit its new AA size nickel-metal hydride batteries. With an internal microcontroller, the charger plugs straight into a wall socket.

my 'archival tape recording' had suffered an embarrassing and irretrievable loss of material.

As the concert continued I sat there with a red face. I too had been caught out by one of the nasty scourges of modern electronics. Yes, I was smarting from a severe case of what I call the 'battery blues'.

As it happens, planning for this article was well in advance at that time. But I had planned an entirely different start, intending to describe the Energiser PR release at the recent Winter CES in Las Vegas. But heck! — *they* didn't even answer my last two faxes, so I'll ignore the new Energiser batteries and their battery packs and look instead at the firms who are prepared to do something constructive, in solving battery problems.

Batteries crucial

Virtually everybody I know now uses one or more forms of batteries on a day by day basis. But most users give scant thought to what they are, how they work or the crucial nature of their functionality and performance.

The batteries most commonly found in your house are likely to be zinc-carbon batteries. They are slowly, but systematically, being replaced by manganese-alkaline batteries in torches, toys and in remote controls for TV sets, VCRs and hi-fi's. Both of those batteries are described as 'primary batteries', because they are not rechargeable. Rechargeable batteries are in contrast described as 'secondary batteries', the most common examples of which have long been nickel-cadmium batteries.

Now nickel-cadmium (NiCad) batteries were originally developed as traction batteries, more than 50 years ago. During the latter part of this century they became the preferred secondary battery for most portable electronic applications. NiCad batteries have some very pertinent attributes, the most significant of which is their ability to provide high discharge current capacity, coupled with a relatively constant output supply voltage.

Now in most applications, NiCad cells hold an almost constant voltage throughout most of the discharge period. As a result, they are used in such diverse applications as portable electric drills of the kind commonly used on building sites, as well as for powering most portable music systems.

A well made nickel-cadmium battery has low internal resistance, and is thus well suited to high current or pulse current discharges. Under controlled conditions they are also capable of being recharged at high rates, and they are designed to operate over a very wide temperature range. They can be overcharged at recommended rates, but only under tightly controlled conditions.

The one design aspect that many manufacturers fail to warn you about is their **memory effect**. If a nickel-cadmium battery is recharged from a partially discharged condition, the battery may 'remember' the last discharge level and will then only accept part of the intended charge. On discharge, such a recalcitrant nickel-cadmium battery will only deliver a reduced charge, as the recharging process leads to electrode crystallisation in the charged cell. When that happens the battery is incapable of accumulating a full charge.

Some manufacturers recommend that any such batteries should be deeply discharged and then recharged, a number of times. Now that may work well with some batteries — but as I have discovered, not with all.

Some models, or more pointedly, some *brands* of nickel-cadmium batteries seem to be less prone to problems than others. Frankly, I have now formed the view that some manufacturers of these batteries (in particular Matsushita in Japan) have spent more time and effort in resolving this problem than many of their competitors. Based on my observations, Matsushita's NiCad designs are less prone to memory effects, as a result of what appears to be superior manufacturing technology.

New technologies

Over the last decade, the major consumer electronics firms in the USA, Europe and Japan have directed their research teams to the development of new and superior batteries. Their goal has been development of secondary batteries with higher energy density, lower weight, and where possible, flat profiles so that they would be suitable for computers. They have also aimed to achieve minimal (or no) risk of causing explosions, and a positive freedom from any trace of 'memory effect'.



Wisconsin-based Rayovac is marketing its new 'Renewal' rechargeable alkaline cells. The matching recharger uses a special IC developed by Benchmarq, which uses a pulse charging technique.

Now that composite quest may sound a trifle optimistic, but as you read on you will find that there have been some outstanding developments. If you're not already aware of these, it's probably high time you were.

But before examining those developments, it is appropriate that we examine some of the basics on which the new battery technology has been based.

Manganese-alkalines

Manganese-alkaline or 'alkaline' batteries are currently one of the most attractive sources of energy for portable equipment. They offer about three times the energy density of nickel-cadmium batteries, but as normally constructed

are useable once only.

Alkaline batteries use a cylindrical depolariser, in contact with a cell container of nickel plated steel. Because of the passivity of the steel, when used in an alkaline electrolyte, there is no chemical reaction between the depolariser and the steel. The depolariser surrounds a cylindrical, granular zinc anode, with the two electrochemical components separated by a porous material.

Now the polarity of this cell is reversed from that of a conventional zinc-carbon cell. However, because of the way in which manganese alkaline cells are packaged, the external appearance is the same and the terminal configuration is the same as a conventional zinc-carbon cell.

Manganese-alkaline cells have become the preferred primary batteries for many portable applications because they just keep on going, and going and going. In fact, unlike the zinc-carbon cell which provides most of its output at voltages above 1.2 volts, the manganese-alkaline battery provides a significant proportion of its output for voltages lying between 0.9 and 1.1 volts.

Now it has long been realised that by modifying the structure and details of the porous separator and modifying the quantity and format of the electrolyte used, that a manganese-alkaline battery could be recharged. Not any manganese-alkaline battery mind you; only those which have been specially designed and constructed to cope with the rigours of a recharging process. However, without an appropriate charger, the recharging operation was potentially dicey — very dicey.

Now at least two manufacturers have released rechargeable manganese-alkaline batteries. The first is the Rayovac Corporation of Madison, Wisconsin, who are marketing the 'Renewal' brand in the USA. The second is the 'Pure Energy' Company in Canada. Both manufacturers claim that their batteries are rechargeable at least 25 times from the fully discharged state, or more than 100 times if recharged after each partial discharge.

A fundamental requirement for both manufacturers' products is their provision of a special recharger, which is purchased separately. Both firms market rechargers incorporating a purpose-designed 'Rechargeable Alkaline Charger Integrated Circuit'. The recharger ICs used by Rayovac were developed by the Benchmarq Corporation and employ a pulsed charging technology. The special ICs incorporate selectable 'end-of-discharge' voltage detection, which prevents over discharge and extends the cycle life. The ICs also provide pre-charge qualification to identify fault conditions and provide dedicated outputs to individual LEDs, which indicate charge status of each of the four cells in the charger.

Now rechargeable manganese-alkaline batteries cost approximately 50% more than the normal primary variety. The chargers, which sell for around $14, plug straight into a power point and accept 1 - 4 batteries at the same time. Whilst a conventional premium AA size manganese-alkaline battery provide a 2300mA/hour charge capacity, the rechargeable version only provide 1400mA/hour capacity.

As the number of recharges increases, this initial capacity is further degraded. After 25 full discharges, the typical capacity drops further to around 600mA/hour, which is on a par with most NiCad batteries.

The most positive attribute of the rechargeable manganese-alkaline battery is that its charge retention is excellent, as it loses less than 20% of its charge after one year's storage. By contrast, a NiCad battery would be 'dead' in less than half that time.

Parameter	Test Conditions	Results
Short Circuit	Short Circuit at 20°C	Cell temperature reached 120°C. No fire, no explosion.
Repetitive Over-Charge & forced discharge	Repeated 150% overcharge and overcharge	Cell failed by first over discharge. No fire. No explosion.
High temperature Storage	Storage at 75°C for 48 hours	No leakage. No explosion. No abnormal weight loss.
Overheating	Conducted at 200°C on hot plate.	Venting, releasing of electrolyte & gas above 140°C. No flame and no explosion under 200°C.
Vibration	0.15mm amplitude. Swept from 10-55 Hz over swept @ speed of 1Hz/minute.	No leakage. No explosion. Cell voltages remained stable.
Mechanical Shock	Average acceleration 75 G. Peak acceleration 125-175 G.	No leakage. No explosion. No damage in cell.
Crush Test	4,000 kg. force between steel plates covered with plastic using hydraulic press	Cell temperature increased to 100°C. Leakage of electrolyte, but no fire
Penetration Test	Sharp metal spike of 4mm diameter & 35 mm long	Cell temperature increased to 95°C. Leakage of electrolyte. No fire.

Table 1: An extract of key information on Sony's US-61 rechargeable lithium-ion cells. Both Sony and Toshiba have received exemptions from dangerous goods transport regulations, for their lithium-ion cells.

Nickel-metal hydrides

Whilst major American and Canadian battery manufacturers are busy developing rechargeable manganese-alkaline batteries, other manufacturers have been more interested in researching alternative battery technology. The market now demands batteries that can be recharged 300 times and preferably more, without displaying memory problems.

One of the more interesting recent developments is the nickel-metal hydride (NiMH) battery. Initially developed for handicams (handheld video cameras), they soon started replacing NiCad batteries in mobile telephones, as they offered an energy density 50% better than NiCad batteries.

With nominally the same output of 1.2 volts, reasonable compatibility with existing NiCad chargers, a life in excess of 500 recharges and only minimal memory effects, NiMH batteries have revitalised the mobile telephone replacement battery market. The most significant limitation that they exhibit is a relatively rapid self-discharge characteristic, losing approximately half charge in less than a month. They also cost more than NiCad batteries although their selling prices are currently dropping.

Still, when their performance and user-friendly characteristics are compared with those of NiCad batteries, few users would be willing to accept a NiCad in their place. Conventional sized NiMH batteries (AA, C and D) are now being trial marketed by Toshiba in the USA. They are being sold in combination with intelligent microprocessor-based chargers that plug straight into the wall outlets and safely (slowly) recharge a set of batteries in approximately 10 hours.

Whilst I have enjoyed the advantages of NiMH batteries in my cellular telephone for more than two years, I was not oblivious of other exciting research which has aimed at developing superior and safer batteries. Why *safer*, you asked? Well if you accidentally short circuit the terminals of a NiMH battery, the results could range from rather disturbing, to extremely dangerous — so BEWARE!

Lithium-ion batteries

But the most exciting, new and practical battery developments are the lithium-ion batteries, initially developed by Sony.

Sony Energytec, Inc started its research more than 10 years ago, and offered us some pre-production samples around six years ago. I believed their initial PR releases, concerning the imminent availability of their product, and foolishly specified lithium-ion batteries for a new portable vibration monitor which we were then designing. Alas, they couldn't deliver and I found myself in a very embarrassing situation. Six years were to pass before I saw the first Sony 'lithium-ion powered' consumer equipment.

Now there were numerous tricky issues to be resolved during the design and development of the lithium-ion battery. One of the most important considerations was the environmental concern.

When a battery no longer holds its charge, it has to be replaced. Other rechargeable batteries containing lead, mercury or cadmium proved to be extremely toxic. They posed serious and very real dangers to our environment, if not disposed of correctly. If thoughtlessly dumped in land fill, they can lead to rapid toxic contamination of ground water, which would ultimately pollute our water supplies. Even the newer NiMH batteries pose significant dangers in this regard.

As my research revealed, there are two different types of lithium-ion batteries now available. The first was the battery developed by Sony, which uses an anode of lithium-cobalt oxide whilst a carbon based structure is used for the cathode. In contrast Toshiba's lithium-ion battery uses a slightly different lithium oxide design for the anode, but maintains a similar carbon-based structure for the cathode (the negative electrode).

Both manufacturers' batteries interpose an organic liquid electrolyte which contains lithium ions. Sony apparently uses a lithium fluoride, dissolved in propylene carbonate for its electrolyte. Both the electrolyte and the electrodes are thin and extremely light. As a result, lithium-ion batteries are considerably lighter than conventional NiCad or NiMH batteries. This is a critical attribute, as it ensures that they are the preferred batteries in any new application which calls for either low weight or for a dramatic reduction in weight.

Whilst NiCad and NiMH batteries have a 1.2 volt nominal potential per cell, the open circuit voltage of a lithium-ion battery is nominally 3.6V, or as high as 4.1V immediately after recharging. With a terminal voltage as high as that, many simple applications require only 1 or 2 cells. If 12V is nominally required, then four cells would be used.

The energy density of a lithium-ion battery is about twice that of a comparably sized NiCad battery, and is only 12 to 15% less than that of a premium manganese-alkaline battery. With a capacity as high as that, portable laptop computers weighing less than 2kg and miniature video or audio recorders with long life rechargeable batteries become a practical reality. More significantly, with no adverse memory effect and with the promise of up to 1000 life cycles, the initial higher cost is no longer as daunting to either the designer or the purchaser.

Lithium-ion batteries have other more critical attributes, when compared with their competitors. The issue that has captured the imagination, hearts and minds of the powers that be in the USA is the **safety issue**.

Table 1 shows an extract of information on Sony's US-61 lithium-ion rechargeable cells. It appears that Toshiba's newly developed lithium-ion cells, although slightly different, are equally safe. Both manufacturers have confirmed that the US Department of Transport has issued a formal exemption from the dangerous materials regulation affecting the use of lithium-ion batteries in the transportation area (i.e., on aircraft, ships and trains). That exemption was followed by a similar ruling of the International Air Transport Association (IATA), that the lithium-ion batteries would not be classified as dangerous goods.

Whilst Sony, Toshiba, Duracell and Varta are all producing lithium-ion batteries, their use is still currently restricted to new equipment for whose use they have been purpose-designed. However Sony Energytec is about to release a range of single cells which will cater for

(Continued on page 35)

	NOMINAL VOLTAGE	PEAK POWER	RE-CHARGE CYCLES	SELF DIS-CHARGE	CAPACITY (AA SIZE) mAh	ENERGY WH/Kg	DENSITY WH/L
Nickel Cadmium	1.2	High	>200	1%/day	800	55	130
Lead-Acid	2.0	Moderate	200	Moderate	N/A	35	90
Nickel Metal-Hydride	1.2	Moderate	500	4%/day	1,150	70	175
Lithium Ion (C-Li or Lix CoO_2)	3.6	Low-moderate	>1000	Moderate not stated	380	115	250
Alkaline (Zinc-MNO_2)	1.5	Low-moderate	N/A	0.01%/day	2,300	130	300
Rechargeable manganese alkaline	1.5	Low-moderate	>25	0.01%/day	1400	80	220

Comparing power packages

One way of comparing old and new battery technology is on the basis of their energy densities, on the basis of either weight (watt-hours per kg) or volume (watt-hours per litre).As all of these batteries are currently available in AA size, the accompanying chart compares their energy capacities — i.e., how long a given current can be generated before the cell is effectively dead. This is expressed in milliampere-hours (mAh). Nominal voltages are also listed for the five rechargeable (secondary) batteries and for one primary (single use) battery.

NEW MODEL 4.5 SYSTEM FROM SONIQUE

South Australian loudspeaker designer and manufacturer Sonique Audio generated a lot of international interest at this year's Consumer Electronics Show in Las Vegas, with the release of a completely new range of high quality but competitively priced speaker systems. Here we look at the new model 4.5 system, which offers very impressive sonic performance from a pair of compact and elegant enclosures.

There really must be something about South Australia that encourages the design and manufacture of high quality loudspeakers, because so much of the country's loudspeaker industry seems to be concentrated there. Perhaps it's the air, or the wine — or just the way an industry can spontaneously take root in a particular area, once a few pioneering firms break the ground.

Anyway, one of the South Australian firms that seems to be achieving good things in this market is Sonique Audio, which was set up in early 1994 by former Duntech executives Greg Walden and Steve Lund. Mr Walden manages the design and QC aspects, while Mr Lund handles the manufacturing and marketing. Together they've already made Sonique a 'high quality' marque, with an international reputation for excellent cabinet finish, impressive acoustic performance and competitive pricing.

At the recent CES in Las Vegas, for example, there was apparently a lot of interest in their new range from both distributors and retailers, both within the USA and from countries in Europe and Asia. A good example of the new range of Sonique systems is the Model ***4.5***, a compact two-way monitor style system which is the second smallest in the overall range, and the smallest of Sonique's systems to employ the well-proven D'Appolito symmetrical driver configuration with a woofer above and below the tweeter.


Each of the two ***4.5*** enclosures measures a compact 412 x 172 x 257mm (H x W x D), and is very solidly made from 18mm thick MDF veneered in Australian Jarrah — which is then finished with three coats of lacquer, to give a very high quality furniture finish. The front baffle is finished in a contrasting matt black, and has a very nicely finished and elegant removeable grille.


The ***4.5*** enclosures are two-way bass reflex systems, with the port at the rear along with the name plate (engraved brass) and the dual input terminals (for bi-amp connections). The latter are gold plated and of the 'three way' type, with gold-plated shorting links for use when the speakers are driven from a single amplifier. Unclipping the front grille reveals a pair of matched 110mm bass drivers, mounted symmetrically above and below a 25mm dome tweeter.

The drivers are from Danish manufacturer Vifa, and the bass unit has a mineral filled polycone material with a high damping rubber roll surround and a vented voice coil. The driver has a magnesium alloy basket, a 240g magnet and an effective cone area of 124cm^2.

The tweeter is of the double-cham-







Above is the response above 500Hz, measured at 1m on the tweeter axis using our IMP system, and already very close to the specification. At right is the electrical impedance plot, again within spec.

Our evaluation

Sonique Audio very kindly sent a sample ***4.5*** system to us for evaluation, and left it with us for a couple of months so we could not only carry out some basic measurements, but also listen to the system at length to get a good 'feel' for its performance with familiar programme material.

First up Rob Evans ran the instruments over the system. Our IMP system was used to get a good idea of the response above 500Hz, and although our testing room makes measurements at a distance of 3m impractical, the response at 1m on the tweeter axis was already within the rated +/-3dB — suggesting that at the rated 3m (which is also much closer to the typical listening distance), it would be even better. Sonique's own curve, measured at 3m with MLSSA, suggests a typical response of within +/-1.6dB up to about 18kHz, and our measurement seems quite consistent with that.

We also measured the electrical impedance characteristic using LMS. This showed a well-controlled impedance with an average figure of very close to the rated 6Ω, and also confirmed the rated minimum of 4Ω. So there's no doubt that the ***4.5*** system should mate happily with just about any amplifier...

With these basic tests done, I took the system home and gave it an extended 'subjective evaluation', extending over some weeks. This gave me the opportunity to spend quite a few hours listening to familiar tracks on many CDs, including a few that I've found good at exploring particular aspects of loudspeaker system performance. I had the Sonique ***4.5*** enclosures about 400mm from the far wall, by the way, and listened at a distance of about 2.5m.

To summarise my impressions, I found the system's performance very clean and well balanced. The bass is quite strong down to below 50Hz, but at the same time not unduly prominent. The crossover region seems very smooth, with my ears able to detect no audible artefacts. And the high end seems very clean and transparent, even on orchestral and choral music. The stereo imaging is also exceptionally stable and well defined.

In short, although very compact and quite reasonably priced, the new Sonique ***4.5*** system gives the sort of performance you'd normally expect from a somewhat larger and more expensive system. This plus the very high build quality should ensure that the ***4.5*** is not only very popular with 'space conscious' music lovers, but also further enhances the Sonique reputation. ❖

---

ber type and has a coated silk and fabric diaphragm, with ferrofluid damping and a specially contoured 'linear response' front plate.

As with other models in the Sonique range, the drivers of the ***4.5*** system are accurately time aligned (within 8us), and the tweeter is surrounded by an inset panel of acoustic felt with a bevel edged star-shaped cutout to minimise diffraction effects.

Inside, first-order equalisation and crossover circuitry is used to ensure the smoothest and most linear operation. The crossover frequency in the ***4.5*** system is 3200Hz, well below the upper limit of the bass drivers, and Sonique stress that only high quality components are used in the crossover networks — polypropylene capacitors, air-cored inductors and ceramic cased resistors with high power rating for stable performance. The internal wiring is made using special high-purity copper cable with over 400 strands and acoustically inert insulation, and the soldered joints are made using special silver alloy solder for minimum resistance with maximum long-term reliability.

The twin-driver bass reflex system used in the ***4.5*** has been computer modelled to give a smooth and extended bass response. (The rear port will of course assist in this regard, when judiciously spaced with respect to the rear wall.) Internal enclosure damping is achieved using carefully selected and positioned acoustic felt, together with CFC-free polyurethane foam.

The nett result of Sonique's attention to detail in both design and manufacture is a very attractive compact system, with equally impressive specifications. Rated frequency response for the ***4.5*** system (measured at 3m on the tweeter axis) is from 50Hz to 20kHz +/-3dB, with a sensitivity of 88dB (1W/1m/8Ω) and a THD (total harmonic distortion) of less than 0.9% measured at a level of 1W. The nominal electrical impedance is 6Ω, with a minimum of 4Ω, and the recommended minimum drive power is 30W RMS — which should make the ***4.5*** system compatible with a very wide range of amplifiers.

In short, the specs are very impressive for a compact system carrying an Australian RRP of $1495. (This price doesn't include the optional matching floor stands shown in the photo, however). By the way, like the other models in the Sonique range the ***4.5*** carries a one year warranty, with a guaranteed option to upgrade to three years.

For more information on Sonique Audio systems, contact the company at 14 Kindale Court, Pooraka SA 5095; phone (08) 262 7911, or fax (08) 262 1189. (J.R.) ❖

Hands-on Review of the

APPLE NIGHTEYES NIGHT VISION SCOPE

The Apple Nighteyes, recently released by Dick Smith Electronics, is perhaps the first professional night vision imaging system made available to the Australian public. Taking advantage of 'starlight technology', this compact device has many applications, including bird and wildlife watching, security, astronomy, etc. Manufactured in Russia by Zenit, who are renowned for their high quality photographic lenses, the Nighteyes ranks as an instrument of superior quality and construction.

by GRAHAM CATTLEY

Go outside on a dark and moonless night, and you'll soon see the benefits of being able to see in the dark. The use of a torch to find your way around is all very well, but the bright light tends to dazzle you and scare off any wildlife or nefarious humans....

The Nighteyes night vision scope changes all that with its ability to amplify light by a factor of over 10,000. Most night vision scopes with this sort of sensitivity employ what is known as 'starlight technology', and can often detect objects with light intensities of as little as 0.001 lux. Compare this with direct sunlight, at over 100,000 lux, and you can appreciate the sort of light levels that we are talking about.

(The SI unit of light intensity is the lux, which is equal to one lumen per square metre, and a lumen is equal to the intensity of one candela at one metre...)

Compact, but solid

Measuring a slim 225 x 95 x 80mm, the Apple Nighteyes looks very much like a small camcorder, and the first thing you notice about it is its weight. At a tad over 1.3kg, the Nighteyes has the reassuring heft of a high quality optical instrument.

About a third of this weight is in the 100mm f/1.5 lens mounted on the front of the unit, giving a narrow angular field of view of a quoted 9.7°, and a magnification of 3.8 times. The lens has the usual aperture and focus adjustments, while an adjustable +/-4 dioptre eyepiece allows you to focus clearly on the displayed image.

Easily held with one hand, the Nighteyes' outer case has only one control — the power switch — and is contoured to fit either hand, making it very easy to pick up and use. The unit is supplied in a handy padded nylon carry case, and comes complete with a clip-on IR illuminator, lens caps and even batteries.

See in the dark!


Using the Nighteyes is as simple as picking it up and pressing the small rubber on/off switch conveniently positioned next to the eyepiece. One important note that is mentioned in the Nighteyes' instruction booklet is that the device can be damaged if operated in daylight, as the image intensifier tube can be overloaded if exposed in even a normally lighted room. It is for this reason that a slightly modified lens cap is supplied by Dick Smith Electronics.

This cap has a small 3mm hole drilled in the centre of it, and it can be used to restrict the amount of light entering the scope. With this cap in place, it is possible to run the Nighteyes in normal room lighting without fear of damaging anything. In the dark, however, the cap can be removed, allowing you to 'turn night into day'.

Looking through the eyepiece reveals the world in a somewhat eerie green glow, due to the type of phosphor used in the imaging tube itself — human eyes are most sensitive to light in the green part of the spectrum, so a phosphor of this colour is most suited to this type of application.

Using the Nighteyes to look around a darkened room, I found that I could see quite clearly, although the lens supplied was only designed to focus to a minimum of about three metres away. As the Nighteyes accepts standard camera lenses, the existing lens assembly could easily be replaced if there were a need for any close work.


After a while of looking around through the scope, I found that although I could see objects clearly through the Nighteyes, my own eyes had adapted to the low light level in the room and I could see everything almost as well without using the device. Obviously the Nighteyes was designed for use in darker places than could be obtained in the somewhat urban environment I was in.



This diagram shows the internal components of a night viewer.

Borrowing the Nighteyes for a weekend, I decided to take it with me to a relative's house down on the south coast. This was a good place to try it out, because at night the area gets *really* dark. Being so far away from city lights meant that the only light around was that from the new Moon and the usual sea of stars.

This was obviously the ideal environ-



ment for the Nighteyes. When I tried it outside that night, I found that the vague shadowy forms of shrubs and trees sprang into life, giving me a whole new world to explore. (In green.)

Venturing out a bit further, I discovered that the main advantage of using the Nighteyes to navigate — over using a torch to light the way — was that my eyes remained dark-adapted and it was practical to change from the Nighteyes to unassisted normal vision in the brighter areas. A slight problem here was that I couldn't use the Nighteyes while walking around, due to its narrow field of view; a little like using a pair of binoculars. This could, of course, be remedied by substituting a standard wide angle lens.

One interesting thing about using Nighteyes was that while pressing the on/off button caused the imaging tube viewing screen to light up as expected, releasing the button didn't seem to turn it off. It seems that pressing the button starts a DC-DC voltage converter, charging a high voltage capacitor within the viewer itself. This in turn powers the imaging tube, which requires approximately 15kV at only a few microamps.

As the tube draws so little current, the stored charge in the capacitor is enough to run the viewer for a good two minutes or so, adding to the expected life of the two penlight batteries that power the device. The user manual quotes a battery life of around eight hours for continuous use, but if you only use the on button to top up the storage capacitor every now and then, you can expect a much longer battery life from the Nighteyes.

How does it work?

All night vision scopes — including the Nighteyes — work on the principle of light amplification. This is usually performed by focusing the weak image to be amplified onto the photocathode on the 'front end' of the image intensifying tube. This end is a thin glass plate, coated on the inside with a chemical film that emits electrons in response to photons hitting it.

Using a high voltage electric field, these electrons are accelerated through a bundle of thousands of parallel microscopic glass tubes, known as a *microchannel plate*, which extends from the cathode to the anode within the tube. Presumably there is a small quantity of a suitable gas in the tubes of the microchannel plate, to allow an avalanching action and consequent electron multiplication.

The end result is that when a resulting larger number of electrons emerge from the ends of each tube to bombard the phosphor coated anode, they produce a pixelated and much brighter view of the original image.

IR illuminator

Of course no night vision imaging system can operate if there is *no* light to amplify, and the Nighteyes is no exception. As the ambient light level falls, so the definition of the imaging tube falls, with the result that the picture gets darker and fuzzier.

Using the Nighteyes in almost total darkness (a closed off windowless room, with the only light entering through a crack under the door), I found that I could make out only the larger more reflective objects in the room, while everything else tended to get lost in the murk. It is in this sort of situation that the semiconductor diode IR illuminator (supplied with the Nighteyes and loosely called a 'laser illuminator') comes in very handy indeed.

Fitting into a standard sized flash shoe on the side of the Nighteyes, the illuminator unit measures only 20 x 80 x 60mm and draws its power directly from the viewer. Powered only when the Nighteyes is switched on, it produces a broad and bright infrared beam that lights up the scene in front of the viewer, giving more than adequate light for clear vision, even in total visual darkness.

Not that you can see the IR light that's produced with the naked eye, of course, as it is too low in the electromagnetic spectrum for human eyes to detect. All that is visible is a dull red glow from the end of the illuminator.

Conclusion

The Apple Nighteyes certainly rates as a professional night vision imaging system, and its quoted retail price of $999 would seem to indicate that the system is aimed more at the professional market, rather than home use. Obviously if you have a need for such a device, you can't go past it in terms of quality, performance and presentation.

Available only from Dick Smith Electronics, the Apple Nighteyes retails for $999 including IR illuminator, and comes with a 12 month full replacement warranty. ❖

NEW BOOKS



Cyberspace re-examined

SILICON SNAKE OIL: Second Thoughts on the Information Highway, by Clifford Stoll. Published by Pan Books (Macmillan), 1996. Soft covers, 198 x 131mm, 247 pages. ISBN 0-330-34442-0. RRP $16.95.

The Internet and World Wide Web are now flavour of the decade, with just about every newspaper and magazine constantly running features on how to 'surf' them. Everyone and their dog is being encouraged to go 'on line', or risk being left behind. But what's the *reality* behind this barrage of hype? Is there no down side to the Net? Do you have to either accept it all without criticism, or eschew it totally and join the neo-Luddite basket weavers? These are the ideas that Cliff Stoll seeks to explore in this very timely new book.

Stoll is an astronomer at the University of Berkeley in California, and like many people in science and engineering he's been using computers and the Net for many years — so he's no Luddite. However he does have serious reservations about some of the less attractive aspects of the multimedia era. Like the way our kids are coming to regard conventional books as 'boring', because they don't provide an 'all singing, all dancing' interactive audiovisual presentation. Or the way people are coming to regard the Net as the fount of all knowledge worth having, when so much of what's there is really very superficial and little more than 'CB via modems'. Or the way our schools and libraries are having to use more and more of their budgets to buy computers and on-line access time, to the detriment of their core activities.

In short, he's become what he describes as 'deeply ambivalent' about many of these developments, and has written this book in an effort to get people thinking seriously about the potential problems.

I found it both absorbing and thought provoking. Mr Stoll writes in a friendly, accessible way, too. I can warmly recommend it, if you're at all interested in considering just where the information highway may be leading us. (J.R.)

Digital primer

DIGITAL CIRCUITS: An Advanced Primer, by P.J. Lesniewski and Dr L.C. Jain. Published by BPB Publications, 1993. Soft cover, 180 x 232mm, 218 pages. ISBN 81-7029-416-9. RRP $22.95.

This is another in the range of low cost books from New Delhi publisher BPB Publications. But unlike previous books I've reviewed from this publisher, the authors are locals, from the University of South Australia.

First up, it's not a book for beginners as, according to the back cover, it has no 'standard fundamental material'. It is described as avoiding excessive repetition and over simplification. The writing style and presentation is clearly aimed at those studying an undergraduate course in Electronics Engineering.

Despite this, its contents appear to be typical of those of a general digital textbook. There are nine chapters in all, beginning with number systems and ending up with memory ICs, A/D and D/A converters. But the text of many chapters is very brief, compressing a lot of concepts into a very small number of pages — often as few as ten.

The main feature of the book is the copious IC data, but its brevity and lack of fundamentals will probably make it unsuitable as a general digital textbook. Certainly it will be useful as a low cost reference, and it presumably suits courses run at the Uni of South Australia.

The review copy came from Jaycar Electronics, and is available from Jaycar stores as Cat. No. BM2491. (P.P.)

SPICE models

SPICE: PRACTICAL DEVICE MODELLING, by Ron Kielkowski. McGraw-Hill Books, 1995. Hard covers, 237 x 158mm, 260 pages, with 3.5" floppy disk. ISBN 0-07-911524-1. RRP $140 (NZ$181.95).


Murphy's law seems to ensure that you don't have the correct model for some key device or component used in the circuit you want to simulate. Some simulators, like Intusoft's IsSpice, come with a set of utilities to help you come up with models for components not in their libraries, using manufacturer's data sheets. There have also been quite a few books on the subject, although most have been so laced with device theory and maths that they've been of use mainly to those with a PhD in solid state physics. This book is designed to be of more practical help to the rest of us...


Mr Kielkowski has already produced one very helpful book on simulation, *Inside SPICE: Overcoming the Obstacles of Circuit Simulation*, which I reviewed in our February 1995 issue. This new book certainly seems to continue in the same down-to-earth vein, with the emphasis on developing *practical* component models quickly.

After an initial and very helpful introductory chapter, there are chapters on modelling passive components, diodes and zeners, bipolar transistors, JFETs and power MOSFETs. A set of data appendices explain how to use a collection of modelling utilities provided on an accompanying floppy disk, which also contains RSPICE (a PC-based version of SPICE 2G.6) and RGRAPH (a matching graphical post-processor).

Like Mr Kielkowski's previous book, I can recommend it to anyone who needs to use simulation 'in anger'.

The review copy came from McGraw-Hill Australia, of PO Box 239, Roseville 2069. (J.R.) ❖








Win an Apple Nighteyes hi-tech night viewer valued at $999!

As a special offer to *Electronics Australia* readers, and to promote interest in the Apple Nighteyes night viewer, Dick Smith Electronics has generously provided us with a unit — worth $999 — to give away as a prize. So here's YOUR chance to win one of these fascinating high tech devices!

All you have to do is demonstrate your understanding of the way a night viewer device works, by adding the missing words in the brief explanation given below, in the entry coupon. Then add your name and address, and send in the coupon (or a facsimile/photocopy of it) to reach the *EA* office by June 28, 1996.

During the first week of July, we'll check all eligible entries and decide the neatest correct entry. The entrant responsible will then receive the Apple Nighteyes viewer — it's that simple!

Send your entry to the Electronics Australia/Dick Smith Electronics 'Win an Apple Nighteyes Night Viewer Competition', PO Box 199, Alexandria 2015, or if you prefer fax it to (02) 353 0613.



The Apple Nighteyes viewer: very compact, it can amplify the light from a scene by up to 10,000 times — allowing clear vision in almost complete darkness!

ELECTRONICS AUSTRALIA/DICK SMITH ELECTRONICS 'WIN AN APPLE NIGHTEYES' NIGHT VIEWER COMPETITION

ENTRY FORM:

Name: .....

Address: .....

..... Postcode: .....

Night viewers like the Apple Nighteyes work by focussing the light ..... from the scene being viewed onto a photocathode, to produce ..... These are then amplified, and used to excite the molecules of a ..... screen, to produce a much brighter light image.

This competition is only open to Australian residents. Entries received after the closing date will not be included. Employees of the Hannan Group or Dick Smith Electronics, their subsidiaries and families are not eligible to enter. Prizes are not transferable or exchangeable, and may not be converted into cash. The judges' decision is final, and no correspondence will be entered into. Description of the competition forms a part of the competition. The competition commences on 29.5.96 and closes last mail 28.6.96. The judging will take place in Sydney on 3.7.96 at 11am and the winner will be notified by mail and also announced in a later edition of Electronics Australia. The prize is an Apple Nighteyes night viewer valued at $999. Total prize value $999.

David Packard: September 7, 1912 — March 26, 1996

THE END OF AN ERA FOR SILICON VALLEY

David Packard's death in late March was mourned not only by his many friends and colleagues in the giant test instrument and computer company he began with Bill Hewlett 57 years ago, but also by a huge number of people in California's Silicon Valley. That's because in many ways, Packard and Hewlett were co-founders of the high tech Valley itself — and either trained, encouraged or bankrolled many of today's entrepreneurs. Mr Packard was also a philanthropist, and his generosity has by no means ended with his own passing...

by MARK HARRIS

On March 26 this year, Silicon Valley lost its founder and most successful high-tech business leader, as David Packard passed away at the Stanford Medical Center. He went at the age of 83, surrounded by his family, after a 10-day bout with pneumonia.

Packard, along with his best friend Bill Hewlett, started Hewlett-Packard in a small Palo Alto garage with a $530 loan. Their first success came in 1939, when Walt Disney purchased eight audio oscillators for $71.50 each for the production of his cartoon film *Fantasia*. Since then, H-P has grown into a US$31 billion conglomerate with more than 105,000 employees in 180 countries, and a brand name recognition synonymous with quality.

Just as one measure of Packard's immense impact on American industry, a 1989 national survey of chief executives rated Packard the nation's most admired living business figure.

During much of his career and throughout his retirement years, Packard became an icon for charity, donating hundreds of millions of dollars to worthy causes ranging from a $180 million donation for the construction of the Monterey Bay Aquarium and nearby oceanographic endeavours operated by his two marine biologist daughters, to the $70 million he gave to the Lucile Salter Packard Children's Hospital at Stanford.

Over the years he and Bill Hewlett have together also given more than $300 million to Stanford University.

Upon his death, his entire US$6.6 billion fortune has been donated to the Lucile & David Packard Foundation, the philanthropic organisation that manages his charitable activities. That will make the foundation, already the 11th largest US charitable organisation, the third largest behind the Ford Foundation (valued at $7.4 billion) and the W.K. Kellog Foundation ($7.0 billion).



H-P cofounders David Packard (seated) and Bill Hewlett pictured in 1939 running final production tests on a shipment of 200A audio oscillators, in the original garage at 367 Addison Avenue, Palo Alto.

Rich, but generous

David Packard either directly or indirectly controlled 14% of H-P. He directly owned 9.2%, or 46.6 million shares, worth US$4.3 billion on the day of his death. The foundation had already received another 25.1 million H-P shares, worth US$2.3 billion.

Giving his entire estate to charity in no way leaves his descendants in poverty. His four children have each received shares worth US$50 - $120 million. In addition trust funds for his nine grand children each contain hundreds of thousands of H-P shares.

The Lucile & David Packard Foundation made 750 grants last year, worth US$116 million, to a diverse list of recipients including $225,000 to the Parents as Teachers program in Salinas; $40,000 to train nature guides at a conservation program in Philadelphia; and $20,000 so low-income women could attend an Ms. Institute training session in New York. Among its major ongoing

programs are a $70 million fellowship program for young scientists and engineers and a $10 million series of grants for black colleges.

The themes of the foundation's grants are science, children, population, education and land conservation — all reflecting the personal interests of Packard, who had been the driving force at the foundation since founding it in 1962.

Public service

Packard was also generous with his time, taking a number of public service positions. He served under President Nixon as US deputy Secretary of Defense from January 1969 until December 1971, resigning from the post in frustration over Washington politics and the almost complete lack of basic business principles by which the US Defense organisation operated.

Fourteen years later, he also chaired President Reagan's Commission on Defense Management, which produced a scathing assessment of the nation's defence spending practices. Packard told a congressional committee that the Pentagon would do just as well in its weapons systems if it eliminated its procurement bureaucracy and "simply picked names from a hat"...

"I am deeply saddened by the death of David Packard, who was a friend and mentor to me for many years", commented US Defense Secretary William Perry. "As deputy secretary of defense under Secretary Melvin Laird, Mr Packard served in one of the strongest teams ever to run the Defense Department. Their leadership is still a model for enlightened civilian management of the military."

"A decade ago, he made another huge and enduring contribution to good government. He chaired the Packard Commission, which recommended a revolution in defense procurement through the application of standard business practices. His recommendations are still being implemented today. They are enabling the military to modernise more quickly at lower cost. In everything he undertook, Dave Packard helped change the world for the better."

Kept it simple

While one of the world's richest men, Packard disdained luxury and maintained a casual California lifestyle. Until recently, he drove himself to and from the office in a weathered station wagon. Up until his death, he lived in the same house he bought in the mid 1950s overlooking Palo Alto and the San Francisco Bay. He was a great outdoorsman, with an exceptional love for fly fishing.



David Packard shown using a signal generator and harmonic analyser at H-P's lab bench in 1940. By then the company had moved from garage to 'Tinker' Bell's building.

"After leading the company for over 50 years, Dave's death is a loss to the company and to the country that he loved so well", said his friend and partner Bill Hewlett. "David was a brilliant scientist, an innovative businessman and an incredibly generous and tolerant human being. One of the greatest things that he leaves behind him is a code of ethics known as the 'H-P Way', that will serve to guide the company in the years to come."

Added Lewis Platt, current chairman and CEO of Hewlett-Packard: "A modest man from Colorado — with his best friend — built a world-class company that employs 105,000 people. He turned the blessings of a successful business career into a lifelong campaign to improve the lives of children, support research in science and engineering, protect and conserve nature and promote the arts. We've lost a friend and a great leader, who will be missed immensely. But with our eye to the future, we'll do what Dave would want us to do — to build on what he and Bill Hewlett began in 1939."

From tinkerer to engineer

David Packard was born on September 7, 1912 in Pueblo, Colorado. His father was a lawyer, while his mother was a high school teacher. He was a tinkerer for most of his youth, a skill which served him well when he went to California to study engineering at Stanford, from which he graduated in 1934.

At Stanford he befriended Bill Hewlett and Frederick Emmons Terman, the famous university dean of engineering who would later encourage a generation of Stanford graduates, including Packard and Hewlett, to stay

David Packard

in the Bay Area and put their knowledge to practical, entrepreneurial use.

Hewlett-Packard was formally incorporated in 1947 and went public in 1957 at $16 a share. Each of those shares today is worth an incredible $8988.

As a measure of their friendship, Packard and Hewlett settled the question of whose name would go first in the name of their company to the chance of a coin toss. For all of their many years as business partners, there was never any argument over management issues. Packard maintained general control over the overall organisation, while Hewlett drove H-P's exceptional engineering efforts.

Grew much wider

Until the mid-1980s, most of H-P's revenues were derived from highly specialised electronics instrumentation, such as test and measurement tools, and medical equipment. In the late 1970s, the company moved into business and consumer-related markets such as business computers, calculators, computers and peripherals such as laser printers.

In addition to the success of the products their company put out, Packard and Hewlett will be long remembered for their unique management style and the corporate culture they created. Generally known as 'the H-P Way', it has been widely copied and is how most of the top-tier companies in Silicon Valley operate.

It is a non-hierarchical structure, that values the contributions of all employees; engineers thought nothing of arguing with their bosses. Workers were treated well; even today, the H-P workforce generally does not suffer the day-to-day fear about job loss that seems a fact of life in much of the rest of the white-collar world.



David Packard pictured at his office desk in 1942.



David Packard (L) and Bill Hewlett pictured in the mid 1940s in front of the Redwood building at 395 Page Mill Road, Palo Alto. The first facility built and owned by H-P, it had 10,000 square feet of office, lab and factory space.

Modest, but generous

Packard was an unpretentious man who loved to potter with tools and machinery, and with Hewlett he shared a love of the outdoors. They co-owned two ranches. Vacations usually meant hunting, fishing or horseback riding, albeit often with a stop to chat with shopkeepers about inventories and sales trends.

Packard's close friends say he lost much of his spirit after Lucile, his wife of 49 years, died in May 1987. In January 1989, Packard created the David and Lucile Packard Center for the Future of Children at his charitable foundation in Los Altos.

Funded initially at $5 million a year, the center targets the health and social problems of minority children younger than seven years old."It could be one of the most important things this foundation does", Packard said when he announced the formation of the centre. "You have tremendous leverage if you can do things (with children) early on."

Packard is survived by his four children, David Woodley Packard, Nancy Ann Packard Burnett, Susan Packard Orr and Julie Elizabeth Packard.

All were at his bedside when he died. There are also nine grandchildren.

Valley remembers...

"David Packard created a whole new way of conducting business", said William Krause, a 13-year H-P veteran who became chairman and chief executive of 3Com Inc. of Santa Clara, and a chairman of the American Electronics Association. "In one way or another, many companies around here are really little H-Ps. A piece of Hewlett-Packard is embedded in many of their corporate cultures."

Tandem Computers founder James Treybig is another H-P veteran, and added "H-P is an example of what, unfortunately, does not often happen in the rest of country. It's not the kind of company that tries to grow 100% a year, and which hires 1000 people one year and then fires them the next."

"That's because of Packard's legacy: extreme devotion to people, to technology and to sound business practices. Which explains why H-P is the success it is. Packard didn't try to make a dollar too fast, but he also didn't forget that his job was to make a dollar."

Some of the other Valley leaders who have fond memories of David Packard commented:

W.J. 'Jerry' Sanders III, CEO Advanced Micro Devices: "I remember a dinner when David Packard was serving as deputy secretary of defense. It



David Packard pictured at the opening of the Monterey Bay Aquarium in 1984, with his daughter Julie (Aquarium's Director). A US$49 million philanthropic project by the Packard family, the aquarium has attracted millions of visitors.

was scheduled for Rickey's in Palo Alto. Some anti-war protesters were going to picket it, so people wondered whether the dinner should be moved. Packard wouldn't move the speech. He had a lot of courage. He was the dean of Silicon Valley. The idea of Silicon Valley wouldn't be around without him. We would not be who we are today, if it weren't for David Packard."

Gordon Moore, chairman, Intel: "Dave represented the best of the best of Silicon Valley. He and the company he co-founded with Bill Hewlett gave us all something to look up to. His example as a businessman, leader, philanthropist and human being will be sorely missed."

Douglas Chance, president and CEO of Wyse Technology: "David Packard was one of the most 'hands-on' and 'down-to-earth' people I have ever met. I remember travelling with him to an H-P corporate function and noticing that he was rubbing his hands, which were all red, swollen and scratched. He had black dirt under broken fingernails. When I inquired as to what he had done to his hands, his eyes lit up and he talked for half an hour about how he had spent the weekend installing a sprinkler system at his new retreat in Big Sur. He had dug all the trenches and designed a reservoir to capture the water from a spring 150 yards up from the house. He even had plans for a small hydroelectric generator to supply power to the home."

Fred Gibbons, chairman, Software Publishing: "There are those who really know him, like John Young, Paul Ely and Ed McCracken. And there are those of us who mainly heard the stories and, if lucky, shook his enormous paw at a new-employee lunch. We are the third generation of H-P employees. We were trained in the H-P Way by those whom he had taught directly... Bill and Dave's philosophy was not lost in the transition. These seeds have been scattered everywhere in Silicon Valley, and a thousand companies have bloomed."

Peter Giles, president and CEO, Technology Museum of Innovation of San Jose: "I used to host affairs for leaders, and I remember one seminar. I was putting away chairs, and David Packard was saying good-bye to the dignitaries. Then he came over and helped me put away chairs. He was holding three in each hand and carrying them down to the basement. I stopped and thought — this is a man who leads by example. No work was below him. I think of him as the rock of leadership. You drop it into the lake, and the ripples touch all the shores of the lake. I think his influence is so widespread that, even now after he has passed away, his influence upon our region will only grow."

Sandra Kurtzig, founder and retired chairman/CEO of Ask Computer Systems: "David Packard had a way of listening to you with undivided attention, as if you were simply the most important person in the world. He was an imposing and generous man, and his company lives on as testimony to his particular genius."

H-P staff, too

At lunchtime on Tuesday March 26, H-P workers first learned about the death of their company's co-founder, as company chairman Lewis Platt broke the news of David Packard's passing over the company's intercom system. Platt said the company would carry on in Packard's memory, and encouraged employees to take time alone or togeth-

er to think and talk about their patriarch. In cafeterias and in cubicles, many workers broke down and cried or stood still in disbelief.

Unlike most large companies, where the top brass is rarely seen by the vast majority of workers, there are few H-P employees without a story to tell about David Packard or Bill Hewlett. The two maintained a passionate regard for their employees at all levels. It was they who created the term 'management by walking around' (MBWA), as the two literally spent many hours a week visiting different departments to talk shop with just about anyone that crossed their path.

Packard, especially, was the company's father figure, prowling the hallways and chatting with just about anyone who approached him. He downplayed his status as the chief executive who was worth billions of dollars. Packard regularly went down to the company cafeteria and sat down randomly with employees to eat lunch and discuss business and personal matters.

The day after his death, the flags flew at half-mast on H-P's many campuses in Silicon Valley and around the world.

"You could see a sparkle in his eye when he said hello to you", said Rhonda Kirk, a graphic designer at H-P Labs in Palo Alto. "He was so approachable."

Jeff Bardin, an air conditioning contractor at H-P's Palo Alto site, said he truly felt as if he had lost a member of his family. His grandfather worked at H-P for 30 years, his father for 15 years, and he, too, has worked there for 15 years. "At a company picnic, he held me in his arms when I was a baby, My whole family was raised on H-P. I've heard people ask what the H-P Way is. It's what Bill and Dave did."



President Ronald Reagan presents the National Medal of Technology to David Packard (R) in July 1988, at the White House.

However close Packard was to his employees, he always kept his mind focused on the business at hand, and would not hesitate to reprimand those who were taking their job and the company's success for granted.


When H-P hit the US$10 billion sales mark in the mid-1980s, Packard had long since retired from day-to-day operations, but he was never far from it.

At the time, the company was in the midst of an earnings slump despite rapidly rising sales. Still, the sales organization felt reason to celebrate the revenue milestone and loaded up several planes with sales reps and managers, with course set for Hawaii. There, they were greeted at the gate by — a very annoyed David Packard, who told them in no uncertain terms that he had very little use for a $10 billion company that didn't make any money. Obviously the mood was less than festive from there on...

Even in 1991, when H-P last experienced a financial stumble and the H-P Way appeared to become a thing of the past, Packard jumped back into the saddle and helped put the company back on a solid financial track — re-instilling the virtues of the H-P Way as the key to the company's long-term success.

There's no doubt that the heart of 'the H-P Way' is the character of its founders, Bill Hewlett and Dave Packard. Their philosophy of high ethics, committment to excellence and willingness to listen to and to act upon new ideas, became a model not only in technology but for well-run companies everywhere.

Perhaps uniquely, Hewlett-Packard's 'culture' and resultant great success are continuing even after the founders are no longer at the helm. ❖



"Oh, no! I should have installed Virus Buster!"

Don't wait until it's too late! Talk to us now about real virus protection.
Choose one of these easy options or we'll tailor a system to suit your needs.

Leprechaun SOFTWARE PTY LTD

A.C.N. 010 989 670
75 Redland Bay Road
Capalaba Q, 4157
Telephone (07) 3823 1300
Facsimile (07) 3823 1233

★Professional - security & complete protection.
★Lite - (lightning fast) easy to use & value for money.
★Corporate - efficient business solutions.

Virus Buster for Windows '95 now available

Virus Buster

READER INFO NO. 31

SHORTWAVE LISTENING

with Arthur Cushen, MBE

Bougainville radio war continues

It is some four years since the breakaway group on Bougainville declared independence, and over that time broadcasting in the area has been from two different points of view.

Bougainville, which is in the Northern Solomons but now officially part of Papua New Guinea, commenced operating as Radio Free Bougainville in January 1992 and was officially opened by the Prime Minister of the Republic of Bougainville on January 21, 1992. The station operated on 3890kHz, later 3850kHz. The transmitter was supplied by the International Amateur Radio Network, and although low in power was heard throughout the South Pacific. It operated under very sparse conditions, and even today news reports from the Solomons indicate that the station still operates; but its reception has not been possible over recent weeks.

To counter the broadcasts of Radio Free Bougainville, a station has been set up on Buka known as Radio United Bougainville, which is the Voice of Peace and Unity in the area. It is not directly operated by Papua New Guinea's NBC network but is an independent station. Although mail service is difficult, a verification received gave interesting details on the establishment and operation of this broadcaster located in the Northern Solomons.

Buka was to be the site of a new 10kW transmitter, but this proposal has not proceeded and in fact, in recent weeks a high powered transmitter has been heard on 3325kHz — which is the new Radio Northern Solomons, operating from the Rabaul area.

The details concerning Radio United Bougainville are that the power is only 70W. Daytime transmissions are on 6010kHz and night-time on 3875kHz and signals have been heard here to closing at 1300UTC. The station also has an FM service on 89.9MHz which has a power of 20W.

According to the Controller of Radio United Bougainville, which has the address of PO Box 268, Buka, the role of the station is to disseminate relevant Government information, comprehensively counteract on the BRA rebels' political propaganda and at the same time provide musical entertainment to the listeners in the area. In his letter the Controller, Emilouyse Tenoa apologised for the delay in replying to my report due to the very poor mail service and indicated that he was the announcer that I heard when I had listened to the broadcast — in September 1994.

Attempts to settle the dispute on Bougainville have been under way for some months, with Australia acting as the peacemaker and it is hoped that some settlement of this dispute will take place in the near future.

With reference to the signal heard on 3325kHz, this is Radio Northern Solomons and the transmitter is located at Rabaul. In a telephone conversation with the Controller at Port Moresby, he indicated the power was 10kW and the transmitter was located with the other two NBC stations at Rabaul on mediumwave and shortwave. The studios of the new station are on Buka and programmes are taken off air from the Port Moresby shortwave signal on 4890kHz.

The Buka studios have some programmes of their own but mainly relay the Port Moresby service and have been heard closing at 1200UTC when they will relay the signal from the key station. Sign on is announced at 1930UTC.

The transmitters at Rabaul were destroyed by the volcano and new equipment is gradually being installed. This is the third one to be put into the NBC transmitting site. Signals have been heard very early in the South Pacific due to the closeness of the site, and the programme service includes news in English at 0900UTC.

Jakarta well received

Excellent reception of Radio Republic Indonesia, Jakarta is being received, from three transmitters. Two of these carry the Indonesian National Programme and the other the Foreign Programme. The National Programme is now heard on 9680kHz and 15,130kHz around 1000UTC, while the Foreign Programme has English 0800-0900 and 2100-2200UTC on 9525kHz.

The Republic of Indonesia recently signed a contract with GEC-Marconi Communications Limited for the supply and installation of three Marconi 250kW shortwave transmitters, which are now in operation, plus five curtain antennas, satellite programme links and ancillary equipment.

The contract, worth over £12 million, gives enhanced coverage of the Voice of Indonesia to Malaysia, China, Japan, Australia, Papua New Guinea, Europe and the Middle East. ❖

AROUND THE WORLD

GREECE: Athens has been heard in English at 1445UTC on the new channel of 9915kHz, also on 9420 and 15,650kHz.

GUAM: KSDA has a completely new schedule up to 27 October, with English broadcasts at 1000UTC on 9370kHz; 1030 on 9530kHz; 1330-1400 on 9650kHz; 1600-1700 on 7395kHz; 1730-1800 on 9370kHz; 2130-2200 on 15,310kHz; and 2300-2330 on 11,775kHz.

JAPAN: Radio Japan is using BBC's Kranji transmitter to Oceania from 0500-0900 on 11,920kHz and 1900-2100 on 6035kHz. This will be additional coverage to the South Pacific area.

MONACCO: TWR, Monte Carlo has English broadcasts daily 0655-0800, and on Saturday and Sunday opens at 0645 and closes at 0820 on 7115kHz.

NEW ZEALAND: Radio New Zealand International has an amended schedule until 5 October: 1650-1952 on 6145kHz; 1953-2206 on 9810kHz; 2207-0106 on 11,735kHz; 0107-0458 on 15,115kHz; 0459-0715 on 9570kHz; and 0717-1206 on 6100kHz.

SAIPAN: KHBI's schedule in English until September 2nd, to this area is: 0800 on 9425kHz; 0900 on 13,615kHz; 1000 on 13,840kHz; 1100 and 1200 on 9430kHz; 1300 on 13,840kHz; 2000 on 9570kHz; 2100 on 13,840kHz; and 2300UTC on 13,625kHz.


SRI LANKA: Colombo on 4902kHz has been heard at excellent strength at 1700UTC. Sign off is around 1730 with local Sinhala programmes.

USA: Radio Marte, which broadcasts special programmes to Cuba, has increased its output and is using the transmitter at Delano, California. All broadcasts are in Spanish and the operation is from 1000-1200UTC on 5890kHz; 1200-1400 on 7405kHz; and 1800-2300 on 13,665kHz.

WYFR Family Radio, Okeechobee, Florida has leased time to the BBC World Service and is broadcasting to the Americas 1300-1600 on 9590kHz.

WWCR Nashville has opened its fourth 100kW transmitter and is operating 1800-2200 on 9400kHz and 2200-0600UTC on 7435kHz. WWCR also plans to use the low frequency of 2460kHz.

This item was contributed by Arthur Cushen, 212 Earn Street, Invercargill, New Zealand who would be pleased to supply additional information on medium and shortwave listening. All times are quoted in UTC (GMT) which is 10 hours behind Australian Eastern Standard Time and 12 hours behind New Zealand Standard Time.



HARNESSING THE FAINT LIGHT FROM CHIP DEFECTS

As integrated circuit chips have become more and more complex, it has become harder and harder to track down design and manufacturing faults. However in the last few years the job of locating chip faults has been made vastly easier by a technique known as emission microscopy — developed by Neeraj Khurana, founder of Californian firm Hypervision. Here's how it works.

by TOM ADAMS

Back in the 1950s, when early semiconductor devices were being designed, a peculiar phenomenon was noticed. If one of these large, clunky devices harboured a defect, it would often give off a faint glow. If the device were energised and the room lights turned off, the glow would be visible from across the room. Researchers thus had a primitive 'darkened room' test for confirming the presence of defects.

At the time, no one foresaw placing 400,000 or more transistors onto a minuscule slice of silicon. The knowledge that many types of circuit defects emitted light remained a sort of curiosity, although it was the sort of neat trick that a researcher (using a light microscope as the devices began to shrink) could pull off dramatically now and then.

The quest for higher speed and greater capacity led, of course, to continually smaller circuit elements. And as chips became smaller and more complex, a

bothersome problem began to appear: it was hard to find the location of a single defect on a crowded chip. A chip with 400,000 transistors, for example, may have a single defective transistor whose behaviour shows up in electrical tests. That single transistor may be defective because of a design problem, or because of a processing error; either way, its behaviour must be analyzed. First, though, you have to *find* the transistor among its 399,999 neighbours...

Looking at a chip with 400,000 transistors is a bit like studying a city of 400,000 buildings from the air. Only one of the buildings contains the elusive culprit you are seeking — but *which* building? If you could only make a beacon light up on the house the culprit is in!

Began in 1987

"A beacon in the night" were the words one failure analyst actually used, to describe the performance of his new emission microscope. Emission microscopy — the business of using high optical magnification to see the exceedingly faint light given off by today's chip defects — had its beginnings in 1987, when Neeraj Khurana began to design and market the world's first emission microscopes. Khurana coined the term 'emission microscopy', wrote the basic patent for the emission microscope, and founded Hypervision, today the leading innovator in the field.

How far the science of electronics has come from the 1950s can be judged by the sensitivity needed by emission microscopes today. Suppose the operator of the microscope (usually a failure analyst working for a chip maker) receives a 'field return' — a plastic-packaged chip retrieved from a system such as a computer or fax machine which failed while being used by a customer. (Perhaps you wondered what became of those chips which the dealer replaced in your home computer.)

The failure analyst will first dissolve away the plastic outer package with hot nitric acid, to reveal the chip. Next, he'll bias (energize) the chip to make defective areas emit light. Light emissions occur when damaged semiconductors draw excess current. This process creates multiplication of electron and hole pairs recombining and relaxing, which in turn results in the emission of photons. The term for the process is *recombinant radiation.*

Most, but not all, chip-level defects emit light. Wavelengths of the emissions are from 550 to 1100nm.

The light from a chip defect, though, is less than one *millionth* the intensity you would be able to see with the naked eye. Simply plunking an optical microscope over the biased chip won't show anything — and even if you could see a light emission, you would have to start imaging at a very low power to see enough of the chip to locate the source properly.

Image intensifier

To boost the intensity of emissions from defects, the emission microscope's camera system contains an image intensifier, which collects photons from the defect and multiplies them lavishly.

First, photons from the defect pass through the objective lens of the microscope. Then they strike a photocathode, which converts them to electrons which are amplified by a microchannel plate. Further along, the electrons strike a bed of phosphors which converts each electron back into a large number of photons. A single initial emitted photon can be amplified as much as 11,000,000 times by this method.

The resulting image, though, shows *only* the defect; it doesn't show the details of the rest of the chip, so you can't tell from the emission image alone where the defect is — just that it exists. To show the location, the microscope uses its own light source to make an illuminated image showing chip details. The final output is an overlay of these two images, showing the light from the defect (generally a red pinpoint) in its exact location on the chip.

Ideally, one would want to look at the whole chip in one view, and still be able to see defect emissions. For this reason Hypervision developed a low power, wide-angle objective lens called the HyperLens. Its magnification is 0.8x; for larger chips, a 0.5x version is available. For all but the largest chips, you



Emission microscopes emulate 'darkened rooms' in order to pick up the extremely faint light emissions from chip defects. The emissions are then intensified for imaging. To locate elusive functional defects, the chip must be 'exercised' by test vectors sent from automated test equipment (ATE). The picture on the facing page shows an ATE test head docked to the emission microscope, to pinpoint functional defects.
(Courtesy Hypervision, Inc.)

can see all of the 'real estate' plus the light-emitting defect.


The implications

What has this meant to failure analysts? The old method of finding defects is by mounting the offending chip in a socket and flipping switches (either manually or via a computer) until the precise combination of inputs is accidentally found which causes the failure; the addresses of the inputs will pinpoint the defect site. For a modestly complex chip, and with average luck, this can take about a week; for some chips it can take a month. Meanwhile, the cause of the defect (a design flaw? a processing error?) goes undetected and uncorrected...

This is why failure analysts like emission microscopes. Preparing the chip (which may mean etching away the plastic package) and making the emission image takes an hour or so. The job of the emission microscope is only to locate the defect; the next step is usually close scrutiny of the defect with a scanning electron microscope (SEM), which can show details of the defect and help to reveal its cause.

Overall, defects at the chip level are divided into two types, static and dynamic. Static defects include forward-biased emissions (also called latch-up), avalanche, hot electron effects, and saturated device emissions. Forward-biased defects emit in a narrow bandwidth; the other three types are broadband emitters.

Some defects involve only a single transistor — or even asingle junction within a single transistor — on the chip. Static defects emit light as long as the chip is biased, but dynamic (also called functional) defects are much more elusive; they emit light only when precisely the right instructions are sent to the chip.




Emission images are actually a composite, with the emitted light overlaid with an illuminated view of the chip structure. The coloured areas at the upper right of this emission image show defect sites.

Those instructions come from ATE (automated test equipment) units, which are basically very big and very expensive computers which test chips by running extremely long sets of instructions (called *test vectors*) through them. Out of 100,000 test vectors, a sequence of perhaps 50 will initiate a functional failure.

Previously, though, there was no way to connect an ATE to an emission microscope, except by using long cable sets, which worked only with low-speed chips and which were fiendishly difficult to keep in repair. For the higher speed chips which everyone was designing, you could tell that a functional failure existed, but because of its evanescent nature you couldn't tell where it was.

Hypervision solved this problem by making a 'docking' emission microscope, in which the large circular test head of the ATE system docks right into the microscope, to place the device under test (DUT — the chip) right under the microscope's objective lenses.

The test vectors are sent through the chip from the ATE. When the site of the functional defect on the chip lights up, the test vectors trigger the microscope's camera. Once the chip is mounted on the ATE test head and the test head docked with the microscope, finding the precise location of the functional failure takes about five minutes.



Because of heavy metallisation, some new high-speed chips are imaged from the back side. A square window has been cut into the back side of this QFP (quad flat pack), to within 50 microns of the circuitry, to permit backside emission imaging.

New problems


The first docking emission microscope was built and sold by Hypervision in 1993. At about the same time, the semiconductor industry was reaching new heights of both chip density and device speed. Along with these new performance levels came new and formidable inspection problems.

Even modest chips often have lines of metallisation on the surface. The low-power HyperLens has a wide-angle aperture because of the metallisation: defects are often located *under* the metallisation, and the light from the defects bounces between the metallisation and the chip to escape at an angle. The wide-angle lens can capture these low-angle emissions.

As the speed of chips grew, metallisation on chips increased until some chips had four or five layers of metallisation, or unbroken ground planes. Increasing layers of metallisation improve speed, eliminate cross-talk, and avoid distortion. But the same metallisation meant the light from defect sites could no longer escape upward at all.

An unsolvable problem? Not at all. Light-emitting defects emit light in *all* directions, not just toward the top of the chip. One of those directions is toward the back of the chip, and fortunately, silicon is somewhat transparent to the wavelengths involved.

The solution which Hypervision devised was a precise and careful — but reasonably fast — technique (a patent is pending) to remove nearly everything behind the active circuit layers. A cutting/grinding tool removes a window through the plastic package, through the metal lead frame to which the chip is attached, and then through most of the silicon of the chip itself.




Once the location of a defect has been pinpointed by the emission microscope, the defect can be studied in greater detail by a scanning electron microscope (SEM). This 15,000x SEM image shows melting of polysilicon at a chip defect site.

Today's chips are usually around 750 microns (0.75mm) thick; the Hypervision method removes about 700 microns of this silicon and leaves about 50um — a nice window thin enough for the light emitted by defects to shine through. The silicon window is also thin enough to transmit incident light, to produce the illuminated image showing the details of the chip. The process is so precise that it can even produce windows through the 'backside' of chips in uncut wafers. Through this window the emission microscope can produce emission and illuminated images just as sharp as frontside images.

For consumers, the benefit of finding light-emitting defect sites is direct and simple: fax machines, computers and all sorts of other systems — which might otherwise fail because of undiscovered chip defects — keep right on running.

Further information on Hypervision and its range of emission microscopes and associated systems is available from Hypervision Inc., 46560 Fremont Boulevard, Suite 415, Fremont, California USA 94538; phone (510) 651-7768 or fax (510) 651-1415. ❖

TAX TIME



Thinking of investing? Want to invest in Australia's future?

Please help us to help a child.

Please send your donation to: Barnardos Australia
Locked Bag 1 Million Broadway NSW 2007

STTF96

$250 ☐ $100 ☐ $50 ☐ $150 ☐ $___ ☐

Name:_____

Company:_____

Address:_____

State:_____ P'code:_____

Mastercard ☐ Visa ☐ Bankcard ☐ Amex ☐ Diners ☐

☐☐☐☐ ☐☐☐☐ ☐☐☐☐ ☐☐☐☐

Signature _____ Exp. date_____

Or Call 1800 061 000 Toll Free

The Childrens Charity
Barnardos Australia

Donations over $2 are tax deductible

VIDEO CAMERAS
$135
PCB CCD MODULES

Choose from 27 Types. ***ALL AVAILABLE NOW ! DON'T WAIT !*** Tiny from 32x32x15mm. Excellent Low Light & Infra-Red Sensitivity, **400** Line Horizontal Resolution and Edge Enhancement Circuitry provide **SUPER VHS** quality images. **2000x** Electronic Shutter copes with wide range of illumination.
2.9mm, 3.6mm and 4.3mm Wide Angle Lenses
2.8mm, 3.7mm and 5.5mm **"PINHOLE"** Lenses
Almost unlimited range of lens sizes for C & CS Mount. On-Board Infra-Red Leds or **50mW/sr 60** degree **IR LEDs $20 packet 50.**

** CIRCLE READER CARD FOR INFO ON OUR **

FULL RANGE of CLOSED CIRCUIT TV EQUIPMENT

ALLTHINGS S & S

Phone (09) 349 9413 Fax (09) 344 5905

READER INFO NO. 44

LOCAL FIRM DEVELOPS SPEAKING WEATHER ROBOT

Easy access to current and accurate weather information is now quite important for many people, including aircraft pilots, bushfire fighters and the fishing industry. Convenient telephone access to this information is now going to be a lot easier, thanks to WeatherVox — a speaking weather reporting system developed and manufactured in Australia by Sydney firm Sphere Communications.

by JIM ROWE

Need to know what the current weather is in Kingsford, a few kilometres south-east of the Sydney CBD? Nothing could be simpler — just try ringing (02) 344 9400.

What you'll hear, when you ring that number, is a report provided by WeatherVox, a speaking microprocessor controlled automatic weather reporting system hooked up to an Ultimeter 2000 Weather Station. It operates 24 hours a day.

WeatherVox has been designed, developed and manufactured here in Australia by Sydney firm Sphere Communications, which is now offering the system as a complete 'turnkey' package for any firm or organisation with a need for an automated weather reporting system. Sphere has set up a demonstration system on the above number, to allow potential buyers to get a better idea of the system's performance and capabilities. The demo unit is set to give a 'brief' report, to minimise the online time needed to get a report, but it will give you a good idea of what WeatherVox can do.

You might anticipate that WeatherVox would be a fairly large and expensive system, but thanks to modern microprocessor technology it's surprisingly small. The unit itself measures only 200 x 112 x 30mm, and weighs a mere 340 grams. Apart from this there's only a plug-pack power supply (9V/600mA), and of course the Ultimeter Home Weather Station. We reviewed the Ultimeter Model II station in the February 1994 issue, by the way.

Actually, nowadays there are three different Ultimeter models — the original Model II and the newer Models 500 and 2000. The Ultimeter II provides outdoor temperature, wind speed and wind direction measurement, while the model 500 adds indoor temperature measurement and the capability of making rain gauge measurements. The Model 2000 provides all of these capabilities, plus the ability to make barometric pressure, indoor and outdoor humidity and more accurate rain gauge measurements (resolution 0.01").

To match these three models of Ultimeter, which it also distributes in Australia, Sphere makes three corresponding models of WeatherVox. The company also makes a version to suit another brand of Home Weather Station, the Davis unit, to allow existing owners to take advantage of the WeatherVox design. (Custom versions of WeatherVox can also be made to order, for other weather stations.)

What's inside

Inside the WeatherVox case is a dedicated microprocessor chip, running from a program stored in ROM, and driving an ISD speech synthesiser. The micro is also provided with non-voltatile RAM chips, to store the actual weather data, plus interfaces so that it can communicate with both the weather station and the telephone line. (Sphere has received Austel approval for connecting WeatherVox to the Australian PSTN, and also from the New Zealand authorities and the USA's Federal Communications Commission.)

All of the WeatherVox circuitry is mounted on a high quality multi-layer printed circuit board using surface mount and plated-through hole technology, ensuring a high level of electromagnetic compatibility.

Both WeatherVox interfaces use compact RJ11-type 'modular' connectors, although the weather station interface is actually a standard RS-232C serial port. Cables are supplied for both interfaces, that for the phone line having an RJ11 plug at each end while the other has a six-way RJ12 plug at the far end to mate with the socket on the weather station console. The WeatherVox also has a standard 'concentric' DC power input socket to accept the plug pack cable connector.

A red indicator LED on the end of the WeatherVox case confirms its power status, while a red/green pair of LEDs adjacent to the RS-232C connector show transmit and receive data status when the unit is communicating with the weather station.


Inside the case, a set of eight DIP switches on the PCB can be used to select user options in terms of the spoken units that WeatherVox uses to report temperature, wind speed and rainfall. The factory default is to give temperatures in degrees Celsius, wind speed in kph and rainfall in inches, however various other options are available including degrees Fahrenheit; metres/second, knots/hour or miles/hour; and centimetres or millimetres. For wind direction there's also a choice of either degrees of cardinal points.

With the versions to suit the Ultimeter 500 and 2000, barometric pressure can also be given in kPa, millibars, mm of mercury or inches of mercury.

A further WeatherVox option, factory set and available to order, allows the unit to be connected to a mobile radio system instead of the telephone network. When a radio call is received WeatherVox can operate the transmitter via the PTT line, and provide its report.

Online configuration

For greater convenience, Sphere's engineers have designed the WeatherVox so that its operating configuration is stored in non-volatile RAM, and can be adjusted remotely using DTMF command codes. The unit allows for this by giving the message "For more information, please press



Sphere's compact WeatherVox unit converts a low cost home weather station like Ultimeter 2000 into an automatic telephone answering, speaking weather reporting system. It's fully approved by Austel for connection to the PSTN, and can be configured remotely using DTMF codes.

Hash", just before hanging up after giving its weather report. An authorised user can then key in a PIN number via their phone keypad, and if the number is correct, the WeatherVox will allow entry of further codes to change its configuration, give statistical reports, and if desired clear its historical data.

Configuration options programmable in this way include the choice of brief, intermediate or long weather reports; setting the averaging interval for wind speed and wind direction; setting the number of rings before WeatherVox answers a call; setting its date and time; selecting either 12 or 24 hour time; resetting its PIN number; and so on. Very flexible, and very convenient.

By the way a 'brief' WeatherVox report includes time; current outdoor temperature; overnight low temperature and when it occurred; wind direction and speed; peak gust on the current day, and when it occurred; average wind speed over the last 10 minutes; average wind direction over the last minute; the current day's rainfall, and the rainfall for the last week. The intermediate and long reports add further items and statistics again.

Considering its flexibility and performance, WeatherVox units are available for surprisingly reasonable prices. Including sales tax, these vary from $608.78 for the WeatherVox II model to match an Ultimeter II Weather Station, up to $730.78 for the WeatherVox 2000 model. The Ultimeter Weather Stations themselves are available from Sphere at prices ranging from $401.38 for the Ultimeter II to $767.38 for the Ultimeter 2000.

Sphere can also supply a wide range of accessories, including an anemometer, medium and high accuracy rain gauges (including a wireless rain gauge), temperature and humidity sensors.

As mentioned earlier, you can easily get a demonstration of the WeatherVox and Ultimeter 2000 combination in operation, by calling (02) 344 9400. Sphere also has a site on the World Wide Web, giving further information on these products, at the URL **http://www.world.net/sphere**, and can also provide information by email from its address **sphere@world.net**.

Needless to say you can also get further information on WeatherVox in the more conventional way by contacting Sphere Communications at 161 Bunnerong Road, Kingsford 2032 (PO Box 380, Darlinghurst 2010); phone (02) 344 9111, or fax (02) 349 5774. ❖



DART: USING ISDN TO DELIVER RADIO ADS

A Sydney-based audio production studio has begun delivering commercials to radio stations around the country in digital form, via ISDN. The advertisers are delighted, and the stations are happy — they get the ads faster, and in high quality form; but claims of 'unfair competition' are coming from production firms still using older analog technology...

by BARRIE SMITH

Radio commercials — you either love 'em or hate 'em. But unless you Araldite your radio dial to an ABC or ad-free community station, you can't avoid them.

In this country we have one of the most advanced and balanced radio broadcasting systems — in terms of both content and technology. But there is one side of it which has been left to wallow in its own hash... the handling of the very ads which bankroll the whole commercial panoply.

In our major capital cities, there are now audio production studios which are equipped to deliver — and do deliver — an output equal to the world's best. One Sydney studio which is a leader in its field is Stellar Sound Studios, based in Glebe.

Stellar is managed by radio veteran Rob Lynch, employs 22 people and houses three voice studios and an unusual section which produces in-flight audio programming for 14 world airlines. Most times these operations run smoothly, profitably and with little headache. But a new area for the company, which kicked off on February 12 last, has caused an unexpected furore from the industry itself.

The new development is DART — Digital Audio Rapid Transfer — a new way to deliver radio ad spots to stations across the country. In a nutshell DART involves sending the ads in digital form, via ISDN (the Integrated Services Digital Network).

When Rob Lynch began as an on-air announcer back in the 60's, ads were replayed from 45rpm vinyl platters: "If you were doing a breakfast show, you'd have chaos in the studio. You'd have your three turntables constantly running. You never turned them off. You just put the next disc on, cued them up and played ad after ad."

That method had lasted about two decades, and was followed by delivery on 1/4" tape reels which went on for 23 years. In recent years most stations dubbed the supplied tracks onto tape cartridges, which at least delivered some form of on-air mechanisation. However the quality of commercials always suffered.

While FM brought benefits from a live voice content and CD quality music, the ads — which really paid for the whole show — often went to air from players stacked with cartridges which had probably seen two to three hundred passes.

Lynch: "The stations had gone digital. But the only thing analog on air were the commercials, the lifeblood. Everything around them was digital and the commercials were analog. Then they (the ad agencies) wanted them brighter, so they'd equalise them to be brighter until they broke up at the top end. This wasn't the solution at all."

In Lynch's view, it was obvious the agencies weren't going to do anything about it, nor were the radio stations: "And then you had the production studios, the third element of it. The studios were making a profit out of sending dubs, and they weren't going to help an end to that monopoly."


But Lynch decided to make it his problem — and to find a solution.

Enter DART

I visited Stellar's DART operation in William Street, Kings Cross and spoke to GM Linda Christian.

Ms Christian: "We've installed in every (commercial) radio station in the

The DART system bypasses the need for couriers and freight movers getting tapes to the stations. It is estimated that 200 radio ads miss their broadcast deadline each week because of delivery breakdowns. With DART, the ads are delivered in seconds, right into the station's computer...







At left, DART general manager Linda Christian monitors a radio advertisement prior to 'sending it down the line'. At her left hand is the master replay DAT machine — a Fostex unit. At right, Ms Christian at the keyboard of a 286-based PC, about to begin delivery of some audio tracks to a radio station via an ISDN link.

country computers and software so that we can send commercials by ISDN. We can have a 30-second commercial anywhere in the country in 45 seconds. All the hardware and management software is run from here."

A DAT cassette, 1/4" tape or ISDN feed is taken from a studio or an agency, traffic instructions are added and the tracks copied to a DAT machine in the main control room, controlled by a bank of PCs. Explains Christian: "It's really just a despatching system. Almost like a digital courier."

The DART setup operates at no cost to the stations, being financed by a transmission cost to the advertiser of $40 per 'send'. This transmission may contain a number of different spots. The conventional method of making tape dubs can equal this figure and more, when courier and freight costs are added.

Linda Christian: "The radio stations think it's just marvellous."

The advertisers also benefit, from the rapidity of delivery and ability to alter the playout schedule quickly. It is feasible for a spot to be written, recorded and transmitted by DART to any station in the country within the space of half a working day.

As the setup operates 24 hours a day, every day, an advertiser can instruct that the ad be transmitted at any time or even withheld until a specified release time.

Each radio station in the scheme (currently 123 out of a total of 161) has a PC linked to Kings Cross by ISDN and the spots are received and downloaded to whatever machine they deploy — be it DAT, CART or whatever — along with instructions for its correct scheduling.

The system is two-way in one sense: if an out-of-Sydney advertiser wishes to distribute material nationally, the tapes are given to a DART distribution point in each state capital to relay to Sydney for dissemination.

The quality is basically that of a CD. Transmission takes place after processing, via rack mounted file servers, linked directly into Telstra's ISDN system. The output to ISDN is 18-bit, 64x oversampled at a user variable 32kHz, 44.1kHz or 48kHz sampling rate. At both ends a 486DX4/100MHz PC is used, each using 8MB of RAM and a 540MB hard drive.

As mentioned, the entire cost of installation at the station end was born by DART. In some cases, the spots arrive and are integrated directly into the station's computer traffic/scheduling system, ready for broadcasting.

Significant outlay

Rob Lynch admits, in the start up phase "there were two schools of thought" on who would bear the cost of the installation:

"I went for what people do in their houses; the phone is put in for nothing, then they're charged to use it. I knew radio stations wouldn't even pay a con-



Recording engineer Brad Power driving one of Stellar's Lexicon Opus digital mixing consoles. The jog shuttle control at lower centre of the picture allows precise inching of any track on the system.

nection fee. But they wanted it and they were excited about it."

"The tenet of this whole idea is that it costs the radio stations nothing. So we stuck with that. I had a few heavy fights because that's where a lot of money went, obviously — about $1.4 million has gone into just the radio station installations."

The period from mid February to March was used to bed in the software and smoke out the bugs.

Pluses and minuses

Obviously, Telstra will gain from the ISDN revenue. Stellar (as a sound company) will lose all their dub revenue — as will other production studios.

Some other studios have revolted against DART, claiming it was a restrictive trade practice and ignoring the quantum leap in technology it offered. One group, 2UE/4BC already use satellite distribution for live programme output. They are opposed to DART.

What DART does is free up studios to maximise their creative input in recording, especially helping the smaller units who use outside dubbing facilities.

As Lynch says, people are still free to send dubs by satellite or any other way — "It's not a monopoly".

Stellar in the air

Well before DART was a twinkle in Rob Lynch's eye, a great deal of attention was paid by the company to its in-flight services. Running now for 22 years, 14 airlines take the service — from Qantas to Malaysian Airlines to Air Namibia. Lynch's company is in fact "the longest established producer of in-flight audio in the world".

Four full time producers make audio programmes for the airline clients. This includes original voicing and mixing with CD tracks, right down to the supply of the aircraft's cassettes.

When, say a classical programme for Malaysian Airlines is required, the producer employs custom computer software to devise a suitable programme, based on desirable parameters. At this point the computer assembles all the components, determines intros, mix and fade points, then goes on to produce the copyright reports.

Compact cassettes are used for output at the moment, but it is expected that Stellar's in-flight programmes will be on CD in the near future.



As DART takes over, so does the old guard of six Studer 1/4" dubbing recorders go out. Any offers?

Where did it go?

On the day of my visit, a crew was busy decommissioning rows of Studer 1/4" dubbers and an Atari 16-track studio recorder — victims of the relentless DART juggernaut...

Having spent many hours over the years in audio studios in various parts of the world, I was always impressed by the massive mixing desk — but less by the rack mounted analog recorders, continuously demanding of the operator's attention, sometimes to the detriment of the EQ and mix process.

Walk into a Stellar studio and you wonder where it all went. It fell, according to studio manager Brad Power, under the wake of Opus: a $300,000 digital mixing and editing system. Opus is essentially a digital audio workstation.

This tapeless digital recording system is fully integrated, offering random access and is controlled from a single mixing console.

Storing and editing audio on conventional magnetic tape always required management of sequential events, with much spooling back and forth to find and work on selected segments; melding analog and digital formats also added to the tedium. The Opus approach delivers the functions and controls of a multitrack tape machine, a mixing console and an editing system.

The audio material is recorded on hard disk drives. All audio inputs and outputs

How the DART idea was born, in Monaco...

It was mid 1994, and Rob Lynch was on a recuperative holiday with his wife in Europe: "I had been to an Edward de Bono lateral thinking course before I left. I was quite interested in ideas."

As he drove along in the south of France he said to his wife: "I've just had a good idea." He told her, and she replied "That's a good idea."

Lynch notes that it was "The first time in 30 years she's ever said that!"

Back in Australia Lynch met with Telstra, who offered to buy the idea. But Lynch said no: "If I'd sold it to them, it wouldn't go anywhere; the idea wouldn't be born. I know how those corporations operate. So I said 'No, but thank you'. And they came in as a sponsor. And they still are."

"After that I contacted software writers and others and started developing the idea. It then got to the point where it had been developed far enough. I had put about 100 grand into it. It was up and running, and then I found a merchant bank to finance the idea, because it has cost a couple of million dollars."

The DART system may well be suitable for video as well, according to Lynch: "We'd also like to take it offshore".

of the mixer can be 'soft-assigned' to either analog or digital input/outputs. Twelve channels of four section digital EQ (equalisation) is provided, able to sweep the entire 20-20kHz spectrum. There is also a DC blocking filter on each channel.

In operation, changes can be made to any element without altering the original material. To perform an edit the in/out points are determined and marked by rocking the audio back and forth, or by entering the time code address on a keypad.

A video display is used to confirm the machine's status and configuration, but many operators find no need for a visual reference.

One freestanding, remotely located cabinet stores the CPU and sufficient hard drive storage to hold over 14 hours of audio sampled at 48kHz. Four disks can amount to a 4.8GB capacity.

How about backup? Small, efficient and low cost Sony format 8mm tapes are used; each can hold 2.3GB or 360 track-minutes of audio.

The Boston-based Lexicon company behind Opus maintains remote diagnostic support and allows for software upgrades via an integral 2400 baud modem. At present there are two companies each in Sydney and Melbourne using the $300,000 Opus system.

It all makes reel to reel or tape cartridges look quite ancient! ❖

NOTES & ERRATA

240V Power Relay (January 1992): When using this unit with a 'master' appliance that draws a small standby current, the circuit can be turned partially on if sensitivity resistor R2 is of an unsuitable value — as detailed in the March '92 errata. If this is the case, the 'slave' 240V outlet may produce a *chopped* waveform much like that from a conventional light dimmer when adjusted to a low setting, which in turn can distress and even damage some appliance power transformers.

In the light of this potential for damage, we unfortunately must recommend that constructors do not build or use this project.

Subwoofer/Bridge Adaptor for 12V (March 1996): Electrolytic capacitors C7 and C9 are shown with the wrong orientation on the component overlay diagram on page 76. When correctly installed, the positive lead of C9 should connect to pin 9 of IC2, while that of C7 must be connected to pin 8 of IC2.

Also, 12V DC input leads are transposed in the overlay. The negative connection is towards the top of the diagram, while the positive lead is the lower of the two, as indicated by the '+' marking on the copper side of the PCB.

PC-Driven PIC Programmer (April 1996): Contributing author Charles Manning has advised of a minor design error in this project, and its remedy:

Although many prototypes have worked well for over a year now, I have discovered a slight design error. One of the purposes of U4, the 74LS05, is to drive the 13V Vpp switching transistor. When the transistor is off, the output voltage on U4 will be 13V, which is higher than the specified output voltage for these parts even though the circuit still functioned perfectly with a National Semiconductor part.

As reliability was a key goal in the design of the programmer, I decided to effect a last minute change. The 74LS05 was changed to a 7407. These parts are pin compatible, but the 7407 is capable of tolerating higher output voltages. Unfortunately these parts are non-inverting, so the control software had to be modified slightly. Since the 7407 is quite difficult to source, I am providing a 7407 with all sofware of full kit orders. So even if you buy only the software set, you will still receive a 7407.

My apologies to anybody who has been inconvenienced, especially the first few people to order kits; a delay in sourcing 7407s meant that they had to wait a few extra days for the kits to be shipped. ❖

The Challis Report

(Continued from page 13)

old as well as new uses.

Other developments

There are of course other new types of batteries currently under development. Some of the most exciting make use of polymer electrolytes in the form of ultra-thin laminates, with foil anodes and cathodes. One potential application of such technology would be to provide cost-effective and range-effective battery-operated cars. General Motors in America has been a serious researcher in this field for more than a decade.

Whilst it appears that the basic technology may be close at hand, a variety of practical problems has placed embarrassing pitfalls in its path. Possibly the most vexing of those problems is the need to assure that each cell in a stack is correctly charged. If not, then over-charging imbalances are likely to occur. Should that occur, then there is the risk of cell damage, or conversely inadequate stack voltage output.

With only four cells to charge in a stack, the task is relatively easy, but when the stack contains as many as 100 or more cells then the issue assumes critical importance. It appears that this problem has not yet been satisfactorily (economically) resolved.

An equally vexing problem facing designers in USA and Canada is the impact of low temperature on battery performance. If a battery doesn't work at -20°C, which is a common winter temperature in most mid-western and northern states, then their problem becomes quite serious. Now lithium-ion batteries fortunately still provide at least 60% of their rated capacity at -20°C. As a result, they still have considerable appeal in many new designs for equipment that is likely to be operated out of doors.

It is my understanding that multicell lithium-ion batteries have been developed for automotive use, but at this stage there are still problems which have yet to be resolved.

With most manufacturers keeping quiet about their new developments until after their public debut, it's difficult to know what's really happening. As I discovered during my most recent trip to America, there are still many manufacturers who believe that their existing technology can be retained and markedly improved. It thus appears that the ubiquitous nickel-cadmium battery is by no means *passe*!

There are still more than one hundred million NiCad batteries being produced world-wide each year. That market appears to be strong and vibrant. Many of the major manufacturers are now developing 'memory resistant' batteries, as they face the competition from new contenders.

It looks like we'll have more batteries to choose from, but many users may still suffer from those vexing 'battery blues'. ❖



When I Think Back...

by Neville Williams

Arthur David Spring - 1: A true 'hands on' electronics engineer

After compiling 99 previous instalments of 'When I Think Back', it still came as a surprise to find myself writing this 100th column on the life story of a friend whom I thought I knew — until I set about preparing it for publication. Fortunately, I managed to persuade him to interrupt his still busy life to spell out his memories of other days onto tape cassettes, to augment a recording he made for the 'Bright Sparks' series on ABC Radio.

Family records attest to the fact that Arthur Spring was born at Wellington in the NSW midwest, in July 1918. His father worked on the railways, which were at the time central to the existence of many such country towns.

On the job, his father had spent many hours in the company of Ben Chifley, who was later to become Prime Minister of Australia. That, and the impact of the bitter railway strike of 1918, probably generated in the Spring family an attitude often described as 'left of centre'.

In his spare time his father busied himself with lodge activities and became an alderman on the Wellington council, where he sponsored the installation of the Wellington Park and a swimming pool to Olympic standards.

In this same time period, Spring Senior took up share-cropping at Mumbil — which I had never heard of until its mention in Arthur's tapes. (It must be close by, having the same postcode as Wellington.) While there, he introduced the Fordson tractor to the area. That phase lasted until 1925, when his father took the family to Sydney to become a Manager in a firm of funeral directors.

So it was that Spring Snr, his wife (a girl from Orange), young Arthur and a brother two years his junior ended up at Petersham, then at Five Dock, where a third son was added to the family.

Being of school age, young Arthur began to absorb the three R's, mainly at Five Dock public and later at Stanmore Commercial School. This last was at the insistence of his father, who tried to impress upon him that there was good reason to study book-keeping and other 'commercial' subjects, in addition to acquiring manual skills. In the taped interview with Stephen Rapley of the ABC, Arthur confesses that he found school utterly boring because it seemed so irrelevant to his real interest, which was in things practical and technical.

More to the point, in 1930 at age 12, he appears to have been bitten by the 'wireless bug' as evidenced by the fact that he built his first shortwave radio. How this came about is lost in the mists of time, although he does recall having enjoyed reading the biography of Thomas Edison. He also remembers that his father had put together a couple of crystal sets; his contribution to the exercise had been to heat the soldering iron on a gas flame — without burning off the 'tinning'. Yes, he would have heard 2FC on a crystal set, but he couldn't recall any special reaction to the experience.

He did however recall a couple of boyhood friends who were interested in wireless, and he did scavenge wireless parts from old battery sets — sufficient to warrant a direction from his mother to 'clean up your room'.



Arthur Spring in his prime, in 1965. Building on his early practical experience, he had become Chief Engineer of A.W. Jackson Industries, and had designed and produced the very successful 'Precedent' range of B&W TV receivers.

The radio 'bug' bites

From that collection of oddments came the wherewithal to build a two-valve shortwave set, powered from batteries and driving an old cone type loudspeaker. Perhaps the wireless craze was born on the day that he picked up a signal direct from Germany and yelled for his parents to "come and listen to this"!


From overseas stations, young Arthur Spring's interest turned to amateur signals and the informal chatter that went on between the operators. This prompted the construction of a receiver for the five-metre (60MHz) band — in the days when transmitters were self-excited oscillators and the receivers superregenerative detectors. Arthur was very proud when he logged an amateur direct from Newcastle.

Back to the HF bands, Arthur and a mate thought it might be interesting to have 'mobile' equipment, and accordingly loaded their gear into their respective billy carts. Arthur had the receiver in

his; in his mate's cart was a car battery, an old Ford spark coil and a modified Emmco B-eliminator which rectified and filtered an HT supply for the set — involving a cable between the carts.
Such was their enthusiasm, they trundled this unlikely outfit all the way to an amateur station in nearby Ashfield.

'Pirate' amateur

Inevitably, perhaps, Arthur was caught up by the urge to be a part of amateur radio, and the result was a simple HF transmitter with which he was able to join in the conversations — as a 'pirate', using the callsign VK2BB.
His father in particular was critical of such activities, mainly on the basis that he was spending half the night playing with 'that thing' when he should have been doing his school work.
All went smoothly enough until he responded to a 'CQ' from VK2AA, who casually inquired about the area where he lived. Arthur discretely omitted to answer the question, but minutes later the phone rang to the sound of a friend's



The first identifiable engineering product designed by Arthur Spring: the Crown model ID-2 dual wave coil bracket, as advertised in 1937.

voice: "That's the Radio Inspector you're talking to!"
Panic reigned, his parents were dismayed, and within record time, all trace of a transmitter had disappeared from the premises. Nothing more was heard of the incident, but VK2BB had been effectively silenced.
By age 15, Arthur had passed all subjects in his curriculum, but at different times. "I didn't officially leave school", said Arthur, "I just lost interest in formal education!"
Meanwhile, Australia was in the grip of the Great Depression, as Arthur discovered when he started looking seriously for a job. He spent endless hours standing in queues, extending 'down the street and round the corner', only to miss out. But he did have one advantage that was to stand him in good stead: he was interested in radio, he had built his own shortwave set and he could solder.
That finally commended him to Radiokes, at the time a prominent manufacturer and supplier of radio components to hobbyists and small receiver manufacturers. They offered him a job in 1935 at 13/6 ($1.35) per week, working with other juniors, male and female. He recalls that he and a Colin Sanderson shared a bench with two girls, assembling small components for the market.



The Crown Radio building as pictured on the cover of their 1937 catalogue. By stacking all and sundry employees into the various departments, the interior photos suggest a staff complement of an improbable hundred or so!

Assembling radio 'bits'

In the 'Lab' were Max Laurey and Harold O'Shea, who 'designed' the components and kept a check on production quality.
In 1936, says Arthur, Harold O'Shea accepted a job in a rival company, Crown Radio, in Crown Street (Sydney) and he in turn proceeded to surreptitously 'poach' Arthur Spring. Arthur didn't mind in the least, because he was being offered 22 shillings ($2.20) per week.
That's how Arthur tells it, but subsequent events have suggested that the rivalry between Radiokes, Crown and RCS was largely posturing. Behind the scenes, it was convenient for all three to exchange information and facilities to their mutual advantage.
Crown Radio at the time was in incredibly 'pokey' premises towards the Wooloomooloo end of Crown Street, and the walk to work each morning took him past apartments occupied by sundry 'ladies of the night' who often made interesting suggestions to the 'callow youths' passing by...
Shortly afterwards, Crown moved to much larger premises at Pyrmont, with more air, more light and enough room to spread the acvities into separate 'departments' — including a quite respectable laboratory. Arthur recalls that, for the preparation of 'new look' literature (The *Crown 1937 Catalogue*) a photographer took shots of the various sections — but only after all and sundry had been shuffled to strategic positions to make the place look fully occupied!
Questioned about the role of unions at the time, Arthur said that for all practical purposes in small radio factories, their role was nil.
Employers paid what they had to, and hired and fired at will, depending on the supply of materials and the state of the Order Book. Work was seasonal: busy in winter, slack in summer and "at its worst in the Ides of March".

'Hands-on' tuition

Be that as it may, young Arthur refined a range of production skills at Crown, including the correct tinning and termination of multi-strand 'Litz' (Litzendraht) wire, observing the critical effect it had on the 'Q', gain and selectivity of tuning coils and IF transformers.
In the same context, he was made aware of the need for operator precision and hygiene in handling fine wire and the ruby mica dielectric in compression trimmmers. (Perspiration from female operatives during their monthly periods presented a subtle hazard.)
He spent time in the laboratory, and contributed to the design of Crown prefabricated dual-wave coil brackets which were used by hobbyists and small manufacturers.
By 1937, he had absorbed sufficient practical know-how about wireless workshop practice to compete for a job in his own right — which is how he ended up at the then-nearby Breville

Radio, again on the heels of Harold O'Shea. There he found himself involved in the production of receiver components, much as in Radiokes and Crown, except that Breville was making them for use in its own receivers.

As one assignment, he was directed to study the design and layout of a new battery powered receiver that was being readied for production and release. His commission was to prepare a set of wiring guides in full colour which could be used on an assembly line. As the chasses were moved along, each operator would instal the particular leads and components shown on their individual display board.

It so happened that Arthur found one of the female coil winders, Myrtle by name, particulalry attractive. In due course, after all the usual preliminaries, they were married in 1942 and set up home at the same street address in Henley where Arthur still lives. It was a happy marriage, and Arthur adds that he was 'devastated' in 1964 when his wife died quite suddenly of a heart attack.

In terms of his career, Breville Radio provided a more purposeful engineering environment than in Arthur's earlier years. It was headed up by none other than Noel Smith who, in evening hours, was final-year lecturer to the first generation of radio graduates coming through the Sydney Technical College — now the University of Technology.

Learning by doing

It was about this time that a maturing Arthur Spring realised that he didn't have a head for routine 'book learning'. I quote: "The shutters went up. I came to grip with theory by actually doing things, and working out why they were so in the hands-on context."


If he was going to get anywhere in life, his best prospect would be to apply himself seriously to the subject they were describing as 'electronics' and seek to become really good at it. Success would be consummated by becoming a chief engineer, a manager or running a company of his own.

For the present, he was warned by Breville management to get more rest instead of staying up into the small hours merely fiddling with radio. Under pain of 'the sack' he simply must turn up for work on time and alert!

He recalls how he once asked Noel Smith: "Should I enroll at tech"?

"No", said Noel; "Do what you're doing now — but keep your mind on the job!"

"The important thing is not to carry all the facts in your head, but to know where to find them when you need them!" For him, Arthur reckons, it was timely advice...



An inside shot of the Breville factory in 1938. An unusual fact Arthur remembers was that the operatives were not issued with stools. They were expected to work standing up, behind high benches!

Breville Radio moved to Missenden Road, Camperdown (Sydney) in early 1937, poised to become a major manufacturer of domestic radios and other retail products under the Breville Radio banner. Painted on the building for all to see was the motto favoured by the proprietor, Bill O'Brien: 'Eventually — Why Not Now?'

Typical of an expanding enterprise, it had a machine shop on the ground floor, radio assembly facilities on the floor above and a laboratory in a first floor extension 'out the back'. In summer, Arthur recalls that the lab was "as hot as Hades", trapped as it was between a galvanised iron roof above and coke ovens below operated by the manufacturer of 'Bonzer' automobile leaf springs.

Arthur knew about the annexe, because he would seem to have become a kind of technical 'handyman', poised somewhere between the lab staff and production.

The problems were gradually sorted out, however, and five test booths were installed, double screened with chicken wire — three for production testing and two for the lab, which had been relocated in what had originally been a showroom.

Reminiscing about traditional Australian radio factories, Arthur observed:

"Blokes like Alan McKeown in the final test rooms were usually very good technicians, not necessarily certificated but very experienced. Arguments between them and the lab most commonly arose because designers didn't make sufficient allowance for cumulative tolerances in production components."

"Final testers had to sort things out when particular chasses tended to come off the line unstable, because factors enhancing the gain met up with unduly low tolerance bypass capacitors."

"The testers tended to complain that 'It's one thing for you blokes to build up a couple of prototypes — it's quite another when we have to mass-produce hundreds of them'!"

That's what Arthur Spring was about when war broke out in 1939. Along with many other manufacturers, Breville was informed that their expertise and facilities would have to be re-directed to meet defence needs, and that their key employees would be provisionally classified as: 'in a Reserved occupation'.

At a purely personal level, this suited Arthur Spring. In personal conversation he told me that he had never been interested in subjects like astrology or religion — being, in fact, an atheist. He was also a pacifist at heart and could generate

no enthusiasm for a 'foreign' war. This, despite the fact one of his brothers was an Army officer. Defence of one's country was one thing; a shooting war about European politics was quite another!

At Breville he was in a reserved occupation. Better still, he became involved in a group required to develop and produce mine detectors for the Australian Forces. For him, any personal conflict had been resolved; he was helping the war effort, not by destroying people but by decreasing their chances of being maimed or killed. He was also engaged in practical technical research. More about that later.

Radio production under wartime conditions posed some weird problems, particularly when they were called upon to produce a quota of civilian and/or welfare receivers without absorbing scarce raw materials. Ganged tuning capacitors were a case in point, where they had to stamp the plates from zinc rather than fine gauge aluminium. The increase in mass was such that they would tend, in the presence of vibration, to rotate heavy section down — thereby re-tuning themselves towards the low frequency end of the band!

Spring's electric car

Arthur's interest in technical projects was underscored in 1942 by his decision to build himself an electric car, (a) to discover whether it was practical and (b) to sidestep civilian petrol rationing. His starting point was an old Fiat, the likes of which I well remember from my own youthful past.

Arthur replaced the petrol engine, gearbox and radiator with a specially wound six horsepower electric motor, driving the layshaft by cogs and chain. Reversing was achieved by switching the polarity of the motor feed.

He stripped off most of the bodywork to save weight, and rearranged things to accommodate an array of lead-acid accumulators. How many and how he came by them is not part of the story, but he did reach one important decision.


He could have connected them in series-parallel to provide a low voltage (e.g., 48V) high current supply, but the efficiency of the system would have been compromised by resistive losses in the cables, the connections and switching.

So he decided on a series connection, giving him a high voltage (nominally 200V) lower current system, with a motor to suit. A further consideration, I gather, was that, with care, a high voltage battery bank would be easier to charge from the AC mains that one demanding a massive step-down transformer and rectifier...

Put to the test on a (then) gravel road between Five Dock and nearby Haberfield, the electrified Fiat whipped up to around 60mph in no time flat — being faster off the mark than his father's V8 Ford!

Having spent some of my own youth riding around in 501 and 509 Fiats, I can assert that the only way they would normally ever reach such a speed would be downhill with a tail wind! What's more, such were their sluggish cable brakes, that the driver might then have needed uphill and a headwind to stop within a respectable distance!

Arthur had known beforehand that back EMF could pose a problem, especially at the instant when, at speed, the motor was disconnected from the batteries. With no batteries to peg down the voltage, residually energised fields and the rotor spinning at speed, the back EMF — in Arthur's words — could build up to "thousands of volts".



An obvious indication of the enthusiast element in the Breville lab — an FM tuner based on the American 'Pilot' design, but intended for use on the ABC's 'experimental' FM channel.

On one memorable evening, Arthur was doing his thing on the gravel track when the copper stop-go switch that served as an accelerator arced across the gap and welded itself 'on'. The 'flying bedstead' was out of control, drawing 36A and hitting 58mph without effective brakes!

Arthur had provided for just such an emergency with a knife switch on the facia. The trouble was that when he reached across to 'save his neck', the resulting arc fried his fingers...

He subsequently tried various tricks with carbon block make-before-break contactors, but in the evening shadows, the 'naked' electric Fiat's progress through the streets of Five Dock was still marked by "more sparks and arcs than a Bondi tram".

The motor didn't like the peak currents, either, and he tired of having to repair it. All told, at that point in time, an electric car was judged not to be an attractive proposition, so he settled for a Morris Minor and a motor bike running on whatever petrol he could get.

Whatever else he learned from the experience, Arthur didn't need any formal lessons about the reality of the back-EMF effect, no matter what the academics might say about the terminology.

Mine detectors

Back at Breville, Arthur remembers the day when a rather talkative man made his appearance with "an idea that might be of interest to the Armed Forces". At the time, Rommel was trying to battle his way into Egypt, while the Allied Forces were just as keen to push him back the way he had come.

Both sides had planted landmines in the desert, with the result that it had become a very dangerous place to venture. Invisible under a few inches of sand, the mines were a major hazard to vehicles, animals and foot soldiers alike.

The talkative one had worked out that it might be possible to detect the mines with the aid of an electronic search coil that would react to the presence of a metallic object under the sandy surface. It would alert the operator by changing the pitch of an oscillatory tone or a heterodyne whistle.

Army officers he had spoken to were interested, but not to the point where they were prepared to put the proposition to the Department of Supply. Perhaps Breville could have a look at the idea 'unofficially' and see whether it might be practical. Why not? So the idea was referred to 'the blokes in the lab'. Initially that boiled down to a certain non-academic but inveterate fiddler and experimenter: young Arthur Spring.

The talkative one had put together a prototype, using batteries and battery type valves which were accommodated in a pack meant to be strapped to the operator's back. The search coil was mounted on a separate wand with a lead plugged into the equipment, along with conventional pair of headphones worn over the ears.

It worked in a fashion, reacting to steel whatnots buried under the turf, but it was obvious to Arthur that a desert soldier might not want to walk around fully erect carrying a cumbersome back pack and manipulating a wand carrying a search coil. If shooting started, he would need to make himself as inconspicuous as quickly as possible — face down, flat on the sand!

In short order, mine detectors became

the subject of much discussion within the Company and with representatives of the armed forces both here and overseas.

Breville's prototype

In the ultimate, when Arthur assembled the Breville prototype, the probe coil and electronics were concentrated at one end of a stout telescopic rod and the batteries at the other. The weight was balanced so that the rod could be slung from a strap over either shoulder and manipulated with one hand or both. It could be dropped easily onto the sand and nudged along with the operator lying prone.

Arthur recalls that he became so involved in the project that he worked alone in the factory for 36 hours straight, over one weekend, interrupted only when the boss turned up with a bowl of hot soup!

Breville finally made up an experimental batch, which was despatched to North Africa by military air transport — a memorable occasion when the heavily loaded plane barely lifted off the end of the runway. ("Phew!")

Fortunately the prototypes made it to their destination and proved to be a practical proposition, well worth pursuing. Indeed, mine detectors were to feature prominently in Breville's future activities, and Arthur tended to specialise in them.

When the emphasis shifted from the Sahara Desert to islands in the Pacific Ocean, conventional landmines were replaced by Japanese anti-personnel mines. About the size and shape of a 'stubby', they were buried upright as often as not, under black wet magnetic sand which shrouded them from magnetic sensing. When triggered, they would jump up about a metre and explode, smashing ceramic marbles into a soldier in a body area where a man is particularly vulnerable!

Detectors had to be devised with a two-way switch for (a) magnetic sensing and (b) eddy current, phase shift effects caused by non-ferrous metal components. Assembled on a long telescopic rod, they were too heavy and awkward to be handled gently during a beach landing but were simply tossed over the side of the landing craft, then recovered and carried through the surf onto the beach, where they were pushed up the slope ahead of operators lying prone on the sand.

At the factory, the electronic unit was final-tested by being placed in a tub of water about four feet (1.3m) deep for a specified time. Any suggestion of bubbles would be interpreted as a leak and a need to re-check the sealing. Personnel mine detectors manufactured by Breville became standard issue to Australian troops under the classification: 'Detectors, Mine, Aust No.2, Mark 3'.

Other military projects

Yet another activity had to do with mines of the original under-sea type. Mine sweepers would patrol the sea lanes using paravanes with cables fanning from either side of the prow. The idea was for the paravane cable to collide with the cable anchoring the mine to the sea bed. Sailors on watch would rest a hand on the paravane cable to sense any such encounter.

It was a tedious job which demanded constant alertness and at Breville, Arthur was able to come up with a clamp-on magnetostriction microphone and amplifier system, which could 'listen' for scraping noises on the paravane cable and sound an alarm.

Amongst the other wartime projects at Breville which Arthur recalls was a general purpose multiband receiver ostensibly for use in Bren Gun carriers. Arthur was involved because of his background in shortwave communication, but during the course of its development, the emphasis shifted progressively to a general purpose role. The specification, however, still required that prototypes be suitable for installation in a Bren Gun carrier.

Arthur says that he can still remember the official visit to the specified Army Base in the quiet comfort of Bill O'Brien's Studebaker. The Bren Gun carrier would be waiting, antenna fitted and crew on standby.

On arrival, the receiver was bolted into place and connected to the antenna — a stout telescopic rod, nominally vertical but free to flex any-which-way by reason of a rubber joint part way up from the bottom.


The route and terrain negotiated for the test run had to be experienced to believe. The Breville personnel had to hang on for dear life, and all the while the rubber-jointed antenna was whipping around their ears like a 'stockwhip from Hell'.

The receiver didn't fall to pieces, but that's about as far as it went. The Army covered the development costs, paid for the prototype and that was that!

They also expressed an interest in a multiband UHF receiver. Breville's Lab did the necessary development work at the Army's expense, but when the time came to place a bulk order, they decided not to go ahead with it. The reason, it seems, was that American radio equipment was appearing on the scene, inhibiting local military planning.

Along similar lines, Breville was requested to quote for equipment to monitor the landing beams serving Mascot Airport. If these were interrupted for any reason, the military wanted to know, without waiting to be told. This option, too, was not taken up.

By way of compensation, however, orders were placed by the US Armed Forces as, for example, timing equipment based on transmissions from WWVH in Hawaii. (*To be continued*) ❖



The Breville Mine Detector, largely the work of Arthur Spring, being demonstrated by his brother in Army uniform.


FORCE ELECTRONICS

RED HOT WINTER SPECIALS!

SET UP YOUR ENTERTAINMENT CENTRE AND HIBERNATE IN STYLE!!!

Avico 5 Channel Surround Sound Processor
"A real surround sound effect at a fraction of the cost!" was $129.95
THIS MONTH... ONLY $99

Surround Sound Centre Speaker twin 3.5" bass drivers matched with a sharp sounding 2" super tweeter in a ported and damped cabinet was $159.95
THIS MONTH... $129



NO NEED TO RATION YOUR TOOLBOX THIS WINTER!

2nd Digital Multimeter RED HOT $19.95!
normally $29.95

MJ2955 2N3055 both normally $3.50
NOW $2.95!

BU326 was $7.95 NOW $3.25!

ZSD350 ONLY $9.95!

BOTH FOR 199!

DON'T BUY ELSEWHERE WITHOUT CHECKING OUR PRICES!

READER INFO NO. 3

FORCE Electronics S.A.

8 Locations Across Adelaide

- Adelaide - 203 Wright St. Ph. (08) 212 5505 Fax (08) 212 3979
- Lonsdale - 9 Somerset Circuit, Ph (08) 326 3331 Fax (08) 382 3366
- Brighton - 2/417 Brighton Rd, Ph (08) 377 0512 Fax (08) 3771440
- Findon - 127 Findon Rd., Ph (08) 347 1188 Fax (08)345 4746
- Holden Hill - 4/650 North East Rd., Ph (08) 261 7088 Fax (08) 369 1366
- Salisbury - 1700 Main North Rd., Ph (08) 283 0755 Fax (08) 283 0755
- Colonel Light Gardens - 584a Goodwood Rd., Ph (08) 374 3346
- Magill - 2/370 Magill Rd. Kensington Gardens, Ph (08) 332 2299

Order NOW by Fax (08) 212 3979

Delivery and Handling

Australia Post Surface Mail Packaging and Postage	
$30.00 - $49.95	$4.00
$50.00 - $99.95	$6.00
$100 - $149.95	$7
Over $150 -	Free


Overnight Service	
1kg - 3kg	$10.00
3kg -5kg	$17.00

Over 5kg - by Road Service
Allow 2 Days to Major Cities
Perth allow 4 Days
Country Areas one additional day

Cheque, Money Order, Bankard, Mastercard, Visa, Amex Welcome

FORUM

Conducted by Jim Rowe



Should electronics technicians be paid more than street sweepers?

As promised last month, I still have a couple of reader responses on the subject of microcontroller-based projects, and I'm presenting them here. There are also some letters following up on other recent topics. But there's been a particularly sobering letter in response to my editorial in the February issue, on the subject of career opportunities in the Australian electronics industry, and because it raises an aspect that tends to affect just about all of us — wage and salary levels — I've decided to give it first kick.

In my February editorial, you may recall, I talked about the current and rather worrying trend in many firms away from permanent employment, on-the-job training and offering true 'career' opportunities. I suggested that this not only discouraged young people, but would turn out in the long run to lead to disaster for both the firms concerned and for Australia as a whole.

I went on to note that luckily there were still some firms, like advertiser Dick Smith Electronics, who *are* still committed to providing permanent employment, on-the-job training and true career opportunities. I felt this was worth mentioning, because at first sight many young people might not think that a distribution and retailing firm like DSE would offer many career opportunities for young people interested in the technical side of electronics — when in fact they do.

Anyway, it seems that this particular editorial managed to hit a raw spot with at least one reader, who sent in the following rather sobering and thought-provoking letter. The reader concerned has supplied their full name and address, as a sign of good faith, but in view of the comments made have asked that I refer to them merely as 'P.R. of Crows Nest, NSW'.

Without further preamble, then, here's what P.R. has to say:

I read with interest your February editorial suggesting young electronics technicians consider a career with Dick Smith Electronics. Certainly I have found most of the staff at DSE and Jaycar, to name just two, friendly and often surprisingly well informed. It does appear a good career start.

However, your editorial touched a tender nerve. I have reached the stage of not recommending electronics as a career to anyone who intends living in Australia, unless they have firm plans of running their own business. The reason is simple. There's just no money in it!

Having recently returned to Australia after many years abroad, I am shocked, surprised, and quite angry at the pathetic wages offered to electronics personnel, whether as technicians or qualified engineers. During my time overseas, I worked in no less than ten foreign countries as basically an electronics technician. In all these areas I earned a very reasonable living — not rich, but well off.

But upon returning to Australia, I find wages for technicians and engineers have remained at a stagnant level for seemingly the last ten years, whilst the wages of most other types of career have risen somewhat with the cost of living.

Here I found it hard to get any sort of electronics work at over about $30k per year. This is poverty level in Australia, and most especially so in Sydney where rents are high and everything is more expensive. Here I see examples of our finest engineers and technical staff, the CSIRO for example, and other research establishments, getting a pittance compared to their colleagues overseas.

I think we have a compound problem in Australia, concerning all types of engineering personnel, electronics and other. For a start we have a 'cultural cringe' regarding our abilities. Despite being hailed, and justly so, as an inventive country, we maintain the attitude in Australia that anything invented overseas must be better. We are constantly bringing in overseas 'experts' to do the 'difficult' jobs for us, when there are plenty of Australians far better trained, and with far more knowledge, right here. Bringing in American 'oil experts' to Bass Strait is a typical example.


We also have a severe problem of 'image'. Hollywood movies are much to blame for this, stereotyping engineers and technicians in movies such as James Bond. Technical personnel in 'weapons research' laboratories are portrayed as eccentric bumbling buffoons, brilliant scientifically but devoid of any social graces, inept in speech, dress and manner, prone to dribble...! We've all seen the 'mad professor' image, the goofy-like technical assistant.

Technician = 'Mr Fixit'?

On the other end of the scale, many in the public indentify 'technician' with 'toaster repair man' — the poorly educated 'Mr Fix-it', who puts plugs on lamp cords, or at best is good at cleaning telephones. Who amongst us hasn't had a faulty transistor radio or fax machine thrust upon us by the dreaded relatives, or a neighbour, when you actually work in Nuclear Science?

A further problem exists, due to our mostly British origins. Not so easily detected perhaps, but there nevertheless. It stems from the English upper class attitudes prior to WWII, that people in 'trade', or engineering people, were not really 'sociably acceptable'. Shakespeare even used the phrase — 'the crude mechanical'. Engineers were nasty messy people who were always covered in dirty grease and oil from their infernal machinery.

Certainly whilst I was at Sydney University in the '60s, engineering students were regarded as 'lacking' in social status. I believe the popular



term now is 'Nerd' — yet another stereotype image, destined for people who like computers.

Well, having worked in all sorts of engineering fields, including research laboratories, I can vouch that these images of technical people are wholly unjust. In the main I see people so dedicated to their work, with a love of electronics and science, that if there is any complaint to be leveled, it's just that they are often too busy to worry much about money. Most know that unfair advantage is being taken of them, but we've never been an aggressive bunch and tend to avoid conflicts about wages.

As a result, we've been left far behind in wages upgrading. I believe, and I hope, that will change in the near future. Already our universities and colleges are noticing a severe downward trend in applications for technical courses. It will be a great loss to Australia if we lose any more of our engineering and technical skills.

What a society! We'll pay our most looney politicians well over $100k+++ per year, local GP's (doctors) are getting depressed at a miserly $80k, yet we begrudge a research scientist, working on increasing world food production or developing amazing communications technology, or yet another wonderful medical technology breakthrough, a mere $40k and often lower wages.

All of those who don't agree with the above can immediately throw away that mobile phone, Walkman, CD player and hi-fi, the TV and VCR, your hearing aids, pacemakers, bone growth stimulators, marine radios, communications systems, satellite links and computerised motor controls for you car. Who do you think invented them?

By all means choose an electronics/scientific career if you must. But besides four to five years of hard study to become either a technician or engineer, it will take up a great deal of your time in constantly upgrading your knowledge, taking further education courses, and lots of home study, just to keep abreast of technology. And you may end up being paid peanuts for your pains.

As a final word, I suggest a study of the popular newspaper job advertisments over the coming weekends. I almost gave up looking for electronic work when I came across an advertisement for a 'Labourer/Street Sweeper', that offered better wages than many of the electronics positions.

Well, there you are: a cry from the heart, if ever there was one. Thanks for your letter, 'P.R.', and you certainly raise some very pertinent questions — not just about the salaries and wages of technical people working in the Australian electronics industry, but about the low status and recognition afforded to a great many of our scientists, engineers and technicians in general.

I don't think anyone would argue that this lamentable situation exists, or that in the long run it's going to prove a serious problem for our country. The real question, I think, is what on earth we can *do* about solving the problem...

I'm aware, for example, that virtually the same situation applies regarding our teachers, and also our nurses. Both of these professions have a high percentage of truly dedicated individuals, who gain a great deal of personal satisfaction from doing their job really well — but in both cases their modest status and meagre salary levels are far below what would be appropriate and just, in view of their true importance to our society.

How have *these* professions tackled the problem P.R. raises? As far as I can see, only by raising public awareness of the iniquity of their position, and also by being prepared to take industrial action, if necessary, to gain improvements in salary levels. Unfortunately industrial

action also tends to detract from their 'professional' image in the public eye, but this is perhaps a tradeoff that must be made, at times...

Mind you, it seems to me that even taking these steps, these professions have actually made very little real headway — either in terms of improving their status or in raising their salary levels to a just level. So perhaps these tactics aren't likely to achieve a great deal for scientists and electronics people, either. Still, if anyone has discovered a better way to raise the status and salary levels of all of these vocations, I'm sure we'd all hear it.

I certainly agree with P.R. that it seems crazy, and a potential disaster for the future of Australia, when higher salary levels are being offered for labourer/street sweeper positions than for electronics technicians.

CD compatibility

Important though this subject is, though, let's leave it for the present and turn to another letter that came from Mr Peter Hanicek, of Brisbane in Queensland. Mr Hanicek is adding to the discussion of compact disc/CD player compatibility problems and their causes, first raised by Gerard Lawrence in the December 1994 issue and since then addressed by others in the March, July and December 1995 issues, and more recently in the March column by Keith Walters.

Mr Hanicek adds another possible cause to the problem of CD players that won't play some discs, based on his direct experience:

Regarding CD players and a possible cause of disc incompatibility due to TOC (Table Of Contents) loading problems, my specific fix for this fault with my own CD player hasn't been mentioned yet, so I've decided to write, for your interest if anything.

I had a problem with my Technics SL-P2 CD player purchased new back in 1986. This player would not load half of my CD's — i.e., it failed to recognise the CD at all and had been written off by the company's servicing centre. As a technician of sorts, I decided to have a look myself.

In this player the laser servo head assembly is driven along two rails by a belt driven motor. At either end of these rails is a leaf-spring type make contact switch, which tells the electronics that the laser head has reached the end of the rail. What I found was the switch at the spindle end of the rail was incorrectly adjusted and this was preventing the laser head from getting sufficiently close to read the innermost tracks. This wasn't visibly obvious.

The adjustment was simple and to date the player has never faulted since, with any CD purchased.

Thanks for your contribution, Mr Hanicek. I for one found it particularly interesting, because it was exactly this kind of fault that I originally suspected might be responsible for those mysterious compatibility problems. I wonder how many of the problems are due to similar 'misadjustments' in other players?

Fax modem compatibility

Moving on again, though, another reader has sent in a contribution to the topic that Tom Moffat first raised in his article 'Formulas for Fantastic Faxing' in the September 1995 issue, regarding the performance of computer fax modems in comparison with dedicated fax machines. You may recall that a reader commented on this in the March column, and was very critical of the simplified line interface and lack of adjustable equalisation used in many fax modems.

The new response has come from Mr H. Jansons, of Wynnum West in Queensland. Mr Jansons works for Telstra, and as you can see he basically seems to support the points made by our first correspondent:

I have just been reading the item 'Fax modem performance' in the Forum section of the March 1996 edition.

I am employed with Telstra. A few years ago I was involved with a Section which investigated technical problems associated with customer complaints and, amongst the many problems investigated, fax problems had their fair share of complaints. This Section had Groups in each of the States and a number of these became specialist in a particular field — with the Sydney group, along with its specialist equipment, becoming renowned for being in the forefront of fax operations and knowledge.

Of the many fax complaints the Telstra troubleshooting Group investigated, the majority was due to exactly the symptoms that your correspondent from South Australia stated — poor equalisation to the cable, incorrect signal levels, mismatched impedances, etc. All led to signal distortion and hence corrupt data, with the result being poor quality faxes. All major fax equipment suppliers eventually realised, just like your correspondent's company, the importance of correct setup. Now they provide a setup service as part of the purchase of a fax machine.

Granted there were pockets of poor telecom cable. However, most of this has now disappeared with the modernisation of the network, upgrade of customer cables, customers being more discerning about their telecommunication needs, and Telstra being more customer responsive.

This leads back to Tom Moffat's article 'Formulas for Fantastic Faxes'. What type of subscriber network have the fax/modems been designed for? (The cable impedance is more complex than just 600 ohms.) Can these modems be better matched to the cable, and how can this be done without the need for sophisticated test equipment?

Maybe you can arrange to discuss this matter with one of the major modem producing companies.

Thanks for those comments too, Mr Jansons, and it's interesting that the findings of the Telstra group agree so well with the points made by our first correspondent. There doesn't seem much doubt that some of the fax modems are either incorrectly adjusted, or incapable of being either properly matched to, and/or equalised for the telecomm line.

I suspect that by now it should be possible to make modems that are capable of performing their own automatic setup, to achieve optimum operation on a given line. I'll try to find out whether this is the case, with some of the newer models.

More on micros

For now, though, let's return again to that topic which has obviously proved so thought provoking — whether or not magazines like *EA* should describe more microcontroller-based projects, and whether we should provide full source code listings when we do. This was launched in the January column, you might recall, and we've published quite a few responses since then. But as I mentioned last month there are still a couple to show you, and their time has finally arrived. Sorry for the delay!

The first comes from Mr Mark van der Eynden, of Ferntree in Victoria. Here's what Mr van der Eynden has to say:

Please allow me to respond to your December '95 EA Forum 'Why Doesn't EA publish more micro-based projects — with full source code'.

I tend to agree with much of what is said by both parties, but I can not agree

with the kit supplier viewpoint. Surely stocking a preprogrammed chip is the same as stocking an XYZ special function chip as used in the ABC project. It could even be more effective for the kit supplier to stock the blank chips, arrange with the author to pay as they copy them, and then produce the ABC and DEF programmed chips as demand dictates...

Now for my main point. I feel a circuit diagram is analogous to a firmware listing and a circuit description is akin to a firmware description. Therefore publishing a 'programmed chip' article without a firmware listing is the same as producing a new 40+40W amplifier design in which you only get the circuit diagram for board A, the main amplifier. For board B, the preamplifier, you send away $$$ to the author, who returns to you an epoxy'd black box with a 10-pin edge connector to plug into board A. Now where is the fun in that?!

It is as interesting to see how and why a piece of code causes a relay to fire, as it is to trace a circuit for the same reason, and I feel it would be advantageous for EA to publish and describe the function of both. I hope I can describe a method whereby everybody can be happy.

There seems to be some misconception as to what happens to copyright when firmware is published. Many seem to think that the copyright then becomes non existent. This is not so; the writer may release all copyright restrictions, but then again they may retain all copyright and/or apply a caveat to the use of the published material.

I would suggest that the firmware is printed with a caveat along the lines of the following: 'This firmware listing is published for the purpose of allowing home constructors to better understand the function of the project. If the home constructor wishes to create his own EPROM from this listing, they must retype the listing (i.e., no scanning) and produce only one EPROM from each typed copy.' The listing should not be available on the Bulletin board and EA may half-tone or shadow the listing in such a way that it cannot be scanned.

Home constructors will have their listing and they will probably decide that the $20 (say) premium they are paying for the pre-programmed chip is money well spent. This will not stop the illegal mass copying of the firmware, but nothing will. If you want to mass copy the firmware, you can always buy one chip from the author and start from there. I know there are copy protected chips around, but that seems the same as making epoxy'd black boards to me. If you can't guarantee replacement chips will be available for the life of the product, you are being quite unscrupulous.

As for publishing the listings, you could get about 400 lines per page using the smallest font you currently use. I'm sure the average reader will not mind if you use an even smaller font that may require a magnifying lens to read easily. The author, of course, should be entitled to a payment for the publication, at a rate lower than the article's word rate.

Thanks for your comments, Mark, and your approach is an interesting one. I see your point about a firmware listing being analogous to the schematic diagram for a hardware circuit, and it seems pretty valid. However I'm not sure how many readers would be happy with listings in a font and point size that let us squeeze 400 lines of listing into a page. Those that were interested would probably complain that it was too small to work from, while the rest would probably think it was still taking up too much space!

And finally, but by no means least, here are the comments that arrived from Mr Dennis Chuah of Riccarton, in Christchurch NZ:

I am writing in reply to your comments in the Forum column in the January 1996 issue. I agree with Mr Olsen that micro based design is becoming more important in electronics design. In fact, I would go one step further and suggest that most modern electronics designs involve the use of at least one micro, from washing machines to Walkmans. The reality is these designs provide better maintenance, more reliability and more flexibility (only firmware needs to be changed instead of hardware).

Take for example, modems. Most 9.6kb/s modems can be upgraded to run at 14.4 or 28.8kb/s just by upgrading the firmware. In fact, electrically, a 9.6kb/s modem is actually a 2.4k baud modem. The only difference is in the firmware. The faster modems employ a stellar I-Q encoding.

It is also easier to 'shrink' a micro based design than one using conventional logic.

I am a regular reader of your magazine (though not a subscriber yet). As such I am on the side of the argument that your magazine should provide more micro based projects. I feel there should be fewer or none of the projects that require specialist parts. Microcontrollers are readily available, and very

(Continued on page 67)

YOU CAN AFFORD AN INTERNATIONAL SATELLITE TV SYSTEM

For years you have probably looked at international satellite TV systems and thought "one day"



YOUR OWN INTERNATIONAL SYSTEM FROM ONLY:

$2300

PAY NO MONTHLY FEES

For Gorizont, Rimsat, Panamsat, Asiasat II, Palapa C1, Apstar 2R*, Intelsat

Programming available from Russia, India, China, USA, Asia, Indonesia, Tahiti, Phillipinnes

HERE'S WHAT YOU GET:

- 400 channel dual input receiver preprogrammed for all viewable satellites.
- 2.3m perforated sheet antenna
- 20°K LNB
- LNB cover
- High efficiency feedhorn
- 25m coaxial cable, with connectors
- Analogue multisystem converter
- Fixed elevation & azimuth rods.

BEWARE OF IMITATORS

Direct Importer: AV-COMM PTY. LTD.

PO BOX 225, Balgowlah NSW 2093
Tel: (02) 9949 7417 / 9948 2667
Fax: (02) 9949 7095

YES GARRY, please send me more information on international band satellite systems.

Name: _____

Address: _____

_____ P'code: _____

Phone: (_____) _____

ACN 002 174 478

READER INFO NO. 4

THE SERVICEMAN

The serviceman who made a temporary repair — to one of a set's integrated circuits!

In the days of valves, and even discrete transistors, it was often possible to make 'temporary' repairs to equipment when the correct replacement parts were not available, to keep it going until the correct parts could be obtained. In most cases such repairs are well-nigh impossible, in these days of large-scale IC's; but one of our stories this month concerns an unknown serviceman who managed to make a temporary 'repair' to an IC — and in a novel way...

The first story for this month comes from one of our long-time contributors who wishes to remain anonymous. It's from L.K., formerly of Daintree in the far north of Queensland but lately of Mudgeeraba, also in Queensland but far less north.

In his covering note L.K. comments that he has now reached retiring age and that this is likely to be his last contribution for some considerable time — if not the last for all time. Which saddens me, because L.K. has been one contributor who could be relied on for a good yarn, consistently well told.

As well, most of his stories contained a hearty chuckle, such was his great sense of humour. We are going to miss L.K. — but then, as he says, old servicemen don't die, they just lose their scope!

Read this story, then, and see what you think of L.K.'s scope:

It is the unusual that makes a story, and this one originated with a tourist requesting service on his NEC portable, an N1423 which has suffered vertical failure. My customer explained that the set had, as he put it, 'done this' a couple of months earlier.

A serviceman he had consulted earlier in his trip had examined the set and advised the owner that an IC needed replacing — which he would have to order in, as this make was not one for which he carried spares.

This arrangement apparently didn't suit the owner, who expressed a wish to keep moving. A discussion ensued, ending with the said serviceman suggesting he might effect a temporary repair but could not guarantee how long it would last.

This was accepted and the TV had been more or less satisfactory until now. He believed that this original fiddle must have finally failed as the set was again exhibiting the same symptoms.


When he departed, I returned to my coffee to ponder just what sort of a temporary repair might have been carried out to an IC, especially in a hurry. As they say, the mind boggled!

I popped the set on the bench, removed the back and this being a live chassis, plugged into the isolation transformer. The owner's description proved correct — not a sign of any vertical movement.

As the oscilloscope was handy, I flipped the switch and began looking for some useful spot to prod with the probe. The yoke socket caught my eye and investigation here showed plenty of signal. The outlook was not so sunny. If this point was OK, it didn't leave much to be faulty but the yoke itself.

Disconnecting the plug, I attached a multimeter directly across the vertical terminations. It was as open as a mouth at the dentist! If this had been the site of that temporary repair, the owner must have got his terminology awry. That's not uncommon and sometimes entertaining.

Further inspection revealed a break in one of the wires where it emerged



from the lower winding; a casualty no doubt of the constant vibration. Fortunately, there remained about 10mm of wire for me to accomplish a repair — although being at the bottom between the tube neck and the chassis left me little room to manoeuvre.


After this, the remaining leads were checked for signs of future trouble before putting a dollop of silastic on the joint to hold it firm against the windings. What lingered was an uneasy feeling when I could find no indication of any previous work in this area.

Plugging the TV back into the isolation transformer, I nevertheless expected to see a successful result. But it was not to be — there was still no vertical action.

By this time the CRO had been shifted

Equalize..

..up to seven TV channels with 42dB UHF gain, inputs for Sat. and FM, and auto. level measure for around $350 plus tax. New Alcad 905C.



Peter C. Lacey Services Pty. Ltd.
80 Dandenong Rd. Frankston VIC. 3199
Tel:(03) 9783 2388 Fax:(03) 9783 5767

READER INFO NO. 5

to another part of the workshop to monitor an intermittent problem and there was some delay in bringing it back to bear on the job in hand. Just as things got organised, a picture appeared, rolled a few times then locked solid — as good as anyone could wish for.

At this point I erred in a direction which would cost me a lot of time. Still suspecting a yoke problem, I decided to let the beast cool down but keep the scope running and connected to the output stage, so when the set was powered up, I could check immediately for drive.

Unfortunately, each time I pressed the button the set started without hesitation. Since it had now passed closing time, I elected to call a halt until the morrow.

Now we come to the first turn-on next morning, and there it was — no scan. A few moments probing established that there was no signal either, into or out of the final transistor pair. But before I could work my way back to the oscillator chip, it was up and away!

Again I shut it off, then set about locating the right IC, to be on the spot when next it chose to have a rest. And it was here that I met up with that elusive 'temporary repair'.

The oscillator turned out to be part of C701, a 48-pin multifunction gadget. At first sight it appeared to have a hornet's nest on the upper surface, but a closer look revealed something more akin to automotive body filler.

What made it even more interesting were the wires which emerged from either end and meandered over to the HOT side of the AC power switch! Whatever this nest was, it was connected directly across the mains. Not an NEC original, and definitely not an official mod...

The substance proved to be quite hard, preventing easy investigation of the innards. However, a check with the ohmmeter gave a reading of nearly 60kΩ, so assuming it to be a resistor, I sat down with a cup of stimulus to ponder the puzzle.

A quick calculation suggested it would dissipate about one watt as heat. After that, to quote a cliche, the penny dropped. I disconnected the 'thing' and tried the set again. This time the oscillator failed to function for quite a while.

In review, it would appear that the original fault had been heat sensitive. the vertical section of the chip would only work after reaching some critical temperature (a bit like aged servicemen?).

Also, it very probably developed the fault in a cooler climate than in far



north Queensland. Thus the previous repairer, having become aware of the problem and not in possession of a replacement, had cobbled up this 'practical solution' and thereby salvaged a fast-fading fee.

He would also have anticipated that the TV would not be switched off at the power point, thereby keeping the IC warm continuously and ready to perform whenever called upon. Though how long such an arrangement was likely to remain successful is anybody's guess!

On the owner's return, he received a full run down on my findings, complete with the strong recommendation that the faulty component be replaced. I happened to have the IC in stock and quoted what I felt was a very reasonable price to do the job.

Alas, he declined the offer, pleading that as the temporary fix had proved reliable for a month or two, he saw no reason why it might not see the set out. I wished him luck!

Finally, some words of warning to those other servicemen out there. I'm currently investigating patent rights so if, one day, you are confronted with an NEC with built-in chip preheating, remember that L.K. saw it first!

Well, L.K., that is a real humdinger. It also suggests to me that the legendary Aussie bush ingenuity has not died out altogether with the coming of modern technology. Who else could devise such a simple cure for a faulty IC? I mean, who could devise *any* sort of repair for an IC?

Of course, our mystery serviceman was lucky in one way. Most heat-sensitive faults show up only when the equipment is hot. Hence the popularity of the can of freezer spray. Not often do you find one that goes the other way. What would he have done then. Built a little fridge on the chip? Can't you just imagine it!

Thanks for that story, L.K., and I sincerely hope that it *won't* be your last. Why not make the acquaintance of your nearest friendly serviceman and write up his stories for the column? We all look forward to hearing from you again.

Mysterious drift

Now we go across the Tasman for another Kiwi story. This one comes from Graham Cheer, of Tauranga. We have heard from Graham before, with stories about ancient calculators and antennas that didn't work too well. This time he's working in the meat trade — what a variety of jobs this man has had!

No, Graham's not a butcher in this story. It's much more technical than that. Here's what he has to say...

This story is from about 1976, when I was involved with the installation of data logging equipment for temperature and humidity monitoring in the meat industry.

It was actually part of an R&D problem as we had designed solid state analog multiplexers for the temperature sensors, to replace reed relay switching — which caused inaccuracies due to the resistance of the reed switch contacts increasing with age.

The sensors being used were platinum wire type resistance sensors where the resistance at 0° Celsius was 110Ω with a negative temperature coefficient. To measure the resistance, a constant current is passed through the sensor and the voltage drop across it is measured. The voltage reading is proportional to the resistance and this, of course, is proportional to the temperature.

In the reed relay system a current of 10mA was used, but it was found that if the sensor was left on for more than 10 seconds, the sensor warmed up due to the heating effect of the current through it and we got an incorrect reading. We reduced the current to 1mA, giving an output voltage of 110mV at 0°, and found that the heating effect was then negligible.

The multiplexers we designed used what was then the newly introduced 4000 series CMOS ICs, and we used the 4016 quad analog switches. To overcome the 'on' resistance (up to 300Ω) of the 4016, we used two

switches per sensor, one to connect the constant current source and the other to connect the low pass filter and A to D converter.

Tests in the workshop showed that the whole system gave very stable readings, but on a real site we found we were getting drift errors of upwards of 2 - 3°. We eventually traced the problem to electrical noise on the sensor cabling being rectified by the protection diodes in the 4016 switches. This placed a DC bias on the line, over and above the constant current source.

The answer to the problem turned out to be quite simple. All we had to do was to separate the digital ground voltage (Vss) from the analog ground. We did this by changing the CMOS power supply from a single ended 0-15V to a split rail of +/-7.5V. This meant that the noise on the line had to exceed 7.5V to cause the protection diodes to conduct. We found the worst case noise never exceeded 2V.

All the installations from then on were fairly straightforward and proved to be very reliable.

Well, there you go! I wonder how many times induced electrical noise has been added to the desired signal information in an analog measurement situation. I can imagine that it has been and probably still is a problem in the automotive world. Just think of all the sensors in a modern car — all of them analog and all susceptible to electrical noise.

It was something I hadn't given much thought to until I read Graham's story, and now you know all about it too! Thanks, Graham. That's the last of your stories to hand, but I don't think it will be long before we hear from you again.

'Too late to help'

Our third contributor this month is Brian Byrne, of Indooroopilly in Queensland. I gather that Brian is a bit peeved that I didn't present a particular story a month earlier. Sorry about that, Brian, but if I had written earlier, you'd most likely have forgotten it by the time your story came about. I think we are all much the same that way. Anyway, here's Brian's story...

This month the Serviceman has really struck a nerve — No! Don't stop me and I'll tell you how.

A few weeks ago I visited a nearby residence whose owner was moving across town. Everything had to go! I spotted a Sanyo CTP3621 (Yes! You guessed it, page 44 in EA for September 94) among the items that 'had to go'. Seeing me viewing it, the owner said "Oh, that's junk! Nothing works in it — it's yours for a couple of bucks". Well, at that rate, a few spare parts from it could be worthwhile so I lugged it home...

A couple of days later I plugged it in and switched on. Nothing — perhaps a tiny whine, but not from the speaker. I soon had the back off, only to find it



was a live chassis switch-mode type. I plugged it into an isolation transformer/voltslider (variac by another name). I've found it causes much less death and disaster that way.

I wound the volts up, but there was only that faint whine — sounded a bit like an inverter being kept low by a short circuited load. I turned it off and tried the most likely short circuit: the horizontal drive transistor. Yep, it was past tense.

On digging around in a bottle of miscellaneous transistors, I found a close replacement and fitted it. Then I turned the set back on and the new transistor worked — for about 4-1/4 seconds. There was a click from the horizontal transformer as the drive transistor joined the official junk collection. A voltmeter monitor on the HT rail had shown excess volts for the electrolytic rating, while it worked.

At this point I would have saved myself a lot of heartache if I had given up, but the set looked clean and neat — so I was hooked. It was off to the dealer for a photocopy of the circuit; but before actually applying the circuit to the brain, it seemed like a good idea to replace the half dozen or so fiddly little electrolytics.

Curiously, on the circuit somebody had ringed C314 (47uF) with a note 'PX flashes, HT unregulated'. Unfortunately, this was one of the fiddly items I had already replaced.

With a new horizontal drive transistor in place, I snuck up on the voltage and the beast worked 100% — at 150V AC input. Obviously the error amplifier/regulator system (so well described by your Serviceman, but too late; I'd already fought this thing two weeks before) was not doing its job.

First, I tried the three transistors — taken out and tested, but all with lovely high betas. They seemed unlikely culprits anyway. I flitted the ohmmeter across the 10 or 12 resistors and pots, and they were all OK.

So what now? There wasn't much left! The diodes all 'dioded' on the ohmmeter. Finally, there was only the zener reference...

Now, I'm a fumble fingers from way back. With one hand holding the voltmeter prod and one on the AC voltage control — yep. My finger slipped and the meter prod shorted the zener to the base of the third transistor. There was a small 'POP!' and the set stopped. The zener now tested dead. So fumble fingers had written off another component...

On reflection, it seemed odd that such a small current source could kill a healthy zener, so it was probably faulty all along. I fitted a new one, and wound up the supply. It worked 100%, just like new. Lovely! And fumble fingers had found a defective zener by the new fumble technique.

So that's how your story touched a nerve — a sore one!

Well, Brian, I'm sorry that you had so much trouble with the old Sanyo. It's not such a bad set to work on, but that zener does seem to be a stumbling block. I've made a note to check that item first time, every time. I may never strike the problem again, but I will be forewarned. I hope you are too!

There was just one problem I had with your story. Are you sure that your 'voltslider' was truly isolated? Most variacs that I've had anything to do with were only simple auto-transformers without any isolating properties. I'd be most upset if your comment led one of our readers to misuse a common variac, with possibly fatal results.

The safest course is to never use



any Variac as an isolating transformer. That way there can be no mistakes...

Thanks for your contribution, Brian. I hope the old Sanyo goes on working well for you, like the one in the following story.

Melted set: the sequel

Back in February 1982 I wrote about a Sanyo television set that had been severely damaged in a fire. The plastic cabinet had melted and run all over the picture tube and onto the chassis. The power switch was buried in a mass of melted plastic and the picture tube was leaning over at a crazy angle, resting on the front edge of the chassis. It was a mess!

The amazing thing about it, though, was that the set still worked. After we had chipped the front panel off the power switch and found the antenna socket among the ruins of the cabinet back, we were able to watch a first class picture.

In the 1982 article, I mused "I wouldn't like to guarantee the set. It might run for a few days or a month. But it is amazing that a TV could suffer such extensive damage without obvious internal faults of one kind or another. I don't think the set will ever be restored, but it is an interesting relic just the same."

I had no idea just how wrong I was going to be!

I gave the set to my colleague who teaches colour TV at the local Technical College. I felt it would be a good example for his students and it well served that purpose for the rest of that year.

When the school year ended, my friend took the wreck home, believing that it wouldn't last over the holidays at school. Somebody would decide it would be OK in their holiday shack and of course, it would never come back to the college...

Time passed, and I had completely forgotten about the old set. Then last week I was visiting my friend and the talk got around to complicated and dramatic TV repairs. My friend told of this set that had been burned and the melted plastic and all. The subject sounded familiar to me but I let him go on with the story.

It seems that he had a friend whose TV had broken down irreparably and he was told about the 'wreck that still worked'. The friend asked what it would cost to replace the damaged cabinet, and so inquiries began.

The upshot was that they bought a whole new cabinet from Sanyo and transferred the works into it. A few quick adjustments and they had a set that looked and worked like a new one.

The only internal part that had to be replaced was the loudspeaker. The speaker cone had taken the full force of a fireman's hose (admittedly from behind the grille) and although it still worked after a fashion, it was replaced to complete the restoration. That was toward the end of 1982.

It is now early in 1996 and the discussion with my colleague revealed that set is still going like a bought one. And what is more, it has not had the back off since it was reassembled nearly 14 years ago!

We tend to class TV sets among the more fragile of housewares — like china, glass, clocks etc. — and to treat them with relative gentleness. This story shows that 'the box' can be a lot more rugged and can tolerate far more abuse than you would ever believe.

The insurance company paid out on the old Sanyo for the original owner. But I have heard, indirectly, that he was not at all pleased with the later model bought as a replacement. I hope he never finds out that his first set is still going strong. I can't bear to see grown men cry!

Well, that's all for this month. I'm in the process of preparing an Index of all Serviceman articles from July 87 to March 96. This will compliment the Index covering January 75 to June 87, which appeared in *Electronics Australia* in January 1988, and will give you a ready reference to every subject that's been discussed in these pages since before colour TV started in Australia. Watch for it in the next few months.

Meanwhile, I'll be back next month with some more stories from the servicing bench. I hope you'll join me. ❖

ROCOM
ELECTRONIC COMPONENTS

SALE!! SALE!!

TRANISITORS

BC338	NPN 25V 0.5A 800mW TO-92 G/Pur.	$0.05
BC547B	NPN 45V 0.1A 500mW TO-92	$0.05
BC548	NPN 30V 0.1A 500mW TO-92 G/Pur.	$0.05
BC557B	PNP 45V 0.1A 500mW TO-92 G/Pur.	$0.05
BC559	PNP 30V 0.1A 500mW TO-92 G/Pur.	$0.05
BC877	NPN 60V 1A Darl.	$0.10
PN2907	PNP 60V 0.6A TO-18 G/P	$0.05
TIP29A	NPN 60V 1A 30W TOP-66	$0.25

REGULATOR

MC7805U	+5 1.5A TO-220	$0.30
LM317T	+ADJ 1.5A TO-220	$0.50
LM323K	+5V 3A TO-3	$1.50

INTERGRATED CIRCUIT

NE555	Timer CMOS	$0.25
LM324N	Low Power Quad Op. Amp.	$0.30
4011BRS	Quad 2-Input NAND Gate	$0.20
4013RS	Dual d Flip-Flop	$0.20
4028	BCD-to-Decimal Decoder	$0.20
4164B-12	DRAM 64K x 1	$0.40
4503	Hex 3-State Buffer	$0.20
4536	Programmable Timer	$0.20
74123	Retrig. M/stable Multivib.	$0.25
74154	4-Line to 16-Line Dec./Dem.	$0.25
74AHCT00	Quad 2 Input NAND Gate	$0.20
74AHCT08	Quad 2 Input AND Gate	$0.20
74AHCT139	Dual 1-of-4 Dec., Act. L/O/puts	$0.20
74AHCT164	8-Bit S/Input/Para. O/P S/Reg.	$0.20
74AHCT244	Oct. Buf/Line Drv/Line Rec.,	$0.20
74AHCT373	Octal D-Type Transp. Latch,	$0.20
74HC04N	Hex Inverter	$0.20
74HCT153P	Dual 4-Inp. Data Sel./Multi.	$0.20
74HCTLS01	Quad 2-In. NAND Gte, Open-Col.	$0.20
74HCTLS03	Quad 2-In NAND, Open-Col.	$0.20
74HCTLS155	Dual 1-of-4 Decoder	$0.20
74HCTLS20N	Dual 4-Input NAND Gate	$0.20
74HCTLS240	Octal Bus/Line Drv. Inver.	$0.20
74LS125A	Quad Buf., Low Enable, 3-St.	$0.20
74LS138N	1-of-Decoder/Demultiplexer	$0.25
74LS151	8-Input/Multiplexer	$0.20
74LS157	Quad 2-Input /Multi., Non Inver.	$0.20
74LS173	4-Bit D Register, 3-State	$0.20
74LS257A	Quad 2-Input Multi., Non-Invert,	$0.20
LF353N	Wide Ban. Dual JFET Inp. Op/Amp	$0.30

STOCK IS SUBJECT TO PRIOR SALE.

SURPLUS SHOP OPEN
FOR COUNTER SALES AT:
37A FENTON STREET HUNTINGDALE VIC 3166
PH. 03 9562 8896

ROCOM ELECTRONIC COMPONENTS
MAIL ORDER SEND TO:
P.O BOX 142 HUNTINGDALE VIC 3166
PH. 03 9548 9229 FAX. 03 9562 8772

WANTED EXCESS SURPLUS STOCK

READER INFO NO. 6

Circuit & Design Ideas

Interesting circuit ideas from readers and technical literature. While this material has been checked as far as possible for feasibility, the circuits have not been built and tested by us. We therefore cannot accept responsibility, enter into correspondence or provide any further information.

Frequency metering for 'Vernus' sweeper


Having built the 'Vernus' audio sweeper (Aug-Sep '92), I was annoyed that my digital frequency meter couldn't read the sweep frequency correctly. So I considered adding analog frequency metering to the sweeper — I had left space on my frond panel for such a contingency!

Using the square wave output from pin 11 of the XR2206 function generator allowed me to do without the usual input conditioning circuitry for the meter. I used a stripped-down version of a design by Andy Flind in *Practical Electronics*, and came up with the following circuit. To modify the Vernus, first cut the track from pin 11 of the XR2206 to ground, and connect it to positive via a 4.7k resistor. This square wave output is then fed to one half of the dual BCD counter IC1b, which in turn clocks IC1a — dividing the frequency by 10 and 100.

When bass-range is selected via SW1b, the square wave is directly applied to a differentiator which produces short negative spikes that trigger IC2, a 7555 wired as a monostable. This produces a string of 2ms pulses which are of equal frequency. To prevent false readings (triggering on multiples of the input cycles), the monostable period is set to less than half of the expected input period (2ms). These pulses are integrated by IC3a, producing a proportional and fairly constant current from pin 1 through the meter.

The meter scale will need to be show three ranges: 200Hz, 2kHz and 20kHz FSD. And as the input frequency is scaled by a factor of 10 and 100 for the Mid and Treble ranges, only one range needs to be calibrated.

M. Schmidt
Edgewater, WA **$40**




Timer for battery chargers

A programmable 24-hour timer using a small synchronous motor is available from various sources for less then $10, and it provides a convenient way to time a battery charger plugged into its socket. One problem comes about though, as the timer cycles every 24 hours — leaving only a four hour window for the removal of the batteries. If forgotten, the batteries could be seriously damaged.

In such timers the motor usually runs as long as the timer is plugged in. However, a simple change to its internal wiring makes the motor stop when the charging period is over. The circuit shows how the wiring is changed to achieve this. It is usually a matter of extracting the motor wire from one terminal screw and placing it under another. (Although one model required a solder joint.)

BE CAREFUL about the wiring —240 volts is lethal and stressed insulation can break down and start a fire. Only attempt this modification if you are sure you know what you are doing, and get someone qualified to check your work, just in case.



E.G. Wormald
Florey, ACT **$30**


Low cost emergency light

This is a simple and inexpensive way to provide an emergency backup light which will turn on if the 240V mains fails.


Two 1.2V NiCad penlight batteries are trickle charged and are used to power the bulb when the mains fails. In the presence of the mains AC supply, around 4.5V DC is developed across C1 which turns off the PNP transistor Q1. Current flows through R1 and D2 to charge the batteries at a rate of about 50mA, keeping them topped up.

When the mains supply fails, D2 is reverse biased and Q1's base is pulled low through R2. The transistor is now forced into conduction, which causes the lamp to light. When the mains is reconnected, the transistor turns off and the batteries are then recharged.

Pradeep G.
Alappuzha, Southern India **$25**



4-bit BCD preset uses potentiometer



By controlling the voltage to the input to what is essentially a 4-bit A/D converter, a simple way of producing a BCD value using a rotary control is achieved.

As the potential applied to R9 drops, one by one buffers N1 to N9 are biased on. IC3 then decodes the highest active input as a binary code, up to the maximum of 111 BCD. D1 to D3 are used as logic gating, to allow the addition of one extra bit for representing decimal values 8 and 9. 4050 hex buffers were used as they could be configured, using two resistors, to provide a much narrower hysteresis band (0.11V) than standard Schmitt triggers.To calibrate the unit, set VR1 to 0 ohms, and adjust VR2 until the BCD output reads 1001 (decimal 9). This BCD output could be used to drive a 7-segment display through a suitable decoder/driver chip, such as the 4511. Also best results will be obtained using 1% tolerance resistors for the input network.

S. Carroll,
Timmsvale, NSW **$40** ❖

EVER THOUGHT OF CONTRIBUTING?

Have you written the best article ever on theory or practice? Or you may have developed a great new circuit or design? If you have, you will want to see your work published as widely as possible.

We'd like to see your work, and of course, we pay you for any articles accepted for publication. If you can't figure out how to get started, we'd be glad to supply you with a copy of our writer's guide notes. Just phone us on (02) 353 0620 or send your article to to:

**The Managing Editor,
Electronics Australia,
P.O. Box 199,
Alexandria, NSW 2015**

DICK SMITH ELECTRONICS

Find All You Need Right Here!

NEW




Mini Rotary Pots 20k

In packs of 10.
Cat R-9945 $1.95

LIMITED STOCKS!

NEW



Small Solenoid

24V DC, 75mA.
Cat P-9012 $2.50

LIMITED STOCKS!

NEW



Slide Pots

Assorted pack of 16.
Cat R-9940 $4.95

MUST CLEAR! LIMITED STOCKS!

3.5 Digit Multimeter

If you don't need accurate measurement below 4 amps in the 20 amp AC range, then don't miss this huge array of features at this very special price.
Cat Q-1564

- Large 22mm display
- 20 amp AC/DC current range
- Auto power off & reset
- Logic test
- Capacitance meter
- Transistor tester
- Diode & continuity tester
- Data & peak hold



Special Low Price **$79**

NEW



Black Fire Retardent Tape

20m roll x 19mm dia.
Cat N-1377
$6.95

NEW



Felt Tape

48mm x 1m
Cat N-1375
$9.95

NEW



Self-Amalgamating Tape

3m roll
Cat N-1376
$7.95



OUT NOW!

Dick Smith Electronics Annual Catalogue 1996/7 packed with our exciting range of products and helpful information to help you find what you're looking for. Check it out today!

SAVE 25%



Blue Mini Strobe Light

Can be mounted outside, making it instantly obvious where the alarm is coming from when the alarm is triggered. 65mm diameter.
Cat L-6002
$14.95


SAVE $20



180° PIR Detector

Can be wall, ceiling or corner mounted. It offers 4 interchangeable lenses so you can set it to focus on the area of your choice and has programmable pulse count for greater accuracy and fewer false alarms.
Cat L-5015
$39.95

SAVE 50%



Small Breadboard

Supplied as board only. 300 holes in 60 buses plus 2 distribution buses.
Cat H-4035
$4.95

Exciting Kits For You To Build!

Talking Electronics

Issue 1

Contains 8 different projects including a car tracker and capacitor discharge unit for model railways!



Cat B-3626

NEW


$3.50

Steam Whistle

Give your model boat or train that final touch with this distinctive-sounding steam whistle. With trimpots to create a two-chord whistle sound, you can adjust the tuning to suit your model. Uses an LM380 Amplifier Ic capable of delivering around 2W into a 4ohm loudspeaker. Kit is supplied in short form with components & PCB only. (Standoff's shown not supplied)

Cat K-3021

$12.95




NEW

EA June '96

Knightrider Scan Kit

Remember the car KIT in the TV series Knightrider? With this kit you can simulate the KIT that created all the interest in the first place. PCB carries a row of 16 LEDs that scans back & forth continuously at a rate that can be set by an on-board trimpot. Working voltage is between 9 & 12V. Kit is supplied in short form with components & PCB.



Cat K-3168 $27.50

SILICON CHIP May '96

Stroboscopic Tuner Kit

Use the stroboscopic tuner as a reference to tune your musical instruments. Contains 84 electronic notes with the beat frequency being displayed graphically on a ring of LEDs. Circuit allows you to dial up a note, then tune the instrument either visually or aurally. Complete with all components, case, PCB, hardware & pre-punched screened front front-panel.



Cat K-5102

$64.95

EA May '96

Laser Pointer Kit

Lightweight & compact, this laser pointer has adjustable focus and output of <1mW. Laser module is pre-built & calibrated. Kit is supplied in full form with laser diode module, hardware, batteries & case.

Cat K-1048 $69.95



SILICON CHIP June '96

Insulation Tester

This high-voltage insulation tester measures resistance from 1 to 2200 giga ohms. It's battery powered and displays readout on a 10-step LED display. Converter within the circuit produces either 100V, 250V, 500V, 600V or 1000V DC. Test voltage accuracy less than 5%; charging impedance 9.4M ohms; current drain 50mA @ 1000V out. Supplied in full form with all components, hardware (including test leads), PCB, case & pre-punched screen front panel.



Cat K-7002 $69.95

SILICON CHIP May '96

50W Stereo Amp

Features 50W RMS per channel into 8 ohm loads, it's ideal for home stereo systems. Protected against thermal runaway, shorts to power-supply rails, undervoltage supply rails, overvoltage from inductive loads and output short circuits. Amplfier provides pre-amp outputs and poweramp inputs on rear panel allowing other equipment to be connected in parallel such as additional amplifiers or sub-woofer amp. Kit is supplied in full form with all components, hardware, silk-screened solder-masked PCBs and pre-punched metal work and front panel.



NEW

Cat K-5590 **COMING NEXT MONTH!** EA June '96 $299

Availability: Our kits consist of many different parts from numerous suppliers. Whilst we have consulted closely with them and are satisfied as to their ability to supply, sometimes problems can arise in obtaining all of the parts. This means there is a slight chance that availability may be delayed. Rainchecks are available, however if you'd like to check beforehand, please don't hesitate to contact your local store.

DICK SMITH ELECTRONICS

This magazine is now on sale at all of our New Zealand stores!

PHONE, FAX & MAILORDER SERVICE

AUSTRALIA: Outside Sydney: FREE Call (1800) 263 922
Sydney and Enquiries - (02) 9937 3366
Fax: (02) 805 1986 or write to
Dick Smith Electronics, Mail Orders, Reply Paid 160
PO Box 321 NORTH RYDE NSW 2113

NEW ZEALAND: Phone: (09) 480 8049 or (09) 480 3331
Fax: (0800) 800 290 or write to
Dick Smith Electronics, Mail Orders Division, Private Bag 102-903
North Shore Mail Centre, Auckland
All major Credit Cards accepted. Overnight Courier Available.

NSW • Albury **21 8399** • Bankstown Square **707 4888** • Blacktown **671 7722** • Bondi **387 1444** • Brookvale **9905 0441** • Burwood **744 7299** • Campbelltown **27 2199** • Chatswood **411 1955** • Chullora **642 8922** • Gore Hill **439 5311** • Gosford **25 0235** • Hornsby **477 6633** • Hurstville **580 8622** • Kotara **56 2092** • Liverpool **600 9888** • Maitland **33 7866** • Miranda **525 2722** • Newcastle **61 1896** • North Ryde **9937 3355** • North Sydney 66 Berry St. **9964 9468** • Orange **618 400** • Parramatta **689 2188** • Railway Square **211 3777** • Penrith **(047) 32 3400** • Sydney City York St **267** • Tamworth **66 1711** • Wollongong **28 3800** **ACT** • Belconnen **(06) 253 1785** • Fyshwick **280 4944** **VIC** • Ballarat **31 5433** • Bendigo **43 0388** • Box Hill **9890 0699** • Coburg **9383 4455** • Dandenong **9794 9377** • East Brighton **9592 2366** • Essendon **9379 7444** • Frankston **9783 9144** • Geelong **232 711** • Highpoint **9318 6300** • Knox Towerpoint **9800 3455** • Melbourne City Strand Central Arcade **9663 5320** & 246 Bourke St **9639 0396** • Richmond **9428 1614** • Ringwood **9879 5338** • Springvale **9547 0522** • **QLD** • Alderley **3356 3733** • Booval **3282 6200** • Brisbane City **3229 9377** • Buranda **3391 6233** • Cairns **311 515** • Capalaba **3245 2870** • Chermside **3359 6255** • Indooroopilly **3878 4944** • Maroochydore **791 800** • Mermaid Beach **5578 5600** • Rockhampton **27 9644** • Southport **5532 9033** • Toowoomba **38 4300** • Townsville **72 5722** • Underwood **3341 0844** **SA** • Adelaide City Pulteney St **232 1200** & Myer Centre **231 7777** • Elizabeth **255 6099** • Enfield **260 6088** • St Marys **277 8977** • Westlakes **235 1244** **WA** • Balcatta **240 1911** • Cannington **451 8666** • Fremantle **335 9733** • Perth City **481 3261** • Midland **250 1460** • Northbridge **328 6944** **TAS** • Glenorchy **732 176** • Hobart **31 0800** • Launceston **344 555** **NT** • Darwin **81 1977**

* STORES IN RED ARE OPEN SUNDAYS. STORES ACROSS AUSTRALIA AND NEW ZEALAND

Construction Project:

50W/CH STEREO CONTROL AMPLIFIER - 1

Here's a design for a new low cost, easy to build integrated stereo amplifier with the ability to deliver 50 watts RMS output per channel. It includes a low noise phono preamp, flexible input and tape recording source select switching, the ability to bypass the tone controls for 'direct' operation, a stereo headphone output and many other features.

This new low cost 50W per channel stereo amplifier design is a revision of the popular 30+30W stereo amplifier published in the April 1992 issue, which itself was a revision of the Playmaster 30-30 amplifier of August 1988. The new amplifier has been developed by the R&D department at Dick Smith Electronics, and DSE will be selling a full kit for it (catalog number K-5590) for the very attractive price of only $299.

The amplifier retains such features as simple appearance and straightforward construction, but also includes several new features to make it more useful in the home stereo environment and generally compatible as a basic amplifier for a home theatre sound arrangement.

The power amplifier channels make use of the new LM3886 integrated power amp IC from National Semiconductor. Here they are run from a +/-35V supply, derived from a 25-0-25V 160VA toroidal transformer, which results in a maximum output power of around 50W RMS per channel into 8Ω loads. The LM3886 devices feature excellent internal protection against thermal runaway, shorts to power-supply rails, under-voltage supply rails, over-voltage from inductive loads and output short circuits. We don't suggest they're indestructible, but they seem quite safe from accidental destruction, very robust indeed and ideally suited to this application.

With the new amplifier, we have attempted to simplify the construction and make the project more modular. As such, the kit is broken down into three main circuit boards. IDC ribbon cable is used to route the audio inputs and outputs between front and back, without the need for multiple shielded cables to be separately terminated — which can be very time consuming.

Note that within the ribbon cables, each audio conductor is separated from its adjacent audio conductor by a grounded conductor in between, to reduce any crosstalk. Crosstalk is further checked by the use of guard tracks between the conductors of the left and right channels on the PCBs.

Instead of a single large PCB as used previously, there are three smaller modules: the RCA socket and phono preamp board, the power amplifier board, and the preamplifier board. Should the phono preamp be unnecessary, then the preamp components can be left out and that section bypassed with two links, thus making the phono input suitable as a further standard 'line level' input.

The line level connections to the rear of the amplifier have also been increased in number. The amplifier now fully supports two tape recorders, with switching to enable either tape unit to record directly from the other one. In practice this connection could be used for a cassette tape recorder as Tape 1 and a hifi video recorder for Tape 2, or other arrangements. Each of the two Tape connections can therefore record either from the standard sources or from the other Tape unit.

A set of 'coupler' sockets is now included, with a coupler switch close by. These connections provide direct stereo patch points to the outputs of the preamps and the inputs of the power amplifiers. The coupler connectors may usually be ignored, by having the coupler switch set to the Normal position where each preamp is connected internally to its power amp. In this position the preamp output signals remain available at the Coupler Output sockets, for external use, even though they are still connected to the power amplifiers.This enables other equipment to be connected in parallel, in particular such equipment as a further power amplifier or sub-woofer amplifier. The signal to this other equipment remains under the control of the amplifier's preamp controls.

With the switch in the 'Coupler' position, the internal links between the outputs of the preamps and the inputs of the power amps are broken, and brought out to the coupler sockets. This would therefore allow connection of things like a sound processor to be included in the path. It would also allow the power amplifiers to be driven solely from an external source.



As you can see, the amplifier provides plenty of inputs and outputs. A nice feature is the ability to separate the front end outputs from the power amplifier, to couple in an external sound processor.

Circuit description

Considering the power supply first, all of the supply components except for the transformer are contained on the power amp circuit board. The 25-0-25V 160VA toroidal transformer is well suited to this particular application due to its high power capability versus its com-



pact size. This transformer does include an integral thermal fuse, but even so, 3A slow-blow fuses have been included in its secondary circuit to protect the transformer. These fuses are replaceable, whereas should the transformer's internal thermal fuse blow this would render it inoperable and it would need to be replaced. The primary of the transformer itself is fused with a 2A slow-blow fuse.

The centre-tapped secondary of the transformer is fed via the 3A fuses to the bridge rectifier. This provides +35V and -35V DC supply rails across reservoir capacitors C601 and C602, which are used to power the power amplifier ICs.

The supply rails for the preamplifiers are taken from the 35V rails, via voltage regulators REG1 and REG2. An LM317 adjustable regulator is used for the positive rail and an LM337 for the negative rail, with their associated resistors to set their output voltages. These devices can accommodate an input voltage up to 40V, and can therefore be directly connected to the 35V rails.

Using these devices also permits us to adjust their outputs to above the traditional 15V. Here they are set to close to 17V per rail, to increase the signal 'headroom'




Fig.7: The power response of the prototype amplifier, with the tone controls bypassed and when delivering 49W into a load of 8 ohms. As you can see it is only 0.5dB down at around 23Hz and 31kHz.




Fig.8: These figures show the response of the amplfier when the tone controls are in circuit, and in the flat, full boost and full cut positions in each case.

SPECIFICATIONS

Performance of prototype:

Output power

Single channel:	54W RMS into 8Ω
Both channels:	46W RMS into 8Ω
	(At the start of clipping, but with THD below 1%)

Frequency response

Power amp input	+0/-0.5dB 20Hz to 30kHz
Line input	+0/-1dB 20Hz to 30kHz (Tone controls defeated)

Input sensitivity

Line inputs	281mV RMS
Phono preamp	5mV RMS
Power amp	1V RMS
	(Single channel input sensitivity for 50W at 1kHz)
	Phono preamp overloads at 200mV.

Harmonic distortion

Less than 0.04%, 20Hz to 20kHz

Signal to noise ratio

CD input	92dB, 98dB A-weighted
Phono input	63dB, 84dB A-weighted

Channel Separation

Preamp	50dB at 1kHz, 35dB at 10kHz
Power amp	75dB at 1kHz, 60dB at 10kHz

Tone controls

Bass	+/-12dB at 55Hz
Treble	+/-12dB at 15kHz

Protection

3A fuses, plus protection as per National LM3886 datasheet, which includes protection against thermal runaway, instantaneous temperature peaks, output short circuits, output shorts to supply.

through the preamplifiers. For convenience we will continue to refer to these supply rails as +/-15V. The LM833 opamps used in the preamplifier permit a split supply of up to +/-18V (36V).

In laying out the PCB tracks around the power supply, an effort has been made to keep the high current paths as balanced or as close together as possible. This is to keep the amount of electromagnetic radiation from any high current loops to a minimum, so as to minimise the induction of hum into the audio path. This also applies to the routing of other high-current carrying cables — see the construction section.

Two separate ground connections to the power supply board, that is the headphone socket ground and the power supply to case ground, are each connected by soldering to a ground link rather than




Fig.1: The amplifier power supply circuit. The unregulated 35V rails are used for the power amp stages, with the regulated 17V rails for the earlier stages.




Fig.2: Each power amplifier uses this circuit, based based on the new National Semiconductor LM3886 device. It is capable of delivering around 50W per channel continuously.

back divider which sets the AC voltage gain to 21, while capacitor C403 ensures that the DC gain is unity for maximum operating point stability. Resistor R408 and capacitor C406 across the output, together with R409 and its accompanying 0.5uH choke (wound on the resistor itself), form a Zobel network to maintain the AC output impedance and ensure stability at high frequencies.

You may note that the LM3886 mute control (pin8) has not been used as an external control; the front panel mute switch is electrically in the preamplifier output path before the power amps, and this arrangement therefore mutes the signal to any equipment connected to the coupler output at the same time.

Pin 8 of the LM3886 connects to an R-C-R network (R405, C404, R407),

connecting them into the PCB. This is to avoid placing them in the direct path of high current AC which may be flowing between the two large capacitors and which may induce hum.

A large U-shaped aluminium extrusion heatsink runs down the centre of the case, and is drilled to accommodate the two amplifier devices and the two regulators. Each of these devices needs an insulating washer between it and the heatsink, and each device is fixed in place with a bolt through an insulating bush. More about this later.

Power amplifiers

The National Semiconductor LM3886 audio power amp chips are used here in a manner which closely follows National's recommendations. Resistors R404 (20k) and R403 (1k) form a feed-




Fig.6: Here is the circuitry for the phono preamps, mounted on the rear PCB. These preamps can be omitted if not required.




Fig.3: The input buffering and tone control circuitry for both channels. The tone controls provide up to 12dB of boost or cut, but can be bypassed when not required.

which has a time constant of about 0.5 seconds and acts as a de-thump mechanism when the power is first turned on.

Note also resistor R600, a 10Ω 1W type located between the large capacitors of the power supply and the power amp input connection. This is common to both channels of the amplifier and acts to reference the amplifiers' input signal ground to the power supply ground. In each amplifier the signal input ground and speaker output ground are separate.

Preamplifiers

The preamplifier stages use LM833 dual low noise op-amps for its basic circuit elements, and a pair of NE5534 devices for the output buffers. Two 100Ω resistors (R302, R303) decouple the power supply rails between the LM833s of the preamp section and the NE5534 output buffers. Each of the op-amps is decoupled individually with a ceramic capacitor across the supply rails beside the device itself.

Note also that a single 100Ω resistor (R301) is used to provide an earth reference point for the preamp, in case the internal IDC cable connectors at the preamp inputs are removed. The main earth connections of the preamps are via the ribbon cables.

From the input selector switching, the line level input signals first pass through the Volume controls and stereo/mono switch, and are then amplified by the two halves of IC1. These have a gain of about three, as set by the dividers formed by resistors R104/R103 and R204/R203.

If the tone control switch is in the Defeat position, the signals then pass directly to the Balance control (VR4), and then to output buffers IC4 and IC5. These each have a gain of about 1.4, as determined by resistive dividers R116/R115 and R216/R217.

When the tone control switch is not in the Defeat position, the signals pass through the tone control stages around IC2 and IC3, on their way to IC4/5. IC2 is wired as a feedback-type treble control stage, and can be adjusted to give anything between 12dB of boost and 12dB of cut at 15kHz; IC3 is the matching bass control stage, and can give the same amount of boost and cut at 55Hz.

At the 'end' of the preamp circuit is the Mute switch SW3. From there the signals go to the Connect switch and connectors on the rear PCB.

As with the rear PCB, which holds the RCA sockets and optional phono preamp, the preamp PCB layout features many ground guard tracks. These

50W/Ch Stereo Amplifier




Fig.4: The input source selection and tape recorder mode switching circuitry for one channel, together with the volume control.




Fig.6: The circuitry around the headphone socket. The switches on the socket are used to mute the speakers when the phones are plugged in.

tracks run between the conductors of the two channels to reduce crosstalk.

Phono preamp

The phono preamp components also reside on the rear PCB, at the other end and close to the RCA phono input sockets. If there is no need for a phono preamp, then all the components of this section can be omitted, and the phono input can be linked through directly as a line level input. The phono preamp bypass links can be seen as the two short vertical links, immediately below where the beads are shown on the overlay. The power supply resistors to the phono preamp can also be omitted, these are R706 and R806.

The phono preamp, when it is included, features a standard implementation of the LM833 as a stereo phono preamp with RIAA correction. Ferrite beads are included over the leads of the first input components for each channel, in this case a pair of 0Ω resistors (link components), so as to avoid the chance of radio frequencies (RF) being picked up and amplified by the sensitive phono preamp.

That concludes the circuit description for the new amplifier. In the second article we'll describe its construction and testing.

(To be continued.)❖

PARTS LIST

Case Parts

Metal case with lid and front panel;1 x rear panel label; 1x heatsink (aluminium extrusion, black);1 x red bezel for front panel (see text)1 x M205 fuseholder;1 x M205 fuse 2A slo-blo mains fuse cartridge;1 x toroidal power transformer,25-0-25V; 1 x illuminated mains switch;1 x 3-way mains connector block;1 x stereo headphone socket 6.5mm(insulated);1 x 4-way spring speaker connector;1 x cable clamp grommet; 1 x solder tag; 19 x nylon cable ties,3mm; 60 mm length of 25mm heatshrink sleeving (for fuse holder); 3 x 25mm lengths of 6mm heatshrink sleeving for mains switch contacts; 4 x CSK M4 bolts, black, for front panel; 6 x RH M6 bolts, black, for case cover; 4 x M2 bolts and nuts and star lockwashers; red and black heavy duty hookup wire for speaker wiring; blue heavy duty hookup wiring for local grounds;brown and blue mains-insulated wire for mains switch wiring; 700mm length of 40-way IDC ribbon cable for inter-board wiring.

Power Amp/Power Supply PCB

Resistors

All 1/4W metal film unless specified:

R401/501,R405/505	22k
R402/502,R403/503	1k
R404/504,R406/506	20k
R407/507	39k
R408/508	5.6 ohms, 0.5W
R409/509,R600	10 ohms, 1W
R410/510	680 ohms (mounted on head phone socket)
R601/602	1.5k
R603/604	120 ohms
(Plus 3 x 0W links)	

Capacitors

C401/501	1uF 16V electro
C402/502	220pF ceramic
C403/503,C607/608	47uF 25V electro
C404/504	22uF 63V electro
C405/505	47pF polystyrene
C406/506,C407/507, C408/508,C603/604	0.1uF ceramic
C409/509,C410/510	100uF 63V electro
C601/602	5600uF 40V electro
C605/606	10uF 16V electro

Semiconductors

REG1	LM317 adjustable regulator
REG2	LM337 adjustable neg. regulator
IC7,8	LM3886 power amplifier
Bridge	PO-4 Rectifier bridge

Miscellaneous

32 x TO-220 mounts for regulators; 2 x mica washers for LM3886s; 10 x PCB terminal pins;4 x M3 x 12mm screws, nuts and washers; 1 x 3-way screw terminal block for 25-0-25V AC input;1 x 10mm insulating spacer; 300mm of 0.8mm enamelled copper wire for chokes; tinned copper wire for links; 4 x M205 PCB-mount fuse clips 2 x 3A(or 3.15A) M205 Slo-Blo fuse cartridges.

Preamplifier PCB & switch sub-board

Resistors

All 1/4W metal film, unless noted:

R101,102	470 ohms
R102,202	220k
R103,203	2.4k
R104,204	5.6k
R105/6,205/6	3.9k
R107/8,R111/112, R114,R117, R207/8,R211/212, R214,R217	100k
R109/110, R209/210	5.1k
R113,213	12k
R115,215	2.7k
R116,216	1.1k
R301/302/303	100 ohms
(Plus 18 x 0W links)	

Capacitors

C101/201	2.2uF 16V electro
C102/202	270pF ceramic
C103/203	1nF MKT
C104/204	56pF ceramic
C105/205,108/208, C109/209,110/210, C112/212,301/302	100uF 16V electro
C106/206,107/207	120nF MKT
C111/211	22pF ceramic
C308	10uF 63V electro
C303,C304, C305,C306,C307	0.1uF ceramic

Semiconductors

IC1-3	LM833 dual low noise op-amp
IC4-5	NE5534 low noise op-amp

Miscellaneous

VR1	50k dual log pot
VR2,3,4	25k dual linear pot

Four-way pushbutton switch (SW8); seven single pushbutton switches (SW1-7); 3 x 30mm knob (black); 1 x 40mm knob (black); 1 x pre-amp PCB (ZA-1252); 1 x switch PCB (ZA-1253); 11 x pushbuttons; 5 x insulating spacers, 15mm; 3 x insulating spacers, 25mm; 1 x 50-pin DIL header pins strip (cut into 2 x 20); 12 x PCB terminal pins.

Connector/Phono preamp PCB

Resistors

All 1/4W metal film unless specified:

R701,R801	100k
R702,R802	47k
R703,R803	390 ohms
R704,R804	16k
R705,R805	200k
R706,R806	33 ohms
R707,R807	560 ohms
(Plus 2 x 0W links)	

Capacitors

C701,C801	33uF 16V electro
C702,C802	100pF ceramic
C703,C803, C706,C806	100uF 16VW electro
C704,C804	4.7nF MKT
C705,C805	15nF MKT

Semiconductors

IC6	LM833 low noise op-amp

Miscellaneous

2 x ferrite beads; 1 x 50-pin section of DIL header pins (use as 2 x 20); 1 x 3-way terminal block (for power in); 6 x PCB terminal pins; 1 x DPDT toggle switch, 90□ PCB mounting; 1 x 4-way RCA sockets, PCB mounting; 2 x 8-way RCA sockets, PCB mounting; 3 x M2.5 x 12mm screws and nuts; tinned copper wire for links; 1 x M3 x 12mm screw with 2 x M3 nuts, 3 x M3 star lockwashers and 2 x solder lugs, for earth terminal; 1 x rubber grommet for coupler switch.

TECS

THE ELECTRONIC & COMPUTER STORES

HEAD OFFICE / MAIL ORDERS:
305 Latrobe Street, Melbourne, Vic. 3000
Phone:(03)9602-3499 Fax:(03)9642-8551
Melbourne suburb:
Cnr. Blackburn & Wellington Rds., Clayton, Vic. 3168
Phone:(03)9562-9501 Fax:(03)9562-9261
Trade orders: TECS Imports P/L, 88 South Pde, Blackburn, Vic. 3130
Phone:(03)9877-7071 Fax:(03)9877-7081

SHOP HOURS: Mon.~Thurs. 8:30~5:30 Fri. 8:30~6:30 Sat. 9:00~1:30

(ALL ORDERS OVER 5Kg MUST TRAVEL ROAD EXPRESS.)

☐ Standard Mail (Max. 500g)	$4.00	(Please allow 3~7 days.)
☐ Standard Mail (Max. 1Kg)	$5.50	
☐ Heavy Mail (1Kg to 5Kg)	$8.00	
☐ Road Express (Max. 10Kg)	$12.00	
☐ Road Express (10Kg up)	$15.00	
☐ Air Freight (Max. 3Kg)	$8.00	(Please allow 2 days to Capital cities and 3 days to Country areas.)
☐ Air Freight (3Kg to 5Kg)	$15.00	
☐ Transit Insurance (Minimum of $1.00) Add $1.00 per $100.00 order value.		(Australia only.)

Free Call Mail Order Hotline!!
(1800) 335-901

N.B. Normal prices charged unless ad prices quoted. Errors & omissions excepted. Prices & specifications subject to change without notice.

Tecs Tecs Tecs Tecs Tecs Tecs Tecs Tecs

EVEREX Notebook Computers



PC MAGAZINE EDITORS' CHOICE

US Edition
September 1995

EVEREX ExpressNote 586

- Cyrix 5x86-100CPU.
- 8M RAM.
- 1.44M FDD.
- 10.4" DSTN colour display.
- Supports Plug'n Play.
- Built-in 16bit stereo sound module / mic / speakers.
- 2 x Type II or 1 x Type II PCMCIA slots.
- Built-in Glide Pad.
- 9 pin serial (16550A).
- 25 pin parallel (ECP & EPP).
- External PS/2 keyboard / mouse port.

$2865



Canon BJC-210

The new low cost bubblejet printer with three colour process without sacrificing the quality. No more "bluish-green mud" substitute instead of black. For high speed black & white printing, the BJC-210 accepts the optional black cartridge, giving you up to 3.4ppm. The standard resolution is 360 x 360 dpi. In addition, BJC-210 offers a special 720 x 360 dpi smoothing function for sharp, laser-like text using the optional 64-nozzle black cartridge.

$389




Canon BJC-4100

Canon have taken the BJC-4000, one the most popular colour ink jet printer, and made it even better! The new, improved BJC-4100 is still the fastest black & white ink jet printer on the market in its class, with speeds comparable to a personal laser. BJC-4100 offers full, four colour (CMYK) process at 720 x 360 dpi and at speed of up to 0.8ppm. It also features improved plain paper performance.

$675

Pentium-100 Multimedia System



- 8M RAM
- 1.2G HDD
- Hex speed CD-ROM
- 15" N.I. XGA monitor
- 2M ET4000W/32p PCI video card
- Sound Blaster 16PnP sound card
- Latest Microsoft 5 CD pack

- Encarta `96 - Golf - Works 4.0 - Dangerous Creatures - CD Sampler

- Microsoft Windows `95

All this plus *FREE*

1.) Delivery & setup.*
2.) 1 year on-site warranty.*
3.) 2 year parts & unlimited labour warranty.


* - Limited to Melbourne metropolitan areas. Conditions apply.

$2650

Uprade options:

Pentium-120MHz CPU in lieu of 100MHz	add $110
Pentium-133MHz CPU in lieu of 100MHz	add $220
Pentium-150MHz CPU in lieu of 100MHz	add $410
Pentium-166MHz CPU in lieu of 100MHz	add $775
Extra 8M RAM	add $180
Oct speed CD-ROM in lieu of Hex speed	add $100


IBM/Cyrix 5x86-100MHz CPU & motherboard



- 256K cache.
- 3 x PCI slots.
- 4 x 72pin SIM sockets.
- on-board dual channel E-IDE controller.
- on-board floppy controller.
- 2 x on-board 16550 UART serial ports.
- on-board ECP/EPP parallel port.

$269

Cyrix 6x86-100MHz CPU & motherboard



- 256K p/line cache.
- 4 x PCI slots.
- 6 x 72pin SIM sockets.
- on-board dual channel E-IDE controller.
- on-board floppy controller.
- 2 x on-board 16550 UART serial ports.
- on-board ECP/EPP parallel port.

$575

As above with Cyrix 6x86-120MHz CPU: $799

Low prices on 72pin memory modules

4M $95 8M $189 16M $389

Construction Project:

LOW COST RF TEST OSCILLATOR - 2

In this second and final article describing our new low cost RF test oscillator design, we describe its construction and setting up. As almost all of the circuitry is mounted on a pair of printed circuit boards connected directly together with PCB terminal pins, there is very little off-board wiring — and the inbuilt frequency counter will obviate the need for external calibration, in many cases.


by JIM ROWE

As you can see from the photos, the oscillator is built in a standard and readily available plastic instrument case measuring 204 x 159 x 65mm. This has been done for simplicity and economy. The usual plastic front panel has been replaced by a piece of unetched copper laminate, with the copper layer connected to circuit earth to provide protection against hand capacitance effects and also a measure of shielding.

There is in fact very little radiation of RF from the instrument, partly because of the shielding from the front panel and partly because the 'hot' RF circuitry runs at quite a low power level and has been kept relatively compact. Although there would undoubtedly be even *less* RF leakage if the unit were housed in a fully shielding metal case, the additional cost and complexity is probably not justified for most purposes. It could of course be done if you wish, however...

Virtually all of the circuitry is on two printed circuit boards, one relatively large and mounted horizontally in the bottom of the case and the other somewhat smaller and mounted vertically along the front of the first board, just behind the front panel. The interwiring between the two is made at their junction via some 27 PCB terminal pins, which solder to pads on both and hence bond them together physically as well.

The vertical PCB measures 170 x 52mm, and its etching pattern is coded 96rfo5b. It provides all of the basic circuitry for the frequency counter 'dial' — the 74C926 counter chip, digit multiplexing driver transistors, LED displays and segment current limiting resistors — plus the wiring to the oscillator's own front panel controls. The latter includes range switch SW1, the CW/Modulation switch SW2, Hi/Lo output level switch SW3, tuning pot RV1, output level pot RV2 and the output attenuator resistors.




Virtually all of the oscillator's circuitry is on two PC boards, one horizontal and one vertical, which are directly connected to minimise off-board wiring.

Note that tuning pot RV1 should ideally be a 10-turn type, as this gives a much 'expanded' adjustment range and makes it a lot easier to set the oscillator to a desired frequency. However these are more expensive, so if you want to save money and are prepared to cope with much more 'tricky' tuning, a standard single-turn 270° pot could be used. I don't really recommend it, though.

I should note also that as 10-turn pots are somewhat longer than than the standard type, a hole about 22mm in diameter has to be cut in the vertical PCB to provide clearance for the pot body — as can be seen in the photos. The PCB pattern has been designed with a 'blank area' to allow for cutting such a hole, but if you choose to use a standard pot there'll be no need for the hole as the pot will mount in front of the board as with RV2.

Range switch SW1 and the two smaller switches are mounted directly on the vertical PCB, minimising lead length and avoiding the need for off-board wiring. As there are two slightly different versions of the plastic-body three pole four position switch currently available, with the three pole pins rotated radially with respect to one another, the PCB pole pads are elongated to be compatible with either type.

In wiring up the vertical board, I suggest you begin as usual by checking it for possible etching faults — cutting any tiny unplanned links between tracks or pads, and bridging any obvious gaps that shouldn't be there. (Check against the PCB pattern published later in this article, if you're in any doubt.) Then begin the assembly proper by fitting the fixed resistors and wire links, using the over-



Another view inside the case, showing how the two PCBs fit together to form a tidy assembly. Many of the components on the main board are visible here, including three of the four tuning coils.

lay diagram of Fig.4 as a guide. There are only two links to be fitted, located just below the positions for LED displays LD3 and LD4.

Once the resistors and links are fitted, it's a good idea to fit the rotary switch SW1 and the two toggle switches SW2 and SW3. In each case you may need to extend/elongate some of the PCB holes slightly with a jeweller's rat-tail file, to accept the switch lugs and allow the switches to be mounted with their bodies as close as possible to the surface of the PCB. Note that SW1 is mounted with its locating spigot not at '12 o'clock', but at about '4:30' (i.e., rotated clockwise by 135°).

Make sure that each switch is mounted as squarely as possible, with its axis perpendicular to the board, before you solder its lugs to the appropriate pads — otherwise you may have trouble later, mating the switch bushes with their respective holes in the front panel.

With the switches fitted, you can now mount the four seven-segment LED displays, making sure that you fit each one with its decimal point LED towards the bottom of the PCB. Then fit the four digit driver transistors Q1-Q4, taking care to orientate them as shown on the PCB overlay, and also that you don't push their bodies down too near the PCB, as this is likely to strain their leads. There's about 15mm clearance between the front of the PCB and the back of the front panel when everything is later assembled, so the transistors don't have to be mounted very close to the board.

There is no need to mount the tuning or level pots to the vertical PCB at this stage; they can be mounted on the front panel, and connected when the two are assembled together. Similarly the PCB terminal pins used to connect the two PCBs together are best left until this is done. In fact the only thing left to do for the present is to fit counter chip U1, and its bypass capacitor C1. Then the vertical board can be placed aside for a while, while you assemble the horizontal board.

Horizontal PCB

The horizontal board is really the main board, carrying not only the RF oscillator/buffer/modulator circuitry, but also the audio oscillator, power supply and all of the frequency counter circuitry apart from the actual counter and display section. This all mounts on a board measuring 165 x 112mm, and coded 96rfo5a. Like the vertical board it is only single-sided — i.e., with copper on only one side — but with a fairly large amount of earthed shielding copper.

There are a reasonable number of links to be fitted to the horizontal board — 16 in all, so I suggest that after checking the PCB for etching faults, you fit these first. Fourteen of them go in the digital section on the left-hand side of the board, with the remaining two over at the right in the analog section. One of the latter goes between the location for




Fig.4: The overlay diagram for the oscillator's vertical PCB. Use it as a guide when you're placing the components.

coil L1 and U12, the audio oscillator chip, while the other goes in the RF oscillator circuitry between R27 and C24, near the front.

I recommend that you use insulated hookup wire for the link in the audio oscillator and the six longest links running 'front to back' in the digital section, together with the longest 'side to side' link running along the very front of the latter section. The rest can be run in tinned copper wire, as there is no risk of short circuits.

With all of the links fitted, I suggest that you then fit all of the fixed resistors, using the schematic, PCB overlay diagram (Fig.5) and internal photos as a guide. All of the resistors are 1/4W metal film types, although some have their leads bent to fit holes spaced apart by 0.5", and others to fit holes 0.4" apart.

Next you can fit the three preset pots RV3, RV4 and RV5. Again you may need to elongate the holes in the PCB slightly to accept the narrower section of the pot lugs and allow the pots to mount securely and level. You may as well also mount the trimmer capacitor CV1 at this stage, in much the same way.

The smaller fixed capacitors can be fitted next. Most of these are monolithic ceramic bypass types, which need to be fitted with their leads as short as possible. However as they are fairly fragile you'll also need to be careful not to strain their leads when you fit them — if necessary shaping them first with a pair of needle-nose pliers. This also applies to the small NPO ceramic capacitors C9, C10 (both in the crystal oscillator) and C19 (in the RF oscillator).




Fig.5: Similarly use this main board overlay diagram as a guide to parts placement on this PCB, together with the photos.

Many of the remaining smaller capacitors are MKT plastic types, which should just drop into place as the PCB holes are all spaced apart by the matching 0.2".

There are also three 2.2uF TAG tantalum capacitors, C3, C4 and C20. These may also need their leads shaped with pliers before fitted them to the board — and take care with their polarity, which is indicated on the overlay diagram.

You may as well add RF choke L5 to the board at this stage, again shaping its leads if necessary to prevent reasonably close mounting without strain.

Before proceeding further, I suggest that you now fit the six PCB terminal pins that are used for the 'off board' connections to the main PCB. Four of these go along the rear edge — two just to the left of centre behind C4, and the other two at the right-hand end behind diodes D4 and D5. The remaining two pins go on the right-hand side, near reservoir capacitor C2 (when it's fitted).

Now you can fit the four main rectifier diodes D3-D6, at the rear right, and also the BAW62 signal diode D1 — at the front between R25 and C21. The four rectifier diodes should have their leads carefully bent in advance to suit holes spaced 0.5" apart, while those for D1 should be bent to suit holes 0.4" apart. All five diodes have their cathode (banded) end towards the front of the board, as shown in the overlay diagram.

Winding the coils

This is probably a good time to wind the main oscillator coils L1-L4, using the information in Fig.6 as a guide. All four are wound using 0.25mm enamelled copper wire, with L1 and L2 wound on F14 two-hole balun cores (13 x 13 x 7mm), L3 on a similar F29 core (13 x 7 x 7mm), and F4 on a small 4mm diameter former of the type with a matching six-pin base and shield can, and fitted with an F29 slug.

Fig.6 shows both the way the various coils are wound, and their connections. Follow these closely, to ensure that your coils are compatible with the PCB. Note that with the three coils wound on balun cores, I have used the convention that 'one turn' is a complete loop through both holes — i.e., 'down one hole and back up the other'. Similarly a 'half turn' means that the wire is passed through only one of the two holes.

When each coil is all wound, it can be prepared for mounting on the PCB. With the coils wound on balun cores, this means cutting the start and finish ends to about 12mm long, and carefully scraping off the enamel from the last 9mm or so, baring the copper ready to be tinned. Similarly the twisted 'tap' is carefully scraped back as well.




Fig.6: Winding details for the oscillator's four tuning coils.

The three leads are then 'dressed' with a pair of needle-nose pliers, so that they are in the right positions to pass through the matching PCB holes when the core is placed on the top of the board. Then before soldering the leads, a nylon cable tie is passed through the two adjacent 3mm holes, looped around the core and pulled fairly tightly, to secure the coil assembly firmly in position. The leads can then be soldered carefully to the PCB pads, keeping them as short as possible without strain.

L4 is prepared a little differently, being wound on a conventional former. Here I suggest that you cement the former to its base first, and then bare the 'start' end of the winding wire. Then pass this end down the hollow pin shown in Fig.6, and solder it carefully inside — taking care to get as little solder as possible on the *outside* of the pin, as this will make it difficult to fit the finished coil to the PCB.




Fig.7: An underside overlay for the main PCB, showing where the two SMD transistors are fitted.

Now wind the first section of the coil, and when you reach the position for the tap form a 'hairpin' loop of doubled-back wire long enough to pass down through the tap pin. Then carefully scrape off the enamel from this loop, and pass it down through the pin until the first section of the coil is tight (i.e., close wound). Then solder it carefully inside the pin as before, and you'll be ready to wind the top part of the coil. At the 'finish' end you can cut, scrape, pass down and solder the wire end as before, completing the coil itself. It should then be an easy matter to pass the pins down through the matching PCB holes (assuming you didn't get any solder on the outside of the pins!), and solder them to the pads.

As this coil is fitted with a threaded slug, this can now be added. However I suggest that you first introduce a length of very thin rubber thread (such as one thread from dressmaker's elastic) to the hole in the former, before screwing in the slug. As the slugs are a rather loose fit, there is plenty of room for the rubber thread, which provides just enough 'resistance' to ensure that the slug remains fixed in position once you have adjusted it.

With the coil pins soldered to the PCB tracks and the slug added, you can finally add the shielding can and solder its leads to the PCB to hold it securely in position.

Now you should be ready to fit the varicap diode CV2, modulator FET Q7, buffer transistor Q8 and the various ICs. As usual take care with the orientation of all of these parts, as they're all polarised. Use the overlay diagram and photos as a guide, and note that Q7 and Q8 are mounted with their flat sides facing. Shape the leads of both these transistors and CV2 so they can be mounted quite close to the PCB, for the shortest lead length that can be achieved without strain.

All of the digital ICs are fitted with their 'notch end' facing towards the rear of the board, while audio oscillator chip U12 has its notch facing the front of the board.

Both of the TO220 three-terminal regulator chips (U10, U11) mount on the board horizontally, with a 3mm machine screw and nuts to hold them down. Only the 7805 (U10) needs a heatsink, and the board allows space for a standard louvred U-shape heatsink

measuring 25 x 28 x 35mm. This is held in place between the device and the board by the mounting screw. It's a good idea to give the bottom of the device a thin smear of thermal conducting grease before assembly, to ensure efficient heat transfer.


The SMD transistors

The BF998 dual-gate MOSFET transistors (Q5 and Q6) are surface-mount parts in the tiny SOT143 package, and mount underneath the board rather than on top. Use the small overlay diagram of Fig.7 as a guide to their location — but note that the diagram is looking at the *underside* of the board, and with the devices with their top towards you (i.e, with their pre-formed tabs down towards the board copper).

If you closely examine these devices with a magnifying glass, you'll find that one of the four tabs is wider than the others. This is the source tab, and as you can see from Fig.7 the two devices are angled at 45° to the front of the PCB, with these wider tabs in the 'right-hand corners' — i.e., towards coils L3 and L4.

To solder each device to its four matching pads, without damaging it, you'll need a soldering iron with a very fine chisel-pointed bit — well tinned, and very clean. The iron should also be reliably earthed, to ensure there are no leakage currents to damage the devices when you solder the tabs.

I suggest that you *very lightly* tin the four PCB pads for each device first, if they haven't already been solder plated by the board manufacturer. Then place the device very carefully in position,



Here are the patterns for the two PC boards, reproduced here actual size for those who wish to etch their own boards.

and hold it in place using a toothpick while you quickly tack-solder the source tab to its pad. Then you can solder the remaining tabs, and finally resolder the source connection if you're not entirely happy with it.

The main things to ensure are that (a) you don't overheat either BF998, during the soldering process; and (b) you don't apply too much solder and create 'bridges' to short between the pads or device tabs. The space between the tabs/pads is very small, so you need to be really careful.

Once the two SMDs are in place (phew!) you can fit the 2MHz crystal (X1), which mounts over between R17 and trimmer capacitor CV1. Also the 12V/50mA grain of wheat lamp (G1) in the audio oscillator, next to U12, and the main reservoir electrolytic C2 just to the rear of R40 and R41. All of these mount in the usual way, from the top of the board.

Joining the PCBs

Your main PCB should now be complete, and if everything seems OK it's time to join the two boards together. I suggest that you tackle this operation as follows.

First, fit the 27 PCB terminal pins which are used to link the two, into the holes along the bottom of the vertical board. Push them in from the copper side, with their *shorter* ends passing into the holes, and don't solder them to the pads as yet. They should be a reasonably secure friction fit, if the holes have been drilled to the correct size.

Now invert the main board, and offer up to its front edge the copper side of the vertical board, also inverted but at 90°. The pins attached to the vertical board should line up with and lie on the rectangular pads of the main board, if you've done everything correctly. It's then a matter of holding the two tightly together at an accurate 90°, and soldering the pins to the copper pads on both boards.

This is a little tricky, but not unduly difficult if you use the right approach. I tacked the two end-most pins to their main board pads first, to hold everything together and allow me to make sure that the two boards were positioned at the correct 90° angle to each other. Then without disturbing this alignment, I carefully soldered the remaining pins one by one, first to their vertical board pad and then to the main board pad. Finally I soldered the end pins to their vertical board pads, to complete the job.

When the full 27 pins are soldered, the two boards are very rigidly joined. Just make sure that they are accurately aligned at 90°, before you begin soldering them all — otherwise you'll have trouble later!

Before proceeding, examine the completed PCB assembly very carefully, checking against the overlay diagrams for misplaced or wrongly orientated components. Also look closely for any accidental solder bridges between tracks.

Preparing the panels

If all seems well, you should now be ready to prepare the front and rear panels, cutting out the holes for their controls and connectors, etc.

As noted earlier, the front panel is made from unetched PCB laminate, cut to the same dimensions as the plastic front panel normally supplied with the case. The copper side faces inward, and is connected to the instrument's signal earth via the earth wire for the RF output connector. For the prototype I made a dress front panel from 'Dynamark' photosensitive sheet, and after the various holes were cut in the laminate panel, this was carefully attached to the front to give a professional appearance.

When the front panel itself is finished, the RF output connector is attached to it along with RF output pot RV2 and the 10-turn tuning pot RV1. A small piece of red filter material is also glued (or taped) to the rear of the panel, behind the LED display window.


Then, before mating the front panel to the front of the PCB assembly, solder a length of tinned copper wire about 25mm long to each of the lugs of pot RV2, and bend these so that when the panel is offered to the vertical PCB, the wires will mate with the corresponding holes. Fit a similar wire to the 'active' centre spigot of the RF output socket, and a longer one which is soldered not only to the 'earth' lug of the socket, but also to the adjacent front panel copper.

It's also a good idea at this point to solder three short lengths (say 50mm) of *insulated* hookup wire to the lugs of the 10-turn tuning pot, ready to connect to the corresponding PCB pads.

Now it should be possible to mate the front panel assembly with the PCB assembly. The two are held together via the mounting bushes and nuts for rotary switch SW1 and the two small toggle switches, and the panel can be set for accurate parallel alignment with the PCB by adjusting the exact positions of the toggle switch front and rear nuts. You'll find this is easier to do than to explain...

Don't forget to solder the three leads of the tuning pot to the corresponding pads of the vertical PCB. Note that you may need to check the pot connections carefully, as 10-turn pots differ from the standard type — and there are also a couple of connection arrangements used by different manufacturers.

Once the panel is fitted to the boards, the complete assembly can be fitted inside the lower half of the case and fastened using six of the small self-tapping



Here is the front panel artwork for the oscillator, also shown actual size.

screws provided, through the mounting holes in the main PCB. Note that you may have to cut away some of the unused mounting pillars moulded in the case, to clear some of the solder joints on the underside of the PCB.

The rear panel has only three holes to be prepared — one for the power cable entry (via a suitable rubber grommet), and the other two for the 1MHz reference signal and audio output connectors. Once these holes are cut, the two BNC connectors and grommet can be fitted, and the panel fitted to the case. Then it's possible to connect the two BNC connectors to the PCB, using light duty shielded wire.

If the lead from your power source is then brought inside the case through the grommet, and soldered to the two power pins at the rear of the power diodes, your test oscillator should be functionally complete and ready for testing and adjustment.

Testing and adjustment

To begin the testing, first set preset pots RV3 and RV4 to mid rotation. Then connect the earth probe of your multimeter/DMM to the circuit earth (say the outside of the RF or audio output connectors), and the active probe to the +9V rail on the main PCB — the rear end of resistor R42, for example. Now apply the power gingerly, and check that the DMM gives a reading of somewhere around 9V. It should be possible to adjust the reading to exactly 9V, using preset pot RV4.

If this seems OK, try moving the active DMM probe to the +5V rail (say the link next to capacitor C11). Needless to say, this should measure very close to 5V.

If either of these supply rail voltages are not present, or give readings well away from the expected values, switch off immediately and look for your wiring fault. Otherwise either your power supply, one of the regulators or other components may be damaged.

If both supply rails seem OK, and once you've set the +9V rail to its correct figure, you can proceed.

You should be seeing some sort of frequency reading from the LED displays. All four displays should be glowing, and the decimal point of either LD1 or LD2 should be glowing also depending on which range SW1 is set to. If one or more displays are 'dead', the odds are that you've installed it upside down — so turn off the power immediately, and investigate. If one *is* inverted, you'll have to desolder it carefully and reinstall it the correct way around...

By the way, try touching the heatsink for the 5V regulator. It should be quite warm by this stage, but not too hot to touch comfortably. If it's really HOT, you may have a short circuit somewhere on the 5V rail (or perhaps a digital IC fitted the wrong way around), so switch off quickly and investigate.

If all seems well, though, connect the rear-panel audio output to a scope. You should see a nice clean audio sinewave,




Fig.8: The traditional 'modulation trapezoid'. To set the modulation at 30%, the maximum RF amplitude A should be 1.85 times the minimum B.

of about 2.8V peak to peak and with a frequency of either 1kHz or 400Hz — depending on the values you chose for R20 and R21.

If there's no sinewave signal, or it's distorted by 'flats' at the positive and negative peaks, you'll need to adjust preset pot RV3. If there's no sinewave, turn it anti-clockwise until the oscillator springs to life and operates reliably; alternatively if there's a distorted sinewave, turn RV3 clockwise until the distortion is completely removed and the amplitude is about 2.8V p-p.

Now it's time to check the tuning span of the various ranges, so first set SW1 fully anticlockwise for the lowest range, and try turning the tuning pot RV1 between its two extremes. The frequency displayed should vary from slightly below 350kHz to about 850kHz.

Similarly on the second range, the frequency should vary from about 750-800kHz and a little over 2.4MHz; and on the third range, between about 2.4MHz and just over 7.8MHz.

If any of these three lower ranges won't tune over the correct span, you may have to modify the appropriate coil slightly. If both ends of the range are too low in frequency, the remedy is to remove a turn (or possibly two) from the 'finish' end of the coil. On the other hand if they're both too high, the remedy is to increase the coil by a turn or two — which is not nearly as easy, of course. You'll have to rewind the coil, in most cases.

If the actual span is not quite wide enough, you may have a BB212 varicap diode (CV2) with a relatively low maximum capacitance. In this case you can try adjusting preset pot RV4 to 'tweak' the +9V rail up a little, to give a wider voltage range, and/or try reducing the value of resistor R13 to give a lower minimum tuning voltage.

When these ranges seem OK, you can turn your attention to the highest range. Here the tuning range has to be set, using the tuning slug in coil L4. The procedure is to set SW1 for the top range, turn the tuning pot to its fully anticlockwise limit, and then adjust the slug until the display reads a little below 7.8MHz — say 7.6MHz. You should then find that when the tuning pot is turned to its fully clockwise limit, the oscillator should tune to a little over 30MHz.

The remaining adjustment is to set the modulation level, and for this you'll need a scope — preferably with a bandwidth of 20MHz or better, and with the ability to display two signals in X-Y fashion.

The procedure here is to connect the scope's Y (vertical) input probe to the emitter of output buffer Q8, with its earth clip to the earthy side of the RF output socket. The X input is then driven by the oscillator's rear-panel audio output. Then set SW1 for the second lowest range and the tuning pot for a frequency of around 1MHz. The CW/Mod switch (SW2) should be set to the 'Mod' position, and the scope controls adjusted to give a traditional 'modulation trapezoid' pattern as shown in Fig.8.

Preset pot RV5 is now adjusted until the modulation level is close to 30%, as indicated by the maximum RF ampli-

Omission from Parts List

Please note that the 12V/50mA lamp used for amplitude stabilisation in the audio oscillator of this project was accidentally omitted from the parts list given in the first of the articles. The lamp is one of the tiny 'grain of wheat' types, and is soldered directly into the PCB. I used one of the lamps with a small white plastic base, as used in car burglar alarms, and this gives quite low distortion.

tude A being about 1.85 times the minimum amplitude B.

Final comments

Your RF Test Oscillator should now be completed, and ready to have the case top added.


You'll no doubt have noticed that I haven't suggested adjusting the crystal oscillator trimmer CV1, to perform a calibration of the oscillator's counter and hence make its readings more accurate. That's because for most users, the accuracy of the instrument will probably be quite good enough with the trimmer simply adjusted to the middle of its range.

If you *do* wish to calibrate it for higher accuracy, the simplest approach is to use a high accuracy frequency counter (such as one with a temperature-controlled crystal timebase, or using timebase signals from our TV-Derived Frequency Reference of Oct/Nov 1993). Then it's simply a matter of feeding the oscillator's rear panel 1MHz reference signal to the counter, and adjusting trimmer CV1 until the counter reads as close as possible to 1.0000MHz.

An alternative approach would be to feed the two 1MHz signals to the X and Y inputs of a scope, and use Lissajous figures to set the Oscillator's timebase to the correct frequency.

If you don't have access to a high accuracy counter or a scope, another approach would be to use a communications receiver tuned to a convenient reference signal, like the 5.000MHz signal from Time and Frequency Standard Station VNG, in Llandilo. Connect a short length of wire to the oscillator's rear panel 1MHz output, and then tune trimmer CV1 until the fifth harmonic of the 1MHz output is at zero beat with the VNG signal.

That's about it. I hope you find the RF Test Oscillator a useful and convenient addition to your test bench. ❖



Your Computer is Australia's only computer magazine written for small business and home users.

Our editorial is locally written and is slanted with a 'hands on' approach for those who believe in PCs as a tool to increase business efficiency and productivity. As it says on our cover we've been Helping PC users since 1981.

ON SALE AT YOUR NEWSAGENTS NOW
or phone 1800 800 933

Forum

(Continued from page 45)

cheap nowadays. Even the heavyweights such as the 80C552 family cost NZ$25 each! Specialist parts are difficult to source (especially in New Zealand) and can cost the Earth.

While I clearly understand the problems you face, I think they are not impossible to overcome. I would like to contribute several suggestions as to how you might be able to overcome some of the problems:

1. Source code too long to publish: You can distribute a floppy disk with the magazine. I for one will not mind paying extra for the floppy.

2. Readers lack the facilities and tools to properly use the source code: You can distribute pre-compiled source code (HEX or BIN files). This way, readers who don't have compilers/assemblers can still use the program. I would also like to suggest a project that allows readers to program a simple micro (such as the Motorola 68HCO5K1). I can think of a very simple project that does this. Also, Motorola distributes their assemblers as freeware. You can then base most of your future projects on this micro (or any that you may deem more suitable).

3. Copyright of source code: To protect the copyright of your technical writers, you can include a licence agreement with packaged floppy disk. 'When you purchase the magazine, you also purchase one copy of the licence to use the firmware...' You may only want to distribute the compiled version in this case.

4. Royalties: If your technical writers require a licence fee to use their firmware, you can still protect them. Encrypt the compiled firmware (with something such as PKZIP for example). Readers who want to use the firmware can then send a sum of money to the writer and receive the key to decrypt the firmware.

5. Assembly Language Listing is not much fun to look at: I do not support publishing assembly language source code for the above reason. However, I think the algorithm should be fully explained. I am of the opinion that coding is trivial once a suitable algorithm has been designed. It is also helpful if comparisons to conventional logic can be made against the micro design. C compilers are also available for some micros.

6. Projects involving micros take longer to design: Rome was not built in one day!

I hope you will take these suggestions into consideration. I look forward to more interesting projects and articles in your magazine.

Thanks for your comments too, Mr Chuah, and we'll certainly take them into consideration. Your point 6 does seem a bit glib, though — magazines like *EA* don't have the resources of the Roman Empire to play with!

There are certainly a lot of things to consider with regard to publishing microcontroller-based projects, aren't there? And as many of the people who have contributed to the discussion have demonstrated, at least some of them are mutually conflicting.

Still, it's obvious that micro-based projects are going to have an ever-increasing role in electronics, and that because of this we're going to have to find ways of both giving you more of them, and making them more informative. All without causing undue sorrow to those who still want conventional 'hardware' type projects...

About all I can say for the present is that we'll be doing our best! ❖

JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS
JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS

JUNE AT JAYCAR

GERMAN MICRO SCREWDRIVER SET

NEW in 96

Another surplus stock purchase. Save a fortune over normal prices. These screwdrivers are made in Germany and are Wiha brand. They are made from high alloy chrome vanadium steel, and the tips have been acid dipped, then sandblasted for long life. The handles are black in colour with a red rotating end for ease of use. These top quality tools will give a lifetime of use.



Normal price for these would be $70.00 per set. The set consists of 10 screwdrivers as listed;

TIP	WIDTH	SHAFT LENGTH	TOTAL LENGTH
Slotted	1.5mm	40mm	118mm
Slotted	1.8mm	40mm	118mm
Slotted	2.0mm	40mm	118mm
Slotted	2.5mm	50mm	144mm
Slotted	3.0mm	50mm	144mm
Slotted	3.5mm	60mm	167mm
Slotted	4.0mm	60mm	167mm
Phillips	00	40mm	118mm
Phillips	0	50mm	144mm
Phillips	1	60mm	167mm

SET INCLUDES 10 SCREWDRIVERS

Cat. TD-2001 **$29.95** **Save about $40.00**

15" PROFESSIONAL PA SPEAKER

Power handling 200WRMS

See catalogue P24 for full details.

Cat. CG-2388

Cat. Price $239.00


June $200.00

Save $39.00



ETCH - YOUR - CAR WINDOWS THEFT DETERRENT

A car alarm or immobiliser will generally deter amateur car thieves. The "Pros" are another matter. One easy way to deter the professional car thief is to permanently etch your car's Vehicle Identification Number (VIN) on each piece of window glass. By doing this the thief will have to replace every piece of glass in order to remove the real identity of the car. (normally professional thieves skillfully change the VIN under the bonnet.) It is a very time consuming and costly process to change all the glass, so the thieves will simply avoid the hassle. Etch window systems are available on a basis where a "consultant" comes out and does your car - for a very solid price! Now you can do it yourself and save a fortune with the JAYCAR AUTO-ETCH KIT.



With this kit you will be able to permanently etch the unique VIN on up to six windows on your car. The kit comes with a special glass etching paste which works really well! You also get a set of etch resistant number and letter decals to make up your unique VIN on six windows. After you have done the job (fantastically clear instructions supplied) you wash up and apply two decals on the main driver/passenger windows which highlight the etched number and warns theives that the vehicle has been permanently marked.

NEW in 96

Start your own business!! You too can become a consultant and etch permanent protection for other people's cars for money. This is a valuable service that you will provide to your local community!

Grab a JAYCAR AUTO-ETCH KIT now and make it one bit harder for the mongrel thieves who make life a misery.

Cat. LA-5120 **$39.95**


Extra Etch Cream

Cat. LA-5125 $9.95

JAYCAR OPENS IN HOBART. 140 CAMPBELL ST.

PREPROGRAMMED AND LEARNING REMOTE CONTROL

This easy to use remote control does it all. Suitable for TV, Video, VCR, Hi-Fi, Satellite, Teletext. Controls up to 4 units.



•Preprogrammed with a huge up to date range of codes. Simply find your brand of equipment from the list of codes supplied and enter it in. If this fails, there is a "Setup by Auto Search" function in which the remote checks all its preprogrammed codes to find the one that will operate your equipment.

•Learning Capability Sometime with preprogrammed remotes, not all functions are included. This learning function allows you to add these odd functions into the remote.

Other features include:-

•Glow in the Dark Touch any button, and the channel selector and volume controls illuminate.

•Punch Through If you are operating the video, it allows you to adjust the TV Volume and Mute without leaving the Video Mode.

•Secondary Function Allows additional functions to be used - eg TV colour and brightness.

NEW in 96

•Anti Shock Has built in rubber edging for those falls.

•Water Resistant If you use it in the rain?

•Easy to Use Concise clear instructions supplied, and the button layout is very easy to use, and there is not hundreds of buttons to confuse you. Requires 4 x AAA batteries (not supplied)

Use Cat. SB-2426 Pkt of 2 $2.50 (2 packs required)

Cat. AR-1705 **$69.95**

DUOTECTOR BURGLAR ALARM PIR / MICROWAVE DETECTOR

NEW in 96

The Duotector is made in Japan, so you instantly know it is going to work very well. It is a Microwave and PIR Detector in one, and both need to be triggered before the alarm is set off, so you can feel very comfortable about false alarms. FEATURES: •MIC Doppler Module •Dual Element PIR Sensor •Latching Memory Function •Walk Test LED •LED Monitor for both Microwave and PIR •RFI Protection •Tamper Protection Cover •Microwave Supervised Output •Wall / Corner Mountable Design •Low current 18Ma at 12VDC •Automatic Temp Compensation •Range - 9m wide x 10m long



Cat. LA-5035 **ONLY $99.95**

JAYCAR BUDGET CAR SPEAKERS

All speakers supplied with grills, cables and mounting screws. 1 year warranty.

4" 2 WAY 20 WRMS

$29.95 pr

Cat. CS-2250



6" 2 WAY 40 WRMS

$39.95 pr

Cat. CS-2258



5" 2 WAY 25 WRMS

$34.95 pr

Cat. CS-2254



6" 3 WAY 50 WRMS

$47.95 pr

Cat. CS-2262



6 x 9" THREE WAY 65 WRMS

$79.00 pair Cat. CS-2268



JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS
JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS
JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS

AYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS

Jaycar ELECTRONICS No. 1 For Kits

Programmable Electronic Ignition Kit For Cars



REFER: SILICON CHIP MARCH 1996

You can program into the system: •the RPM at which ignition advance begins •RPM for full advance •max advance angle •REV limit •dwell angle •vacuum advance •number of cylinders •two digit security code. The unit features keypad data entry, tacho drive output, points/sensor input plus 7 segment display. This kit is designed to interface with our High Energy Ignition kit, KC-5030 $55.00. Both kits required. Kit includes PCB, keypad, pre-programmed micro, plus all electronic components and microswitch.

Cat. KC-5202 **$65.00**

NEW in 96

New Generation Plastic Power 175 Watt Amplifier Kit



REFER: Silicon Chip April 1996

A REAL POWERHOUSE!!!

Output power is 175 watts RMS into 4 ohms or 125 watts into 8 ohms with low distortion typically <0.003% THD, S/N of 114dB and 122dB A-weighted, frequency response -0.3dB down at 20Hz to 20KHz - with unconditional stability! This amplifier is much quieter than any CD player! The amp requires +/-56VDC rails for optimum output (prototype deliverd more than 200 watts!) - you will need our MT2140 300W torroidal transformer plus suitable filter caps - all information supplied with the kit. Pre-tinned PCB, genuine Motorola MJLZ1193/4 transistors, pre-wound inductor, high quality MKT poly capacitors, plus all specified electronic components including the genuine Bourne trimpot.

Cat. KC-5201 **$89.50**

NEW in 96

Automatic 10 Amp Battery Charger Kit



REFER: Silicon Chip May 1996

Although its possible to buy commercial chargers for under $50, it certainly won't get you out of trouble in a hurry if you have a flat battery. These types of chargers usually output 4A continuous, which means that it can take many hours to bring the battery up to scratch - usually the rest of the day or overnight. This kit will pump out 10A continuous and will automatically charge 6, 12 or 24V batteries. Output short protection, charge status, LED indicators, auto charge from high through medium to trickle. Push aside your old "toy" charger, this beaut design will get you and your car/boat/bike going again quickly on those cold winter mornings. Case, punched and silkscreened front panel, punched rear panel, torroidal, PCB, plus all specified electronic components supplied including high current leads and battery clips.

Cat. KC-5206 **$179.50**

NEW in 96

Subwoofer / Bridge Adaptor Kit For 12VDC



REFER: EA MARCH '96

This is an active subwoofer filter or amplifier bridging adaptor, and will operate from a single 12VDC supply making it ideal for use in car sound systems. It will accept either RCA line levels or speaker output levels and has a frequency response down to zero hertz. The kit is supplied complete with case, PCB, silkscreened front panel, RCA sockets, plus all electronic components.

Cat. KA-1784 **$22.95**

ESR & Low Ohms Meter Kit



See 1996 cat P13 for details. Cat. KA-1783

$69.50

Dual 12V Battery Isolator For 4WD



See 1996 cat P16 for details Cat. KA-1782

$44.95

HIGH VOLTAGE INSULATION TESTER KIT



REFER: Silicon Chip May 1996

If you build or repair mains operated equipment, its wise to test the insulation resistance between active and neutral to earth. The essential tester can measure from 1-2200 gigaohms, has five test voltages from 100 to 1000V, is battery operated and displays the readout on a 10 step LED display. Kit includes case, pre punched & silkscreened front panel, PCB plus all specified elec components. 9V battery required use SB2395.

Cat. KC-5205 **$89.50**

NEW in 96

Knock Sensor Kit For Cars




REFER: SILICON CHIP APRIL 1996

This kit warns you when engine knock is occuring, so that you can ease up and avoid costly engine damage. Indication is via a LED bargraph, and piezo buzzer, mounted inside a jiffy box that can mount near the dashboard. PCB, case, silkscreened front panel, electronic components plus parts to make the sensor all included. Cat. KC-5203 **$34.95**

NEW in 96

Improved Knightrider LED Scanner Kit



REFER: Silicon Chip May 1996

This kit simulates the row of scanned lights used on the car in the Knightrider TV series. It has one row of 16 LEDs and is more realistic than our previous kit (KC5042). This new version scanning is in one direction, then the other. The circuit can be modified to drive 12V 35W globes for use in 12V systems (extra components not included). Kit is supplied with PCB, LEDs plus electronic components.

Cat. KC-5204 **$19.95**

NEW in 96

PC Driven EGO Analyser



See 1996 cat P20 for details Cat. KA-1781

$37.95


Jacobs Ladder



See 1996 cat P18 for details. Cat. KC-5191

$29.95

Screecher Car Alarm



See 1996 cat P19 for details. Cat. KA-1675

$39.95

FM Wireless Microphone



See 1996 cat P11 for details. Cat. KM-3068

$12.95

WE ARE PROUD TO SAY THAT ALL JAYCAR KITS ARE


"AUSTRALIAN MADE"

AYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS

JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONIC
JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONIC

SAVE ON CAR AUDIO CABLE!!!

8GA POWER CABLE




Diameter 4mm. See Cat P120 for full specifications.

RED: Cat. WH-3060 BLACK: Cat. WH-3062

was $2.95/m - was $220/100m roll

NOW $2.50/m - $180/100m Roll

4GA POWER CABLE




The really thick stuff.
Diameter 7.7mm

RED: Cat. WH-3064 BLACK: Cat. WH-3066

was $7.95/m - was $325/50m roll

NOW $6.50/m - $250/50m Roll

OFC FIG 8 TRIPLE SHIELDED



With central switching wire.
Cat. WB-1509

was $3.50/m - was $250/100m roll

NOW $2.50/m - $190/100m Roll

Save On Professional Quality OFC Reference Series RCA Leads

SAVE $$$$



These Reference Series use OFC shielded low capacitance cable with a central lead wire for remote switching of car amps, or for extra grounding on home Hi Fi. Cable is figure 8 OFC blue colour with an OD of 5mm per side. Plugs are superb quality gold with nickel metal covers. Each lead is colour coded with red and black RCA plugs. Each lead has two RCA plugs on each end.

Specifications:

- Material: Oxygen Free Copper
- Stranding: 10/0.12mm
- Shield type: Spiral
- Ground wire: 10/0.12mm
- Capacitance: 68.8PF/M
- Size: 0.40mm
- Diameter: 0.75mm
- Standard: 45/0.12mm
- Resistance: 0.0385Ω/M
- Impedance: 65Ω at 1MHz

0.5 metres	was $19.95	June $14.95	Save $5	Cat WA-1060
1.5 metres	was $24.95	June $18.95	Save $6	Cat WA-1062
5.0 metres	was $34.95	June $25.95	Save $9	Cat WA-1066

NEW TOOLS

These are a range of handy bench tools to make your project building easier.

NEW '96

The clamps and set squares are made in New Zealand and the Mitre Box Set is made in the USA. These tools will give years of service, and won't break the first time you use them. As with most things, quality costs a little more.

12mm G Clamp

NEW '96

Very small G clamp for those finicky jobs where you need that extra hand. Plastic "G" with steel thread. Max opening 12mm.

Cat. TH-1954 $5.95



24mm G Clamp

For those slightly bigger jobs. Plastic "G" with steel thread. Max opening 24mm.

Cat. TH-1956

$7.50

150mm Sliding Bar

NEW '96

This is basically an adjustable G Clamp. The clamp slides up the bar which in turn varies the jaw opening immensely. Jaw opening up to 70mm. Bar is aluminium. A very handy tool. Total length is 153mm.



Cat. TH-1958 $13.95

MITRE BOX SET

MADE IN USA



Consists of an aluminium mitre box with a Razor saw set. Ideal for hobbyists. Mitre box length 137mm, diameter 40mm. Saw blade length 126mm.


NEW '96

Cat. TH-1950 $24.95

4 PIECE SET SQUARE SET

NEW '96

Consists of a 4" (100mm) Set Square, 3" (75mm) Set Square, 4" (100mm) Adjustable Bevel and a Centre Finder. All have steel straight edges with plastic handles. Made in New Zealand.



Cat. TH-1952 $22.95

SHORT CIRCUITS

LEARNING ELECTRONICS IS FUN

- NO PRIOR KNOWLEDGE OF ELECTRONICS NEEDED
- GAIN VALUABLE & EXCITING KNOWLEDGE AND HAVE FUN DOING IT
- TOTALLY SAFE! NO SOLDERING, 6V POWER SOURCE
- IDEAL FOR ALL AGES
- NO CONSTRUCTION SKILLS NEEDED
- DESIGNED & MADE IN AUSTRALIA

Some of the exciting projects that you can build from this book include:

- Short circuit tester
- "Magic Eye" light alarm
- Police siren
- Electronic organ
- Sound effects unit
- Light chaser
- Solar powered radio
- 3 types of transistor amplifiers
- Computer type circuits
- And many many more



SHORT CIRCUITS BOOK AND PROJECT KIT

Apart from the book, you get the baseboard, plenty of spring terminals and ALL the components required to build every project in the book, INCLUDING the bonus projects!

Cat. KJ-8502 **only $24.95**

SHORT CIRCUITS BOOK

This full colour 96 page book, which measures 205mm x 275mm is lavishly illustrated with over 100 drawings and diagrams. Each project features components which are "state of the art". The projects are fun to build but, perhaps more importantly, are relevant to the electronics scene in the '90's. It is a great read in itself and far superior to cheap alternatives.

Cat. BJ-8502 **only $12.95**

SHORT CIRCUITS PROJECT KIT


The complete kit of parts available separately. This includes plastic baseboard, spring connectors and all components needed to complete every project in the book. No instructions are supplied with this kit as they come in the book which is available separately.

Cat. KJ-8504 **only $14.95**

NEW SEMICONDUCTORS

Cat. ZT-2227	MJL21193 PNP Transistor	$17.95
Cat. ZT-2228	MJL21194 NPN Transistor	$17.95
Cat. ZC-4553	4553 3 Digit BCD Counter	$2.75

PRINTER LEAD BARGAIN!!!




D25 PLUG TO CENTRONICS PLUG - 10M LONG

Cat. PL-0950 Cat Price $19.95

June $12.95 Save $7

VCR Washer Kit



Universal VCR, CD player, video camera plastic washer set - 175 pieces. Such plastic and nylon washers are very common in VCR mechanisms etc. Washers must be replaced upon removal. The pack includes 175 standard and split washers. **Cat. HP-0100**

was $14.95

NOW $7.50

HALF PRICE

JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONIC
JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONIC
JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONIC

JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS

CAR SPEAKER KIT SYSTEM

AMAZING SCOOP PURCHASE!!
We have purchased a large quantity of these systems and have passed the savings on to you!!! Consists of 2 x 6.5" bass enclosed polypropylene woofers, 2 x 1" dome tweeters and 2 x 2 way high power crossovers.
•Power handling: 70WRMS (180WPMPO) •Impedance: 4 ohms
•Freq Response: 60Hz-22KHz
•Sensitivity: 91dB/1W/1M. Comes complete with mounting screws and speaker wire. This system retails in the market for over $150.



Cat. CS-2276 **Save Over $50** **ONLY $99**

1 Amp Regulated Power Supply Bargain


This power supply gives 6,9 or 12V DC at 1 amp.
Unit is regulated, so gives exact stated output voltage at any current draw up to 1 amp. Supplied with 7 reversable plugs.



Cat. MP-3032
Cat Price $39.95 June Only $29.95 Save $10


SAVE $$ ON AIR SPACED 75Ω COAX

100 METRE ROLL Cat. WB-2006
Was $95 Now $69
30 METRE ROLL Cat. WB-2007
Was $29.95 Now $25
PER METRE Cat. WB-2006
Was $1.35 Now $1.10



JAYCAR LOW COST 240V SOLDERING IRON

Ideal for the hobbyist and handyman. Our lowest price 240 volt quality iron has a stainless steel barrel. 25 watt. Cat. TS-1450 ***Normally $17.95***



JUNE $12.95 SAVE $5.00

DOLBY PRO-LOGIC SURROUND SOUND KIT Cat. KC-5175/6 only $199.50



DOLBY PRO-LOGIC KIT WITH CENTRE/REAR AMPLIFIERS Cat. KC-5200 $379



24 V REDUCER To 3, 4.5, 6, 7.5, 9, 12V


Regulated at 1.2 amp
Cat. MP-3056
Was $29.95
June $20
Save $9.95



JAYCAR WHOLESALE (02) 743-5222


Anti-Static Workplace Mat

This mat, measuring a generous 550W x 300Dmm is ideal for anyone who repairs or services sensitive electronic equipment. The mat is over 3mm thick, has a hard wearing face over a dense sponge rubber base. It has a very pleasant feel. Two snap-type connectors are on the mat at one end allowing left or right handed use for connection to antistatic wrist straps, the equipment you are working on, earth etc. A connector and coded lead is included with the mat. The mat can also be used as an anti-static base for computer keyboard.



Cat. TH-1782 ***$19.95***

CANNON TYPE PLUGS



Every day low prices on these black anodised plugs and sockets.

3 Pin Chassis Male	$3.50	Cat. PP-1010
3 Pin Line Male	$3.95	Cat. PP-1012
3 Pin Chassis Female	$5.50	Cat. PS-1014
3 Pin Line Female	$3.95	Cat. PS-1015

6 Sound Siren Bargain

Limited Qty Available
This is like our LA-5705 siren (see cat P155) but the different sounds are not selectable. They sound one after the other. Your alarm will stand out against the others.



Cat. LA-5710 **only $20**

Jaycar ELECTRONICS

HEAD OFFICE
8-10 LEEDS ST RHODES 2138
PHONE: (02) 743 5222
FAX: (02) 743 2066

Quality System — Quality Endorsed Company ISO9002 Lic 6143 Standards Australia

WHOLESALE
PHONE: (02) 743 5222
ORDERS: 1800 620 169
FAX: (02) 743 3070

MAIL ORDERS
PO BOX 185 CONCORD 2137
ROAD FREIGHT ANYWHERE
IN AUST (up to 20kg) $14.00

MAIL ORDER - PHONE
FREE CALL - ORDERS ONLY
1800 022 888
HOTLINE (02) 743 6144

bankcard MasterCard VISA Diners Club International AMERICAN EXPRESS eftpos

ADELAIDE SA •194 Wright St (Cnr. Selby St)•Ph:(08) 231 7355 •Fax:(08) 231 7314•Mon/Fri:9-5.30•Fri:8.30•Sat:9-4pm
BURANDA QLD •144 Logan Rd•Ph:(07) 3393 0777•Fax:(07) 3393 0045 •Mon/Fri:9-5.30•Thurs:8.30•Sat:9-4pm
CANBERRA ACT •11 Kemble St. Fyshwick•Ph:(06) 239 1801 •Fax:(06) 239 1821•Mon/Fri:9-5.30•Sat:9-1pm
COBURG VIC •266 Sydney Rd•Ph:(03) 9384 1811•Fax:(03) 9384 0061 •Mon/Fri:9-5.30•Fri:8.30•Sat:9-4pm
MELBOURNE CITY •Shop 2,45 A'Beckett St•Ph:(03) 9663 2030•Fax:9663 1198 •Mon/Fri:8.30-5.30•Fri:8.30•Sat:8.30-4•Sun:10-4pm
SPRINGVALE VIC •887-889 Springvale Rd Mulgrave. Nr Cnr. Dandenong Rd •Ph:(03) 9547 1022•Fax:(03) 9547 1046 •Mon/Fri:9-5.30•Fri:8.30•Sat:9-4pm

SYDNEY CITY •129 York St•Ph:(02) 267 1614•Fax:(02) 267 1951 •Mon/Fri:8.30-6pm•Thurs:8.30pm•Sat:9-4pm
BANKSTOWN •363 Hume Hwy Cnr Meredith St•Ph:(02) 709 2822•Fax:(02)709 2007•Mon/Fri:9-5.30•Thurs:8.30pm•Sat:9-4•Sun:10-4pm
GORE HILL •188 Pacific Hwy (Cnr. Bellevue Ave)•Ph:(02) 439 4799•Fax: (02) 439 4895•Mon/Fri:9-5.30•Thurs:8.30•Sat:9-4•Sun:10-4
NEWCASTLE •830 Hunter St. (Cnr Stewart Ave)•Ph:(049) 653 799 •Fax:(049) 653 796 •Mon/Fri:9-5.30 •Sat:9-4pm
PARRAMATTA •355 Church St (Cnr. Victoria Rd)•Ph:(02) 683 3377 •Fax:(02) 683 3628•Mon/Fri:9-5.30•Thurs:8.30pm•Sat:9-4•Sun:10-4pm
PENRITH •199 High St•Ph:(047) 21 8337•Fax:(047) 21 8935 •Mon/Fri:9-5.30•Thurs:8.30•Sat:9-4pm•Sun:10-4pm
PERTH •326 Newcastle St Northbridge•Ph:(09) 328 8252 •Fax:(09) 328 8982 •Mon/Fri:9-5.30•Sat:9-4
RHODES •8-10 Leeds St•Ph:(02) 743 5222•Fax:(02) 743 2066 •Mon/Fri:9-5.30

POST & PACKING $10 to $24.99=$4.00 $25 to $49.99=$5.00 $50 to $99.99=$7.00 OVER $100=$8.00

JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS JAYCAR ELECTRONICS

Construction Project:

'STEAM WHISTLE' FOR MODEL BOATS & TRAINS

Does your latest model seem to be lacking something? A model steam boat cruising around on the water in near silence isn't terribly realistic; neither is a model steam train pulling away from a station with nothing but the whine of an electric motor behind it. This compact circuit can provide your model with a distinctive steam whistle sound, giving your models that extra touch of realism.

by GRAHAM CATTLEY

If you've worked long and hard on your model train layout to make it look great, why not add that final touch and make it *sound* great as well? This project can reproduce the sound of either a steam boat or train whistle quite realistically, due to the fact that it uses two oscillators to produce the note, as well as a white noise generator which, when mixed with the note, gives it that characteristic steam whistle sound. This design improves on existing designs, in that the note produced can be easily altered to suit the size and type of model you are using.

Two notes


If you listen to a real steam whistle, be it on a vintage boat or locomotive, you probably won't hear just one note, but rather a chord of two slightly different notes mixed together.

This is because the actual whistle itself is usually made up of a pair of pipes of differing diameters or lengths, tuned to give a harmonious chord. This, along with the sound of escaping steam as the whistle blows, is what makes steam whistles sound so distinctive.

For the musically inclined, one note is usually either a major fifth higher than the other (that's a spacing of seven semitones, like the notes C - G, D - A, E - B, etc.), or a major third higher (four semitones, C - E etc.). Of course, other tunings are used, and in this steam whistle project we have included trimpots for each note, so that you can adjust the tuning to suit both your ear and the type of model. (After all, you don't want your model train emitting a blast befitting a departing ocean liner, do you?)

In fact, this design allows you to change almost every aspect of the note, with adjustments for the frequencies of each of the two oscillators; the balance, or percentage of each of the two tones in the output; and both the amplitude and percentage of steam in the note — as well as a way of adjusting the small delay between the higher and lower notes starting up.

As you can see, with such control over the note produced, this whistle should be able to emulate the sound of almost *any* real steam whistle reasonably well.



The circuit


The circuit falls rather neatly into four major blocks: two audio frequency oscillators, based around Q1 and Q2; a white noise generator (Q3 and Q4); and a mixing/amplifying stage consisting of trimpots VR3-5 along with U1, an LM380 amplifier IC capable of delivering around two watts into a 4Ω loudspeaker.

Looking at one of the oscillators, you can see that its frequency is determined by the distinctive 'Twin-T' feedback network. By using this style of oscillator, we can produce a reasonable sine wave output which is easy to adjust in terms of frequency using just one variable resistor.

The two oscillators can be adjusted to run over a wide frequency range, with the one labeled 'A' in the circuit diagram set to run at a slightly higher rate (250-650Hz as opposed to 250-500Hz), due to the lower values for R7 and R8 in the feedback network.

The output of these two oscillators is taken from the wiper of trimpot VR3, which allows you to vary the output level of each note. This control is labeled 'Balance' on the PCB overlay diagram, and with it you control the proportion of the two notes in the output.

The 'steam' sound is produced by the white noise generator based around Q3 and Q4. In this part of the circuit we are taking advantage of a characteristic of the PN junction inside all silicon transistors, namely its reverse bias leakage current.



The two oscillators based around Q1 and Q2 form the heart of the whistle, with a white noise generator (Q3 and Q4) providing the 'steam' sound. The six trimpot adjustments allow you to produce a wide variety of steam whistle sounds.

If the circuit's supply voltage is greater than the reverse breakdown voltage of this junction, transistor Q3's base-emitter junction will break down and current will flow backwards through it. By including a 330k resistor, R10, in series with the base, the current through the transistor is limited to approximately 40uA, preventing the junction from being damaged. The noise produced across this junction due to the reverse current flowing through it is then amplified by Q4, set up in a simple auto biasing configuration.

The three audio signals (the two tones from the oscillators and the white noise) are then mixed at the top of the volume control VR5, with R13 attenuating the steam sound output so as not to swamp the notes from the oscillators. If the transistor that you are using for Q3 seems to be producing a particularly low level of white noise, the value of R13 can be reduced to give a higher output volume for the steam.

An LM380 was the obvious choice for the power amplifier, as it provides a reasonable output power without the need for an external heatsink; by using the copper foil pattern on the PC board, adequate heatsinking can be achieved while keeping the unit compact. The LM380 is used here in a somewhat standard configuration, heavily decoupled by C16 and C17, with R14 and C14 acting as a Zobel network which helps to improve the amp's stability. Also, C19 was included to prevent the amp from breaking into high frequency oscillation, as well as filtering a lot of the harsh higher frequencies out of the white noise, making the note sound a little more 'friendly'.

Note shaping

When designing the prototype, we found that while the circuit produced notes that sounded very realistic, something was lacking somewhere...

Ah yes — *real* steam whistles don't switch sharply or cleanly on and off; they have a reasonable attack and decay, and one note (usually the lower one) often comes in a little later than the the other.

The simplest way to implement this, as it turned out, was to include a 50k pot in series with the positive supply to the oscillators. When the power switch/pushbutton SW1 is closed, the voltage across the 10uF capacitor (C18) slowly rises. This causes the oscillators to slowly spring to life, and increase in output volume as they do.

As the feedback network in the lower frequency oscillator has a longer time constant than that in the other oscillator, it takes slightly longer to 'come up' than the higher one — simulating a real whistle quite accurately.

This method of shaping the tone has another advantage, in that as the switch is released the oscillators keep running on the stored charge in C18. This charge quickly dies away, but it gives a slight 'tail' to the note, again making it that much more realistic.

By adjusting the value of VR6, you can vary the rate of the rise in volume (and also the delay between the two notes coming on), from a short sharp tugboat 'toot' to the fairly long drawn-

out sound often heard from steam trains.

You may have noticed that the amplifier is left running the whole time, and not switched on and off with the rest of the circuit. This is to prevent the all too familiar 'Thump' as the amplifier turns on — a sound that steam whistles are not known for. Q4 is similarly connected permanently to the supply rail, as it was found to thump a bit on switch-on as well.

A jumper on the PCB allows you to select between continuous steam, or having it switch on and off with the note. One small thing to point out here is that in order for this circuit to operate correctly, it needs to run off at least 11V due to the voltage requirements of the white noise generator. (The supply voltage needs to be greater then the B-E reverse breakdown voltage of the transistor Q3, which for a BC548 is around 10V). Running the whistle at a lower supply voltage won't hurt anything — you just won't get any steam noise in the note.

The other two links on the board allow you to disable either note A or note B, independently, if you wish. All these two jumpers do is connect the collector resistors of the two oscillators to their positive rail. In contrast, the steam jumper selects either switched or continuous steam sound by connecting the steam generator's positive rail to either the switched or unswitched side of SW1. (Of course removing the steam link 'C' all together will turn off the steam, as will winding VR4 fully anticlockwise.)

Construction

Start construction of the steam whistle by installing the six PC pins in the holes on the right-hand side of the board. These are sometimes a tight fit, and you may find that a small pair of pliers comes in handy. Don't forget to solder them to their pads, when they're in place.


This done, install the four wire links on the board, keeping them as flat and straight as possible. You have a choice with the steam link (C), as it can be fitted in one of two ways on the board. For now, fit it in the upper position (switched steam) — you can always reposition it once you know that the whistle is working correctly.

Mount the resistors next. There's a few of them on the board, and it is quite acceptable to verify each value with a multimeter before soldering it in — especially with the newer five-band 1% tolerance resistors that are somewhat prevalent these days.


The capacitors can now be installed, ensuring correct polarity with the electrolytics, C13, C15, C17 and C18. These are mounted with their positive lead towards the top of the board, except C15, which has its positive lead on the left.

The five trimpots are next, and these can be either the horizontal or vertical types — although you may find that the horizontal style will be easier to adjust once the board is mounted in position.

Finally, install transistors Q1-4 and the amplifier IC, U1. Watch the orientation of these parts, and check them against the component overlay diagram before soldering them in. Make sure that your soldering iron is good and hot when soldering U1, as you'll find that the large copper areas around the IC — used here as a heatsink — tend to perform their function a little *too* well and soak up the heat needed for the joint. It's best to leave the soldering iron to heat up for a few seconds after you solder each pin, otherwise you'll find that the iron will start sticking to the joints. Don't worry too much about overheating the IC, as it is designed to take a little heat in operation and is quite robust.



Use this component overlay as a guide when installing the parts on the board. The steam link 'C' can be installed in either the upper or lower position, and don't forget the small link betwen VR4 and VR5.



This close up clearly shows how the components are mounted on the board. Note that a 50k log potentiometer could be connected as a volume control instead of the trimpot VR5, making volume settings a little easier.

PARTS LIST

Resistors

(All 1/4 watt 5%)

R1,2	100k
R3,6,11	1M
R4,5	4.7k
R7,8	82k
R9	10k
R10	330k
R12	2.2k
R13	470k
R14	2.7 ohms
VR1,2,4,5	50k trimpot, horiz. or vert. mount
VR3	1M trimpot, horiz. or vert. mount
VR6	10k trimpot, horiz. or vert. mount

Capacitors


C1,7,11	10nF MKT polyester
C2,3,8,9	4.7nF MKT polyester
C4,5,6,10, 12,14,16	0.1uF MKT polyester
C13	4.7uF 16VW electrolytic
C15,17	470uF 16VW electrolytic
C18	10uF 16VW electrolytic

Semiconductors

Q1,2,3,4	BC548 or equiv. transistor
U1	LM380 5W audio amp IC

Miscellaneous

PCB 11.5 x 4.2mm, coded 96sw6; 8Ω speaker; Normally open pushbutton; 50mm tinned copper wire; hookup wire, solder, etc.



Here's the full sized PCB pattern for those of you who make your own boards.

All that remains now is to connect a suitable pushbutton and loudspeaker, and to connect the unit to a 12V DC supply, as shown in the overlay diagram.

As this project was designed to be mounted inside a model boat or train (or perhaps under a layout), the details for mounting the PC board are obviously left to the reader.

Adjustments

As we mentioned before, there are lots of trimpots in this project, allowing a wide range of sounds to be produced. Probably the best way to achieve the sound you want is to get twiddling!

You'll find though, that you'll get better results if you keep the B oscillator (adjusted by VR1) running at a frequency lower than the A oscillator (VR2), as this helps the turn-on delay — due to VR6/C18 — operate a little more effectively. Apart from that, you should find that you can create a wide range of steam whistle sounds which should suit almost any application.

If you find that you can't get the frequency range that you need, you can change the values of the resistors in the feedback networks for either of the oscillators (R1/R2 and R7/R8), to say 33k and 27k respectively. These lower values will result in both oscillators running in the higher octaves, suitable for smaller steam trains.

Of course you can increase these values to give lower notes (for a passenger liner perhaps), but you may find that you will need to increase the value of C2-C3/C8-C9 to 5.6 or 6.8nF to get the oscillators working correctly.

Speakers

The overall volume of the Steam Whistle is largely dependent upon the size, impedance and mounting of the loudspeaker, and this may be dictated by the space available within your model. While a small 57mm (2-1/4") 8Ω speaker would certainly be adequate for small train layouts, a larger (4") speaker of the automotive type is more the go for the larger models.

No matter what size speaker you end up using, you'll get much better results if you follow a couple of basic rules:

Firstly, the impedance of the speaker you use will have a large effect on the amount of power the whistle's amplifier will put out — the lower the impedance, the higher the volume. Eight ohms is the most common impedance, but if you use a 4Ω speaker you'll find that you can get more power out of it.

The other major factor affecting the sound quality of the whistle is the mounting of the speaker within the model itself. Your best bet is to mount the speaker so that it is firmly secured to a mechanically stable part of the model.

This isn't the place to go into the intricacies of loudspeaker cabinet design, but if you feel that you're not getting adequate volume, try experimenting with different speaker positions.

Ideally, you want to prevent the sound waves coming from the back of the speaker from cancelling out those from the front. By mounting the speaker so that there is no direct path for air to flow between its front and back, you should get a reasonable increase in volume, particularly for the lower frequencies. ❖

EA'S COMPUTER BBS

As a part of its service to readers, *Electronics Australia* operates a Reader Information Service Bulletin Board System (BBS). This provides a wide range of useful information, for convenient access and downloading by readers equipped with a PC and modem.

The BBS is ANSI-compatible and operates for 24 hours per day, seven days a week. Call it on (02) 353 0627, with your modem set for full duplex, 8N1 and any standard speed to 28,800b/s.

SOLAR PANEL

warehouse

manfacturers / wholesale / retail

Huge range of panels
Crystal or amorphous from
10 mA to 5000 mA.Mega
panels, 30% extra power

Free delivery this month over $50

SolarCorp

259 Broadway BROADWAY ph 02 5664340

READER INFO NO. 8

Want to get more in-depth with the 'how', 'why' and where in the world of Music, recording, Multimedia and more? Read

AUSTRALIAN DIGITAL
MUSIC, RECORDING, MULTIMEDIA

To subscribe to *Australian Digital* magazine phone TOLL FREE 1800 800 933 - Sydney residents phone (02) 353 9992 - and have your credit card details ready. Or send your name, address and phone number, with your payment of $35.00 for 6 issues (cheque, credit card details or money order) to: Federal Publishing, Subscriptions Dept., Reply Paid No. 3, PO Box 199, ALEXANDRIA NSW 2015 (no stamp required) or fax (02) 353 0967.

on sale NOW

ALTRONICS COMPONENTS

ALTRONICS Fax Order Line: (09) 328 3487




ALTRONICS 1996 Electronic Components Catalogue

Yours Free this Month When You Call Us On 1-800 999 007.

Our 1996 Catalogue now contains even more fantastic products and greater value than ever before. We still offer the technical help that only a staff of electronic enthusiasts like yourself is able to give. Of course, in addition to this we have our Famous Overnight Delivery Australia Wide, with Credit Card phone orders up to 4pm (E.S.T.) Monday to Friday. Quality products at direct import prices, means you save up to 50%!

Regards,
Jack O'Donnell, Managing Director *Jack O'Donnell*

Discolight Light Controller Kit



Combine it with our K 5790 strobe kit for a spectacular light show!

(See SC July/Aug '88) The Discolight flashes party lights on and off in beat with music from your amplifier.
Features: • 4 light channels controlled by 4 separate audio channels • Forward reverse and auto-reversing chaser patterns • Simultaneous strobe on all four channels • Alternating light patterns • Music modulation available on chaser strobe and alternate patterns • Inbuilt microphone or direct inputs for beat triggering or audio modulation of lights • Sensitivity control • Individually pre-settable sensitivity levels for each channel • Front panel LEDs mimic light display • Altronics Kit pre-punched and silk screened

K 5805 **$179**

Beat Triggered Strobe Kit

Great for DJ's, Theatres, Skating Rinks etc



(See AEM July '85) Designed by Australian Electronics Monthly. Flashes in time to your music. Will also work as normal strobe. Exclusively customised by Altronics into our H 0480 Instrument Case, making construction a breeze and improving stability, safety and overall appearance. Two tube option available which boosts lighting output.

K 5790 Strobe Kit **$109**
K 5795 Two Tube Option **$18.95**

Single Cell Ni-Cad Discharger Kit



(See SC May '93) Do you have problems with nicads that are not performing to their maximum capacity because of 'memory' problems. This low cost single cell discharger will correctly discharge any single nicad cell so that it can be recharged to full capacity.

K 1642 Was $24.95 **Now $16**

Economy Dual Rail Power Supply Kit

Ideal for Op-Amp prototyping and experimenting



(See SC Oct '94) Especially designed for the experimenter. No mains wiring required as the supply uses a 16V AC 1 amp plugpack. Outputs include 11 switch selectable dual rail voltages - 1.25V, 1.5V, 3V, 4.5V, 5V, 6V, 7.5V, 9V, 12V, 13.5V and 15V. Features on/off load switch, and drop out indicator. Up to 500mA of current available. Supplied complete with screen printed case.

K 3240 Normally $39.95
This Month Only $29
M 9125 16V AC Plugpack to Suit **$17.95**

Current Limited Bench Top Power Supply Kit

A Power Supply for the Experimenter Over 5000 Sold!



(See EA Jan '85) Our most popular power supply kit. Offers excellent value and performance. Features a variable output of 3 to 30V DC and 0 to 1 Amp current limiting. Ideal power supply for the experimenters, hobbyists, technicians etc.
Features: • Variable Output • Short Circuit Protected • Full 1 Amp Available • Variable Current Limit • Separate Earth Terminal • Dual Scale Meter

K 3210 **$109**

IR Remote Control Extender Kit


Control the Video in the Lounge Room From Your Bedroom!



(See SC April '94) This kit will enable infra-red (IR) remote control of your VCR/CD etc from separate rooms. It works by receiving the infra-red signal from your remote control and then re-transmitting it to your VCR/CD etc. Ideal for watching the video on a second TV in a separate room.

K 5900 **$49**
M 9102 12V DC Plugpack **$11.95**

Insulation Tester Kit NEW



(See SC May '96) This high voltage tester can be used to test electrical mains wiring leakage and the breakdown of insulation in transformers, automotive generators, and alternators. Its an ideal piece of test gear for domestic, industrial or automotive electricians. Powered from a 9V battery (not supplied), and is enclosed in a Jiffy box with metal lid. It even includes the test probes!

K 2557 **$79**

Check insulation of transformers, motors, alternators, etc.


Low Cost Temperature Probe



(See EA Jan '88) Here's an easy to built probe which adapts a multimeter or electronic voltmeter into a general purpose thermometer. Measures accurately from -20°C to 120°C.

K 2570 **$21.95**

40 Watt Amp Module Kit



(See SC March '94) Very compact module, designed around the National LM3876 50W power amplifier IC. The overall performance is quite amazing for such a simple design. Kit supplied complete with all parts including the specified heatsink.

K 5114 **$39**

2 Way Active Crossover Kit



(See EA Jan 92) This great kit enables you to customise your sound system in your car or at home. The circuit simply connects between the audio source and the amplifiers. There are two outputs one for bass and another provides signal for the upper range. Thus each amp is dedicated to a frequency range (i.e. one for bass, one for midrange and treble). Because no passive crossover is required in the speaker one per channel is required. Operates on + and - 15V rails. The result is much better sound with less distortion.

K 5570 Was $24.95 **Now $19.95**

VOX Relay Kit

Great for VOX keying of amateur radio or CB transceivers!



(See EA April '82) This versatile VOX circuit is triggered whenever a noise or sound is made, causing the relay to close for a preset time. Requires 12V DC power supply (not supplied) and a microphone. Reaction sensitivity and on time are fully variable. Can be used for tape recorders, slide projectors, paging systems, hands-free intercom switch over or a push-to-talk button replacement.

K 5540 **$19.95**

Low Ohms Adaptor for DMM's

Measure resistive losses in connections, over cable loops, and shunt resistances!



(See SC Feb '88) As we all know, it's difficult to obtain accurate resistance measurements below 50 Ohms or so with conventional multimeters. This adaptor plugs directly into a digital multimeter via built-in banana plugs enabling measurements from 1kΩ to 0.01Ω (10mΩ). Suits most DMM's.

K 2518 Was $33.95 **Now $22**

Calling All Musicians:

Check out this professional looking but easy to build DI Box. DI Boxes enable you to run long lengths of cable from a microphone, guitar, or any unbalanced equipment to balanced input mixers or amplifiers, with virtually no induced noise. It does this by converting unbalanced lines to balanced lines.

Quad DI Box Kit



(See EA June '91) The K 5555 allows you to use four separate instruments or microphones. The output of the DI boxes are XLR sockets. This unit also has a 20dB pad switch so you can use a wide variety of different impedance inputs.

K 5555 **$89**

Doc.JH469


OVERNIGHT DELIVERY

Aviation Headset

Now Supplied With Doubled Cushioned Headband for Extra Comfort!

1000's Sold Across Australia-Includes 2 Year Warranty!

It was not to long ago when spending $450.00 on an Aviation Headset was not uncommon. Altronics changed all that when we released our C 9070 Aviation Headset for $199.00. Add to this enhanced microphone, improved lead shielding and headband comfort these headsets must be the best value for money in Australia!



BONUS FREE headset carry case valued at $19.95 to the first 100 callers only!!

C 9070 $199

Modular Crimping Tool


Rugged steel and polycarbonate construction. Crimps 4, 6 and 8 way modular connectors. Inbuilt cutter and stripper with stops for correct stripping length. Replacement blades available.



T 1568 $65

T 1569 Replacement Blade Set **$5.95**

Impedance Meter



Measuring a transformer with a standard ohm meter will not give accurate results because it is measuring with a DC signal, not AC. This invaluable unit is fantastic for checking transformers and speaker impedances. For those people dealing in PA equipment, the built in tone generator enables an entire PA system to be checked before the amplifiers are connected. Uses one 9 Volt battery. (Not supplied). Three ranges enable accurate measurement of 2 - 20,000 ohms. Accuracy mid range typically ±5%.

K 2550 Kit Version **$99**

K 2551 Built Version **$159**

Micron 20 Watt Soldering Iron

A fantastic general purpose iron for the hobbyist or beginner and is ideal for kit construction. It features a high efficiency patented heating element, with a 370°C fixed temperature. Tips are iron clad and chrome plated for long life. This iron is fully energy authority approved and is supplied with a 1.5mm conical tip.

Normally $29.95!



Great for the Beginner or Hobbyist!

T 2420 $19

Professional Gas Iron Kit

The advanced *CADIK* Soldering Iron offers a convenience and a range of functions that redefine the limits of soldering. This kit consists of the *CADIK* Gas Soldering Iron supplied in a handy carry case with a range of tips and accessories.

Features: • See through gas chamber • Built in ignition cap • Uses standard butane gas • Supplied with safety stand, cleaning sponge, solder dispenser, blow torch, hot air blower and hot knife cutter



T 2502 $74

BONUS OFFER!

Limited to the First 100 Callers! Buy the T 2502 CADIK Gas Iron Kit and get a T 1200 200g roll of solder and a T 2447 150g butane gas refill valued at $12.45 *FREE!*



CB Type Microphone

Low impedance dynamic microphone with curly cord (including switching pair). Suitable for CB's, radio transceivers, PA systems etc. Supplied complete with mounting clip. Does not include plug.



C 0333 Was $16.95 **Now $7**

Alcatel/Cannon 3 Pin Plugs & Sockets



Huge savings on Altronics' range of high quality ALCATEL 3-pin XLR type plugs and sockets. These are professional grade connectors which represent a no-compromise approach to connector technology, with rugged construction, secure mechanical characteristics and low introduced noise levels. Used in band PA setups, DJ systems, nightclubs and more. Ideal for musos and professionals alike!!

	Normal	This Month 4 or More
P 0900 3 Pin Line Female	$8.00	**$5**
P 0902 3 Pin Line Male	$7.30	**$5**
P 0904 3 Pin Chassis Female	$8.75	**$6**
P 0906 3 Pin Chassis Male	$6.50	**$4**

Save 25% on ALCATEL connectors!


19" Rack Cases **Save 10%**

Available with Raw Aluminium, Natural or Black Anodised

Each finish is available in 1U (44mm), 2U (88mm) or 3U (132mm) high. Overall depth 255mm. Mounting hole centres conform exactly to international racking specifications both vertically and horizontally.

Features: • Raw aluminium, black or natural anodised finish • Aluminium construction with removable top and bottom steel cover panels • All dimensions conform to the International Standard • Ventilated lid • Deluxe finish front panel • Individually packaged • Supplied in Flat Pack Form - Easily assembled in minutes.

Cat No.	Unit Height	Height (mm)	Internal Height (mm)	Front Panel Finish	ea Normally	ea This Month
H 5011	1U	44	38	Raw Aluminium	$69	$62
H 5012	2U	88	79	Raw Aluminium	$84	$75
H 5013	3U	132	122	Raw Aluminium	$89	$80
H 5021	1U	44	38	Natural Anodised	$77	$69
H 5022	2U	88	79	Natural Anodised	$92	$82
H 5023	3U	132	122	Natural Anodised	$99	$89
H 5031	1U	44	38	Black Anodised	$79	$70
H 5032	2U	88	79	Black Anodised	$95	$85
H 5033	3U	132	122	Black Anodised	$99	$89




Save 10% on Professional Rack Cases! Ideal for building Amplifiers, Pre-Amps, Power Supplies etc.

19" Rack Shelves **Save 10%**

These ingenious rack shelves are ideal for mounting traditionally desk standing equipment into a 19" rack frame. Great for CD's, tuners, amps etc is a breeze with these handy rack shelves. Industrial strength black powder coat finish, includes special rear support to keep equipment in place.

Cat. No.		Depth	Useable Height	Normally	This Month
H 5352	2 Unit	340mm	76mm	$49.95	$44.95
H 5353	3 Unit	340mm	120mm	$54.95	$49.45
H 5363	3 Unit	400mm	120mm	$64.95	$58.45
H 5354	4 Unit	340mm	164mm	$59.95	$53.95
H 5364	4 Unit	400mm	164mm	$69.95	$62.95



Now available - extra deep shelves for multi-play carousel CD players etc.

Professional Series Speaker Grills

Add some class to your speaker cabinets with this professional series of mesh grills. Sturdy steel construction features plastic surround and open grid appearance. Each includes 4 fixing clamps.

C 3706 6.5" (165mm) Was $8.95 **Now $6.70**

C 3708 8" (200mm) Was $10.95 **Now $8.20**

C 3710 10" (250mm) Was $13.95 **Now $10.40**

C 3712 12" (300mm) Was $16.95 **Now $12.70**

C 3715 15" (380mm) Was $19.95 **Now $14.95**



SAVE 25%! Great for DJ speakers, subwoofer enclosures or nightclub boxes.

Micron Series III Soldering Station

The *MICRON* Series 3 soldering station employs electronic switch mode circuitry in lieu of a mains transformer. Excellent for all general purpose and production soldering.

Features: • High insulation ceramic heating element • Rapid heat-up and instant recovery • Heater insulation of over 100MΩ • A zero voltage circuit ensures no high voltage spikes or magnetic field are present at the tip to damage sensitive components • Continuous temperature adjustable from 250° to 430°C (480° to 800°F) • Grounded power cord • Selecting the desired operating temperature is as simple as turning a knob.

Now Supplied with Long-Lasting Iron Clad Tip!

T 2443 Normally $129

This Month $99



Amazing Special!
A Professional Soldering Station for Under $100. Why Pay $160 or More?

ALTRONICS Fax Order Line (09) 328 3487

1-800 999 007 **PERTH (09) 328 1599**

ALTRONICS COMPONENTS

ALTRONICS Fax Order Line: (09) 328 3487

Micron Sure Shot Desoldering Tool



Exclusive to Altronics in Australia. This stand alone, fully self-contained desoldering tool makes it a breeze to remove components from any PCB. Even double sided, through hole plated boards. All it needs is a squeeze or two on the trigger and the component virtually falls out. **Features:** • Totally self contained • Light and compact • Anti static tip • Easy to use • Simple to clean and maintain • Variable tip temperature. The ***Sure Shot*** generates a high speed vacuum every time the trigger is squeezed. This vacuum causes the molten solder to flow into the collection reservoir contained within the unit. Here the molten solder solidifies into small particles. With its inbuilt variable temperature control the ***Sure Shot*** is ideal for single sided, double sided and through hole plated P.C.B.'s. With just a couple of squeezes of the trigger all holes are left solder-free for easy removal of the component.


T 1280 **$279**

T 1282 1.0mm Replacement Tip to Suit **$34.95**
T 1283 1.6mm Replacement Tip to Suit **$34.95**

Now over 1000 units in service Australia wide!

De-Solders a 14 Pin IC Socket in Around 30 Secs!

BONUS THIS MONTH
Receive a Free T 1274 Bench Stand Valued at $24.95 with every T 1280!



Piezo Alarm



An ear piercing pulsating tone for use in house alarms, car alarms or warning systems. 100mm fly lead length.
SPL Output: 100dB @ 1m
Supply Voltage: 1 - 13V DC
Dimensions: 45Ø x 27H
S 6117 Was $5.25
Now **$4**

Ear piercing piezo for use in alarm panels, reversing buzzers, warning systems etc.

Weatherproof Horn



8 Ohm. 10 watt. For use in house alarms, CB PA/extension speaker, boats etc. White PVC construction with swivel mounting bracket.
C 2015 Was $15.95
Now **$10**


Flush Mount Circuit Breakers



These circuit breakers push fit into a panel and protrude only 5mm from the mounting plane. Push-to-reset action with coloured button and current rating on bezel for easy identification.
Hold Current: 100% indefinitely at 25°C
Trip Current: Within 1 hr at 135% of rated load at 25°C
Within 1 minute at 200% of rated load at 25°C
Maximum Voltage: 250V AC or 32V DC
Dimensions: 52L x 13.5H x 15.5W
S 5553 3 Amp
S 5555 5 Amp
S 5557 7 Amp
S 5560 10 Amp
S 5565 15 Amp
All **$6.95** ea

Ideal for Amplifiers Power Supplies etc. Instantly Resets at the Push of a Button

PCB Terminal Blocks



These terminals are slightly imperfect and in some cases they will not readily dovetail together as the grooves are slightly burred. However, if the burr is removed with some side cutters, they join together perfectly. 5mm Pin Pitch with wire protect terminals. Rated at 15A at 300V AC

P 2034 2 way **40¢** 1-9, **30¢** 10-99, **20¢** 100up
P 2035 3 way **60¢** 1-9, **45¢** 10-99, **30¢** 100up
(Note: Not available from resellers)


Thermalloy TO-3 Heatsink



More than 50% off! Stock up NOW!

Includes threaded studs to secure transistors. Thermal resistance 7°C/W. Ideal for all those projects with TO-3 transistors such as power supplies, small audio amps, power switching circuits etc.
H 0503 Normally $1.20
This Month **.50¢ ea**

True RMS Digital Multimeter



Supplied with high quality hard carry case and silicon test leads. This 3.75 digit 4000 count digital multimeter would have to be best meter we have ever evaluated. Features include menu driven functions (no complicated instructions to remember), large backlit display, timer function, 20 amp current scale and many more.

Highly Recommended for Scientific Research & Development Work

Other Features: • RS-232 Mode (Q 1098 only) for interface to PC computer • True RMS mode • Large display includes main and sub displays with bargraph • 10 Location memory • Stop watch/pre-settable count down timer • Minimum, maximum, average and relative modes • Decibel measurement • Capacitance and inductance measurement • Temperature mode (°C and °F) • Pulse signal generator for logic and audible testing etc • Continuity and diode test • Logic test • Auto power "off" and "keep on" mode • 20A current range • Warning buzzer sounds when leads are incorrectly inserted in the 20A current mode • Back lit display • Data hold and run mode • Low battery indication • Overload protection • Safety design in compliance with UL 1244 and VDE0411


BONUS THIS MONTH
Receive a FREE Q 1093 carry holster and Q 1092 temperature probe adaptor valued at $35.50!

Specifications & Ranges Available:

DC Volt:	400mV, 4V, 40V, 400V, 1000V
AC Volt:	4V, 40V, 400V, 750V
DC Current:	400µA, 400mA, 20A
AC Current:	400µA, 400mA, 20A
Frequency:	10kHz, 100kHz, 1MHz, 10MHz
Resistance:	400Ω, 4kΩ, 40kΩ, 400kΩ, 4MΩ, 40MΩ
Capacitance:	100µF
Inductance:	100H
Temperature:	-17° - 1093° C (0° - 2000° F)
Display:	3.75 digit, 4000 count LCD

Q 1091 Standard Model **$239**
Q 1098 RS-232 Interface Model **$289**


Heavy Duty Speaker Stand



Adjustable height from 1 to 2 metres. Sturdy aluminium tube construction with steel anti-sway bars and heavy duty plastic fittings. Folds down for easy transportation and storage. Comes with tee piece for mounting to speaker boxes, or will fit a 'top-hat' adaptor. Ideal for raising speakers and lighting to audience level. Great for DJ's, bands, clubs etc.
C 0520 Was $140
This Month **$99**

30%Off! Only 50 units available at this incredible price!

Weather Proof Sound Monitors



Ideal for Hi-Fi extension, surround sound or outdoor use.
Features: • Rugged moulded Luran-S plastic construction • Engineer designed in Australia • Excellent reproduction • Superior to imports - yet a fraction of the price • Comes complete with Wacki bracket swivel mount • 2-way speaker system design with computer engineered crossover and ported bass reflex enclosure • 100mm bass driver with polymide ferrofluid dome tweeter • High efficiency design, 90dB 1W / 1m • Built in polyswitch overload protection
8 ohm 30 Watt
C 0904 White **C 0905** Black
Normally $249 per pair **This Month** **$199** per pair

Save a MASSIVE $50!

"They compare favourably with imported U.S. and European made speakers costing twice as much." John Negus, Audio Equip.

High Power High Performance 4" Speaker Bargain



This high quality and high power mid/bass driver is ideal for car sound, extension speakers etc. Amazing bass response for such a small driver when used in suitable enclosure.
Impedance: 8 ohm
Maximum power: 20W
Resonant Freq.: 80Hz
Freq. Response: 80Hz - 13kHz
Sensitivity: 94dB (1W @ 1m)
C 0629 Normally $26.95 Each
This Month Buy Two For **$26.95**

HURRY! Stocks are strictly limited!

Amazing 2 for 1 Offer! Save 50%!

MU65 Panel Meters



Overall dimensions 100W x 82H. Bolt mounting centres 80W x 64H. 63mm hole required, nuts and washers included.

Over 50% Off! Ideal for power supplies and test gear!

Q 0540 1mA
Q 0550 100µA
Both Models **$10 ea**
Were $24.95 ea

PECC Speaker Bargain



This punchy, powerful bass driver features Poly Emulsion Coated Cone (PECC) and large barium ferrite magnet to form a package which has quite remarkable performance and extremely low distortion. Call ALTRONICS for full specifications.
Max Input Power .....60 Watts
Freq Response.....50Hz - 5kHz
C 3022 6.5" PECC Woofer Normally $49.95
This Month Only **$38**

Update those old hi-fi boxes, or build your own speakers!

1-800 999 007 **PERTH (09) 328 1599**

Doc.JH469

OVERNIGHT DELIVERY

Up to 50% Off Professional Series Instrument Cases. That's Less than Normal Wholesale Prices!!

As a result of a massive scoop purchase, Altronics can now offer these fantastic cases to you at rock bottom prices!

Lightweight and Compact

As used in many EA and SC kit projects and by many major manufactures Australia wide, these instrument cases are moulded from ABS plastic and feature internal mounting posts, PCB guide rails and ventilation slots. Attractive textured finish, with removable black front and rear panels. They offer many advantages over folded sheet metal cabinets, namely: • Very easy to drill and machine • Requires no painting • The front and rear panels can be direct machine engraved or silk screened • There are no dimensional variations from one cabinet to the next - ie. they are the same every time • They are very cost effective and look good



Small Size

Dimensions - 200W x 155D x 65H mm
H 0480 Light Grey Case
H 0481 Black Case
Normally $15.00 ea,
This Month $9, or 4 & up $7.50 ea

Large Size

Dimensions - 250W x 190D x 80H mm
H 0482 Light Grey Case
H 0483 Black Case
Normally $20.00 ea
This Month $12, or 4 & up $9.50 ea

Give Your Project a Professional Finish! At These Prices, Why Not Stock Up for Future Projects??

Super Compact Car Alarm

Exclusive to Altronics



Super compact in size, this alarm features shock sensor (with adjustable sensitivity), voltage drop sensing (can be disabled) and negative trigger input (for door, boot and bonnet etc). Wireless remote control with arm/disarm and panic functions. Will flash car indicators or park lights when arming and disarming. All the electronics and piezo siren are housed inside one neat enclosure measuring only 100L x 75W x 45H mm, making it ideal for cars and motorbikes. Supplied complete with a flashing dash mounted LED and wiring harness.

Features: • Remote controlled (≈15m range) • 110dB piezo siren built into controller • Very compact size • Voltage drop sensing circuit (selectable) • Audible arming / disarming with trigger indicator • Built in adjustable shock sensor • Remote panic • Negative trigger input • Triggered memory • 30 second reset and rearm after triggering • 25 second arming delay • 10mA current draw in armed mode

Protect your car from theft. Install one of these alarms & save hundreds $$$ on comparable systems!

S 5210 Alarm Only **$99**

S 5211 Additional Remote Control **$16.95**

KSN 1141A Horn Tweeter



The powerline series of Motorola horn speakers incorporates protection circuitry which allows them to be used safely with amplifiers rated as high as 400 watts. Great for use in DJ speaker boxes, PA bins, guitar or keyboard speaker bins etc.

Frequency Response .....1.8KHz - 40KHz
Average Sensitivity .....92dB @ 1m/2.83V
Max Power Capacity.....400W
Max Temperature.....80°C
Horn Size.....177mm x 83mm

Motorola horns for DJ and PA Audio Systems!

C 6150 Was $45 Now $37

These Motorola Horns Are Covered by a One Year Burn Out Guarantee

Stony Broke Speaker Kit by *REDBACK*

Amazing response and definition!

As featured in SC Magazine June '94.

This speaker kit is a bit like the Volkswagon; not too pretty to look at but performs superbly. Well that's the same as the Stony Broke speakers; pretty ugly but sounds sensational. Frankly, the reproduction from these speakers must be heard to be believed. Ideal for bookshelf speakers, extension speakers or speakers for personal walkman type systems. Comes supplied in kit form. The kit for each speaker consists of two large jiffy boxes, one C 0629 30 Watt driver, one C 3010 tweeter, crossover, innerbond wadding, port tube, spring loaded terminals, 6 metres of cable, all fixing screws etc. In fact all you will need is a tube of silicon or similar to seal the 2 boxes together. The main speaker holes have been machined, all you will have to do is drill the mounting holes for the speakers. No special tools are required. Basically all you will need is a screwdriver, soldering iron, drill with 3mm drill bit, cutters etc. Even though these are a low cost kit, there has been a considerable amount of engineering to achieve the resultant sound! The main speaker driver complimented with the tuned enclosure exhibits quite amazing bottom end for a speaker for this size.



"These have no right to sound as good as they do!" Leo Simpson, Silicon Chip Magazine.

C 3200 Only $99 per pair

KSN1188A / KSN1196A Tweeter

A horn tweeter for serious speaker enclosures. Horn measures a massive 380 x 130mm with a screw-on driver. Can be used in DJ boxes, band PA enclosures, or other applications where LOUD top end is required.

Frequency Response ....800Hz - 20KHz
Average Sensitivity .....93dB @ 1m/2.83V
Max Power Capacity....100W
Horn Size.....380mm x 130mm



C 6158 Normally $165,
This Month **$150**

ALTRONICS

174 Roe St. Perth W.A. 6000
Phone (09) 328 1599, **Fax** (09) 328 3487
MAIL ORDERS C/- P.O. Box 8350
Perth Business Centre, W.A. 6849

We welcome ... bankcard MasterCard VISA

Standard Delivery & Packing Charge: $4.00 to 500gms, $5.50 500gms-1 kg, $8.00 1kg-5kg. Where possible we process your order the day received and despatch via Australia Post. Allow approx 9 days from day you post order to when you receive goods.

Overnight Jetservice: Up to 3kg is $9.50, 3kg to 5kg is $18.00—We will process your order the day received (if placed before 2.00PM WST) and despatched for delivery the next day. Country areas please allow an additional 24-48 hours.

Heavy Service: All orders of 10kgs or more must travel Express Road—Please allow up to 7 days for delivery. $12.00 to 10kgs. $15.00 over 10kgs. **Insurance:** As with virtually every other Australian supplier, we send goods at consignee's risk. Should you require insurance cover against loss or damage please add $1.00 per $100 of order value (minimum charge $1). When phone ordering please request "Insurance". **Altronics Resellers:** Chances are there is an Altronics Reseller right near you—check this list or phone us for details of the nearest dealer. Blue Ribbon Dealers are highlighted with a ●. These dealers generally carry a comprehensive range of Altronic products and kits or will order any required item for you.

WA - COUNTRY

ALBANY	BP Electronics ●	(098) 412681
	Micro Electronics	(098) 412077
BUNBURY	Micro Electronics	(097) 216222
BUSSELTON	Mark's Music	(097) 523522
ESPERANCE	Esperance Comm.	(090) 713344
KALGOORLIE	Golden Mile Electronics	(090) 215212
ROCKINGHAM	TV Joe's	(09) 5271806

VIC - CITY

	All Electronic Comp.	(03) 96623506
	TECS ●	(03) 96706474
CHELTENHAM	Talking Electronics	(03) 95842386
CLAYTON	TECS ●	(03) 95629501
CROYDON	Truscott Electronics ●	(03) 97233860
FOOTSCRAY	G.B. Telespares	(03) 93266035
PRESTON	Preston Electronics ●	(03) 94840191

COUNTRY

BALLARAT	Ballarat Electronics	(053) 311947
BENDIGO	Sumner Electronics	(054) 431977
MILDURA	Truscott Electronics ●	(050) 238138
SHEPPARTON	Andrew Guyatt Elect.	(058) 219497

QLD - CITY

	Delsound PL●	(07) 38396155
NEWSTEAD	E.C.Q.	(07) 32541153
WEST END	B.A.S. Audiotronics	(07) 38447566
WOODRIDGE	David Hall Elect.●	(07) 38082777

COUNTRY

GLADSTONE	Gladstone Elect. Services	(079) 724459
MAROOCHYDORE	Mals Electronics ●	(074) 436119
TOWNSVILLE	Super Solex ●	(077) 724466

TAS

HOBART	G.H.E. Electronics ●	(002) 342233
LAUNCESTON	G.H.E. Electronics ●	(003) 316533

NT

ALICE SPRINGS	Farmer Electronics	(089) 522388
KATHERINE	Logicware	(089) 723030

SA - CITY

	Aztronics ●	(08) 2126212
	Force Electronics ●	(08) 2125505
BRIGHTON	Force Electronics ●	(08) 3770512
COL. LIGHT GDNS	Force Electronics ●	(08) 3743346
ENFIELD	Aztronics ●	(08) 3496340
FINDON	Force Electronics ●	(08) 3471188
HOLDEN HILL	Force Electronics ●	(08) 2617088
KENSINGTON PK	Force Electronics ●	(08) 3322299
LONSDALE	Force Electronics ●	(08) 3260901
SALISBURY	Force Electronics ●	(08) 2830755

NSW - CITY

	David Reid Elect. ●	(02) 2671385
SMITHFIELD	Chantronics	(02) 6097218

COUNTRY

COFFS HARBOUR	Coffs Habour Elect.	(066) 525684
NEWCASTLE	Novocastrian Elect.Supplies	(049) 621358
WARNERS BAY	Vilec Distributors	(049) 566792
WOLLONGONG	Newtek Electronics ●	(042) 271620
	Vimcom Electronics	(042) 284400

ALTRONICS Fax Order Line: (09) 328 3487

1-800 999 007 PERTH (09) 328 1599

Doc.JH469

ANU's Siding Spring Observatory is now

CAPTURING THE WARM GLOW OF HEAVENLY BODIES

The Australian National University's 2.3-metre Advanced technology Telescope at Siding Spring is now able to capture detailed infra-red images of the heavens, thanks to a cryogenically cooled imaging sensor known as CASPIR. Designed and built by Mount Stromlo astronomer Peter McGregor, CASPIR looks set to keep Australian scientists at the forefront of IR astronomy.

by GEOFF McNAMARA

In the film *Silence of the Lambs*, the climax is played out in the dark cellars of the villain's home. Deprived of light, the heroine struggles to find any trace of her opponent; while he, equipped with infrared goggles, navigates easily in the tense gloom.

In a similar way, astronomers often find their cosmic prey invisible in ordinary light. Often the objects they want to study are buried deep within clouds of dust that light just cannot penetrate. Infrared radiation, on the other hand, can penetrate the gloom, allowing astronomers to peer deep into the heart of phenomena ranging from newly born stars to the core of our Galaxy.

But while artificial optical detectors — at first film and later photoelectric devices — have been around for over a hundred years, infrared detectors have only been used for astronomical purposes for little more than a decade. In that time, however, they have been employed in some spectacularly successful instruments.

One such infrared camera is called CASPIR — the Cryogenic Array Spectrometer/Imager. Designed and built by Peter McGregor, an astronomer at Mount Stromlo Observatory near Canberra, CASPIR has been setting the pace for infrared astronomy in Australia since 1993.

CASPIR has been designed for use with the Australian National University's 2.3-metre Advanced Technology Telescope, atop Siding Spring Mountain in northern New South Wales. You may have seen some of CASPIR's images when comet Shoemaker-Levy 9 ploughed into Jupiter in July 1994 — they were the ones where Jupiter seemed to glow from the inside.



The dome of the Australian National University's 2.3m New Technology Telescope, at the Siding Spring Observatory in northern NSW. (Photo by Brenda McNamara)

But CASPIR is used for more than taking sophisticated snapshots of rare events. Not only can CASPIR look deep into Jupiter's atmosphere; it's giving astronomers a detailed view of the very heart of the Milky Way Galaxy and is helping to answer the question of what lies there.

The need for astronomical infrared detectors arises because the Galaxy is a dusty place. Visible light simply scatters off the dust, the way a car's headlights simply illuminate fog, rather than allow you to see through it.

But while infrared light can penetrate interstellar dust, it has a hard time making it through the Earth's atmosphere where carbon dioxide and water vapour make the sky almost opaque to infrared radiation. This forced astronomers to launch infrared cameras into Earth orbit. Examples are the highly successful Infrared Astronomical Satellite (IRAS) which spent 10 months in 1983 surveying the sky in the 10 to 100fm (femtometre) bandwidth, and its successor, the recently launched Infrared Space Observatory (ISO).

But telescopes like these are rare and expensive. As a result, the time available to individual astronomers is correspondingly short, and difficult to secure at best. ISO, for example, was oversubscribed by 50% long before it was even ready for flight.

Despite the infrared opacity of Earth's atmosphere, there are three 'windows' in the near-infrared spectrum, which extends from 0.8 to 8fm. These windows allow ground-based telescopes to peer through the sky into the infrared universe.

Although multipixel infrared detector technology has been used by the military for some time, it has only been used

for astronomical purposes since the mid 1980s. Up until then, infrared 'cameras' consisted of a single detector. To build up an picture of an object under study, the astronomer had to point the telescope equipped with the detector at one point after the other, slowly building up an image one pixel at a time.

The advent of charge-coupled devices that use silicon wafers meant that multi-pixel optical images could be created just as photographic film uses the photo-chemical effect to record whole scenes. The advantage of CCDs over film is that the images can be stored electronically for later manipulation. When it came to infrared imaging, however, the system doesn't work — for the simple reason that silicon is transparent to radiation beyond a wavelength of about 1fm. Infrared photons just fly right on through, without triggering any electrons.


Doped detectors

To get around this problem, detectors can be 'doped' with impurities such as indium, gallium or copper. An alternative is to create an infrared-opaque layer from either indium antimonide or mercury-cadmium-telluride, to stop the infrared photons.

The first widely used detector like this was produced by the Santa Barbara Research Center in California, and consisted of a 58x62 pixel indium-antimonide array. Later, NASA funded Rockwell Science Center to produce near infrared arrays for the Hubble Space Telescope. The latest detectors have arrays of 256x256 pixels; most major observatories are now installing these devices as part of their suite of instruments. While these detectors are rivalling optical detectors, there are plans to develop 1024x1024 pixel detectors over the next few years.

The detector used in CASPIR was manufactured by the Santa Barbara Research Center and uses an indium-antimonide layer bonded to a silicon wafer. At each pixel storage site 'bumps' of indium metal connect the two layers. This hybrid device, which makes use of the now well-developed silicon solid-state technology, detects infrared photons on the surface but stores the charge in the silicon multiplexer underneath.

The minimum speed at which the detector operates is about 100 milliseconds per exposure, which means the camera produces 10 frames every second. To keep up with such a high production rate, the system uses fast analog-to-digital converters (ADCs) and a transputer based co-adder to combine multiple short exposures into a single image.



A closeup view of CASPIR, a cryogenically cooled infra-red spectrometer/imager, when attached to the 2.3m telescope at Siding Spring. A helium refrigerator cools it down to 32K. (Photo courtesy Peter McGregor, Mt Stromlo and Siding Spring Observatories)

To keep CASPIR working as efficiently as possible, it has to be kept cold — *very* cold. Because infrared is basically heat radiation, anything at room temperature glows brightly to CASPIR's sensitive eyes. If the camera itself weren't cooled, it would have as much success detecting faint infrared sources as you would trying to read this article while your eyes glowed like a car's headlights. A closed cycle helium refrigerator is used to cool CASPIR to -241°C, or just 32° above absolute zero.

One of CASPIR's primary tasks is to provide images of celestial objects in the near infrared. Such objects can include the planets, the centre of our Galaxy, supernovae in external galaxies — even counting faint galaxies with the aim of determining the geometry of the Universe. Already it has provided some spectacular infrared images that not only rival those obtainable at optical wavelengths, but revealing features that optical detectors just can't see.


But CASPIR does more than just produce images of the sky. By using a clever system of lenses and prisms, CASPIR is able to manipulate the incoming infrared light in a number of ways. For a start there's spectroscopy

CASPIR: Capturing the warm glow...

— dispersing the spectrum into its component wavelengths.

Dispersion in CASPIR is achieved using devices called 'grisms', a cross between a prism and a diffraction grating. The advantage of using a grism is that while the grating disperses the light into a spectrum, the prism characteristic deviates the beam so that it remains more or less parallel to the optical axis of the instrument.

Three grisms are available in CASPIR, in the three infrared windows.



Infra-red images of Saturn taken by CASPIR in August 1995, when the Earth passed through the plane of its rings. Images like these allowed the exact crossing time to be determined. (Photo courtesy Peter McGregor, Mt Stromlo & Siding Springs Observatories)

For each of these, a second grism at right angles to the first further enhances the spectra produced.

CASPIR also permits imaging polarimetry, essentially measuring the percentage and direction of polarisation of incoming light. This is done using a device known as a 'half-wave plate' that can be rotated in the infrared beam before it enters CASPIR. This polarises the beam in a known way. A prism then produces two images of the object with perpendicular planes of polarisation. By rotating the half-wave plate at intervals of 22.5°, the images produced can be combined in such a way that the degree and direction of polarisation can be determined.

Measuring or imaging faint objects near bright ones calls for a feature called a coronograph. Essentially, a coronograph is a baffle that covers the brighter object, allowing the fainter one to be seen more clearly.

To keep the coronograph properly positioned over the brighter object, CASPIR has to rotate on the back of the telescope. The reason is that as objects move across the sky they slowly rotate with respect to the horizon. But because the 2.3-metre telescope that CASPIR is attached to rides on an alt-azimuth mounting — moving up and down and in azimuth — it stays in the same orientation as the horizon. The 'bottom edge' of the telescope remains parallel with the horizon all night long. If CASPIR didn't rotate, the brighter object would peek out from behind the coronograph baffle and spoil the image.

The lenses used in CASPIR had to be specially made. Ordinary glasses, while transparent at visible wavelengths, become opaque in the infrared. The lenses used in CASPIR are made from CaF_2 (calcium fluoride), BaF_2 (barium fluoride), MgO (magnesium oxide) and sapphire crystals. They were ground in the optical workshop at Mt Stromlo Observatory, and given an anti-reflection coating of MgF_2 (magnesium fluoride) at the CSIRO's National Measurement Laboratory. This gives CASPIR a peak throughput of about 80%, while the overall efficiency (photons in to electrons out) is about 30%.

One of the neat things about CASPIR is that it's a fully self-contained, yet extremely versatile instrument. The collection of lenses, filters, grisms, and baffles is cleverly arranged on a series of wheels that rotate around a common shaft. Depending on which mode CASPIR is to work in, the wheels rotate to swing the desired optical components into the ray path.

What can it do?

Now that CASPIR is operational, what can it do? The answer is: anything that needs infrared imaging! "What I do is generically infrared astronomy", McGregor said. "I built this camera — put in the investment of time — so I'm involved in everything that it can do!"

One of the most recent applications for CASPIR was when the Earth passed through the plane of Saturn's rings. McGregor used CASPIR to watch the planet leading up to the crossing, with the aim of determining the exact time of the crossing. This information tells astronomers a lot about how Saturn 'precesses', or wobbles in space. This in turn tells them about the physical make-up of Saturn.

"We were viewing the dark side of the rings. In the near infrared the planet is also dark, because methane gas (in Saturn's atmosphere) absorbs the reflected sunlight," McGregor explained.

With the brightness of the planet suppressed, the rings were easier to monitor. As it turned out, the observations were quite successful: McGregor and other astronomers around the world were able to pinpoint the time of the ring plane crossing.The different appearance of planets like Saturn in the near infrared prompted McGregor to contribute to the barrage of images of Jupiter in July 1994, when the ill-fated comet Shoemaker-Levy 9 ploughed into the planet. You may recall seeing some eerie images in which the giant planet seemed to glow from within.

Long before anything was visible in the optical spectrum at the time of the collisions, CASPIR was being saturated by the brightness of the impacts. As the impact sites cooled, the near-infrared brightness decreased rapidly; but CASPIR continued to detect the emerging stratospheric clouds kicked up by the impacts, which reflected sunlight more efficiently than the surrounding methane clouds.

Yet McGregor has his own astrophysical interests, within the range of infrared studies. "Most of what I do concerns the

centre of our Galaxy", explained McGregor. One of the most popular ideas for what exists in the centre of the Galaxy is a supermassive black hole, weighing in at perhaps two million times the mass of the Sun.

"The only way you can tell if there's a black hole at the centre of our Galaxy is to look at the motions of the stars there," McGregor continued. The gravity of a massive object in the centre of the Galaxy would cause the stars to move differently than if there were nothing there. "You can't see the centre of the Galaxy in the optical — but you can in the near infrared!"

McGregor is working with theorists at Mt Stromlo Observatory to try and answer the question of a black hole at the Galactic centre. They've concluded that there is no single massive object there, however there is evidence to suggest that there may be a large number of smaller black holes, possibly on the order of ten solar masses each.

A second project McGregor has going is looking into clouds of gas and dust found near the Galaxy's centre. About ten million years ago the centre of the Galaxy underwent a period of starburst — a time of rapid star formation during which several massive stars were born. But massive stars don't live as long as lower mass stars, and McGregor wonders if these glowing clouds of gas and dust are related to the evolution of the massive stars. The objects are glowing at a temperature of about 500K, as if something were warming them from the inside.

"There's something buried down there powering these things, that we can't see," said McGregor. "When lower mass stars grow old they tend to blow off an envelope of gas and dust — sort of like soot — and that buries the star so you can't see it optically. If that same process is occurring in these very massive stars, then that would account for these dust-obscured objects."

With such a wide range of applications, from imaging Jupiter to helping understand the age and evolution of the Universe, CASPIR has a major role to play in astronomy. It has greatly enhanced the capabilities of the 2.3-metre ANU telescope.


CASPIR is now providing views of the Universe which rival the results achieved in visible light. McGregor is understandably proud of his achievement: "With CASPIR, Australian astronomers are well placed to continue making a significant impact in world astronomy."

(Geoff McNamara is a freelance astronomy writer and Associate Editor for *Sky & Space* magazine.) ❖

A Truly Integrated Digital Storage Scope To 100MHz and Digital Multimeter...

ScopeMeter® Series II

FLUKE



Fluke ScopeMeter is a battery powered, combination scope and meter designed for measurements on-the-go. Just push the MEASURE MENU button, select one of 30 measurements and ScopeMeter configures itself to take the desired reading. Good waveforms are automatic.

While probing from test point to test point, the CONTINUOUS AUTOSET feature instantly adjusts the timebase and amplitude. Manual controls are still there, but Series II is so fast and easy, why use anything else?

Designed with a sealed, ruggedized case, the Fluke ScopeMeter Series II performs reliably even in wet, dusty, or dirty environments. And the backlit screen makes for easy readings in bright light and no-light locations.

Fluke offers five versatile ScopeMeter models.

Discover how the most popular, portable combination scope and meter can make your job faster and easier.

FEATURES	91	92	96	99	105
MHz Bandwidth	50	50	50	50	100
Number of Channels	1	2	2	2	2
Continuous Autoset	✔	✔	✔	✔	✔
Measure Menu Automatic Setups	✔	✔	✔	✔	✔
Min Max TrendPlot™ - Long Term Recording	✔	✔	✔	✔	✔
Multimeter Display with Full Width Waveform	✔	✔	✔	✔	✔
True RMS Volts	✔	✔	✔	✔	✔
Continuity Beeper	✔	✔	✔	✔	✔
Time/Division (10 ns/div to 60 sec/div)	✔	✔	✔	✔	✔
(5 ns/div to 60 sec/div)					✔
Volts/Division (1 mV/div to 100V/div)	✔	✔	✔	✔	✔
Digital Trigger Delay (Cycles, Events, Time & Zoom)	✔	✔	✔	✔	✔
Special Multimeter Modes (RPM, Temp & More)	✔	✔	✔	✔	✔
Scope Input Current Clamp Scaling - Read Amps	✔	✔	✔	✔	✔
Oscilloscope Cursor Readings			✔	✔	✔
Glitch Capture - 40 ns	✔	✔	✔	✔	✔
Screen Memory			5	10	10
Waveform Memory			10	20	20
Set-up Memory			20	40	40
Waveform Math & Filter				✔	✔
Signal Generator Output - 4 Fixed Frequencies				✔	✔
Component Tester Output - Volts & Current				✔	✔
Optically Isolated RS-232-C Interface			✔	✔	✔*
Printer Output			✔	✔	✔
Wave/Screen Transfers & Remote Operation	scrn to PC	scrn to PC	scrn to PC	✔	✔*
Backlit Display	✔	✔	✔	✔	✔
On Line Information & Help Function	✔	✔	✔	✔	✔

*Interface cable and FlukeView™ software included

Many other DMMs available. We stock a full range of accessories, probes, test leads, holsters etc. – call us with your requirements.

Ask for NEW 1996 Catalogue. Available FREE!


OBIAT PTY LTD

129 Queen Street, Beaconsfield.
P.O.Box 37 Beaconsfield NSW 2014
Tel : (02) 698 4111 Fax : (02) 699 9170
Call for the name of your local stockist

bankcard VISA MasterCard

READER INFO NO. 10

AUTOMOTIVE ELECTRONICS



with JON LOUGHRON Assoc. Dip. Electronics

Bosch EST in the VK Commodore and XF Falcon

This month I am going to discuss the Electronic Spark Timing (EST) system found on some VK Commodores and XF Falcons. The system on both vehicles is made by Bosch and is a derivative of similar systems found on earlier European vehicles (EZK).

As indicated by the name of the system, control of the advance and retard of the ignition system is achieved by electronics, not mechanical advance weights and the associated vacuum unit on the distributor. Control of the system is implemented by the use of a microprocessor controlled ECM (electronic control module) and associated peripheral input/output hardware.

Fig.1 shows the system block diagram. The main input, apart from power supply rails, is the input trigger. It is obvious that the ECM must know the crankshaft position and speed to be able to calculate and provide sparks at the correct instants, so it is very important to ensure that the trigger is functioning correctly.

The GMH and Ford systems use different triggers and these will be discussed in detail later. It also should be noted that even though the 25-pin connectors on the ECM's are the same, the actual pinouts are different and as a result they cannot be interchanged.

The ECM must also know what load the engine is under, and manifold vacuum is translated into a voltage by the manifold absolute pressure (MAP) sensor. Engine temperature is also taken into consideration via the coolant temperature sensor (CTS) and engine mode — i.e., idle — when calculating the final timing offset.

The negative side of the coil is switched by a large internal power stage, and this is mounted onto the ECM metal case to provide good heat dissipation. The primary winding of the gnition coil measures less than 1 ohm and it has a 12 volt supply (even higher when the alternator is charging the system), so you can see that a good heat sink is necessary.

While we are discussing the power switching of the electronic system, it provides a good time to discuss briefly why automotive manufacturers decided to pursue electronic ignition over the old points or Kettering method.

Points vs electronics

If you measure the resistance of a points system ignition coil primary winding, you will notice that the resistance is much higher (some coils are up to 4Ω). The reason for this is quite simple: the points in most ignition systems cannot sustain much more than 3-4 amps consistently without burning out. In addition, during normal operation the points become pitted and corroded, due to arcing, and this requires continual maintenance ('cleaning the points') to prevent degrading the system's performance.

On earlier ignition systems this became a problem, because as engine technology advanced and higher revving, multi-cylinder engines developed, the available time to charge the coil at higher RPM became very short. Increase the primary current, I hear you suggest — well, it can be done, but not without reducing the service life of the points to an unacceptable extent.

To overcome this problem, the number of turns on the coil primary winding was reduced, with the inclusion of ballast resistor to keep the primary system resistance to approximately 3-4 ohms. Because of the ballast resistor the primary current was not increased substantially, but the reduction in primary winding turns reduces the coil's primary inductance, so its opposition to the incoming current is reduced and therefore the current can build up more rapidly.

This overcame some of the problems, at least for a while, but again the search for more powerful engine technology pushed the ballasted points system to its limits.

Around this time transistor technology was beginning to take a firm grip on the power electronics industry, and it




Fig.1: The block diagram for the EST system used in some XF Falcons and VK Commodores, showing the ECM (centre) and its associated sensors and other 'peripherals'.

PIN No.	XF DESCRIPTION	VK DESCRIPTION
1	Earth	N/C
2	Hall Sensor +10 Volt supply	Diagnostic Lamp
3	Trigger Input	Coolant Temp Sensor
4	Static Timing Input	Idle Switch
5	Coolant Temp Sensor	Trigger Input (reference)
6	Coolant Temp Sensor	Coolant Temp Sensor Earth
7	Idle Switch	N/C
8	Air Conditioning Swicth	N/C
9	Diagnostic input (STI)	N/C
10	N/C	N/C
11	Cannister Purge Solenoid	N/C
12	Earth	N/C
13	Diagnostic Earth	N/C
14	Ignition Coil (-ve side)	Earth
15	Earth reference (Hall sensor)	Ignition Coil (-ve side)
16	Diagnostic Output	+12 Volts Supply
17	Crank Signal	Air Conditioning Switch
18	Power Supply MAP Sensor	Diagnostic Enable
19	MAP Sensor Signal	Power Supply MAP sensor
20	N/C	Earth
21	Earth Reference MAP Sensor	Earth Reference MAP Sensor
22	N/C	Trigger (AC signal)
23	N/C	Crank Signal
24	N/C	MAP Sensor Signal
25	+12 Volts Supply	N/C

Fig.2: The connections to the EST ECM are quite different for the XF and VK versions, even though both use a 25-pin connector. Interchanging the two is therefore not practical.

was not unnoticed by automotive OEM designers. As a result a myriad of weird and wonderful systems emerged on the market — some destined for fame and others failure. But out of all the confusion and research, stable, reliable systems began to appear on the family wagon.

The early electronic systems still used points to trigger the electronics, and mechanical/vacuum devices to advance and retard the ignition timing — but did use a power transistor to control coil switching and dwell. The main advantage of the semiconductor output stage is the ability to switch on and off very quickly, and also the ability to switch increased current levels reliably.

As technology advanced, pulse generators such as Hall sensors (XF Falcon), inductive pickups (VK Commodore) and optical triggers (VL Commodore) emerged and replaced the points entirely. But this did not overcome the problem of mechanical and vacuum ignition timing variation.

When microprocessor technology became more approachable the automotive engineers rubbed their hands with glee — because now with microprocessors, once the basic control system was built, the ignition timing could be adjusted by a simple ROM change.

So all of that history has stated the obvious: that microprocessor based controllers have enabled designers to provide a more sophisticated, environmentally friendly, flexible and reliable ignition system. This does not mean 'inexpensive', though...

Before we go any further into the Bosch EST system, though, a word of warning regarding safety.

Beware: danger!

As mentioned earlier, the ECM switches the negative side of the coil to ground and then releases control at the correct time so that primary current collapses. Due to the coil's primary inductance this causes a substantial voltage 'kick' — in some HEI systems up to approximately 400V peak. Yes, we're still talking about the primary circuit, and it's a lot higher than just 12V.

As the ignition coil is in reality a step-up transformer, this action induces energy into the much larger number of turns in the secondary winding. Because of the winding ratio the secondary generates approximately 20kV to ionise the spark gap.

The point I'm making is that high-energy ignition (HEI) systems deserve respect on *both* the primary and secondary side, and if you have ever been connected to either circuit when it's active, you certainly understand my point. I am not sure which is more uncomfortable: the actual electrical shock from the system or the crack on the back of the noggin, as you stand up suddenly — forgetting the unfortunate proximity of the bonnet. Ouch!

System connections

The EST system connections for the VK Commodore and XF Falcon are summarised in the table of Fig.2. The inductive trigger unit for the VK system is mounted at the rear of the engine and it should be noted that it passes through the transmission housing to access the flywheel. There are three metal pins mounted on the flywheel 120° apart, so as to inform the ECM of the crankshaft speed and position. The resistance of the sensor is approximately 1000Ω and it generates a peaky AC voltage as the flywheel spins.

To ensure the inductive pickup is operating correctly, an oscilloscope

Applied Vacuum (KPa)	Output Voltage
0	4.4 - 5.3
-25	3.3 - 3.8
-50	2.0 - 2.5
-75	0.7 - 1.1

Fig.3: The output voltage from the MAP sensor used in both VK and XF versions, for different levels of manifold pressure.

should be used to inspect the output pulses (remember no trigger — no spark). The wiring to the sensor has a coaxial shield to minimise interference and reduce false triggering; so ensure that the shield wire is intact and terminated correctly.

The base timing on the VK cannot be varied, so moving the distributor is futile because the the base timing is fixed and derived from the 'pegs' on the flywheel. (If you remove the distributor cap on a VK with the EST system, you may be surprised to find only a rotor button inside.)

Apart from the wiring to the ECM plug, the trigger, advance map and canister purge control, the XF EST and the VK EST are very similar. The coolant temp sensors and map sensors have the same specifications (see Figs.3 and 4), and both employ an idle switch (for adjustment see the applicable manual), cranking input and air conditioning switch.


Temperature (deg.C)	Resistance (Ohms)
0	5.4 - 6.3 k
20	2.3 - 2.7 k
80	300 - 350
100	170 - 210

Fig.4: The resistance/temperature characteristic for the coolant temperature sensor (CTS) used in both the XF and VK versions.

The trigger on the XF Falcon is a Hall sensor, and it is mounted inside the distributor. So base timing is adjusted by moving the distributor (10° +/-1° BTDC), and can be accomplished by shorting out the two terminal static timing connector near the brake master cylinder. (But remember to remove the link when the adjustments are complete!)

The Hall sensor's power supply is supplied by pin number 2 on the XF Falcon's ECM, and ground on pin 15. The sensor provides an 'open collector to ground' output stage, which generates a 5V square wave with a 50% duty cycle.

One precaution that should be taken when replacing the a faulty Hall sensor is to ensure it is the correct version. The XF's EECIV system (see *EA* May 96) also uses a Hall trigger, which has the same mounting holes and also fits into the EST distributor. The problem is that the actual sensor is mounted on the base plate in a different position; therefore the ignition timing will be incorrect and the resulting problem difficult to diagnose. ("Everything seems to be working correctly!?") So my advice is to check the new Hall sensor carefully against the old one, before it is installed.



Code No.	Description
11	System Pass
21	Coolant Temp Sensor
22	MAP Sensor
58	TPS (Idle Switch)
68	TPS (Idle Switch)

Fig.7: The fault diagnostic codes for the XF version. Note the two codes available for the idle switch.

Code No.	ECM light	Description
-	Erratic	ECM problem
1	*	Coolant Temp Sensor
2	**	MAP Sensor / TPS
3	***	MAP Sensor / TPS

Fig.5: In the VK version, the ECM light flashes these diagnostic codes every eight seconds, if there is a fault and when the diagnostic connector is earthed (see text).

When fault finding on either system, ensure that the power supplies are correct and that peripheral device parameters are within specification. The connections and specifications for the MAP sensor and CTS sensor are listed in Figs.3 and 4. Remember that when you are disconnecting or reconnecting any ignition components, always ensure the ignition key is in the OFF position.

Fault codes

As the EST systems are microprocessor based, this means that they produce diagnostic codes to aid the technician with fault diagnosis.

The VK system has a warning lamp on the dash and when a fault occurs, the EST warning lamp illuminates. The codes are displayed by this lamp when the diagnostic connector is grounded. This connector is taped to the wiring harness, and located near the rear of the engine rocker cover. Fig.5 lists a summary of the VK codes. Unfortunately when the ignition key is turned off the codes are not stored, so intermittant faults may be hard to find.




Fig.6: The static timing connector (left) and the diagnostic connectors (right) are both located in the engine bay, near the brake master cylinder.

The XF system needs to have an external device to check the codes, such as an LED test lamp. The connections and code summary are provided in Figs.6 and 7.

As you can see, the EST systems used in the XF Falcon and VK Commodore are quite similar, but do have variations that must be understood before testing or servicing either system.

That's all for now, though. Until next time, bye! ❖

If you've got something to prove to the world... ... we'll hand it to you.

If you're one of an elite new team of experienced Electronic Design Engineers we're about to employ, the world will be your 'oyster'.

You see, at Bosch Australia, the world's very much knocking at your door.

- A growing export business based on our role as the Bosch Group's worldwide centre of competence for vehicle security systems;
- A leading supplier to Australian car makers and their export programs in fuel injection, engine management, electronic controls, ABS, starter motors and alternators;
- A commitment to lead the way globally in the search for new conquests in automotive electronics engineering in the next millennium (1996 Victorian Training Employer of the Year is proof of that!).

All from right here at Bosch Australia in Clayton (... we've come a long way from making a few spark plugs 40 years ago).

If you're successful and join our team, rest assured, we'll give you the world:

- Opportunities for managing your own projects and teams;
- Assistance for further education and training;
- Opportunity to work elsewhere in the world;
- Commitment to R&D that makes dreams reality. (World class Autotest centre, EMC lab and on-site manufacturing will also help).
- Excellent working conditions, employee benefits and $$$ packages.

So, if you're as good as you think and an experienced Project Leader looking to take on the world in Electronic Design Engineering, call us and prove it. We'll show you a world of difference.

Call Steven Bartho today on (03) 9541 3916 or 0412 116 390 to discuss these opportunities. Alternatively, send your written application showing how your experience and qualifications meet our requirements to:

Steven Bartho,
Human Resources Projects Officer,
Bosch Australia,
Box 66, Clayton South MDC,
Clayton, Victoria, 3169

Fax: (03) 9541 3961
e-mail: pergen@c031.aone.net.au

BOSCH

E X C E L L E N C E • A L W A Y S

READER INFO NO. 12

Losing your Mum lasts a lifetime...



No-one understands loneliness more than those who have lost a loved one. Even as adults, the desolation, depression and feeling of helplessness can be overwhelming. And the prospect of facing life alone can seem hard to bear.

Barnardos knows the pain of children who lose their Mum and is there for them. But we can't be there without your help.

Please donate to Barnardos' Annual Appeal

1800 061 000 Toll Free

Donations over $2 are tax deductible.

Please send your donation to: Barnardos Australia
Locked Bag 1 Million Broadway NSW 2007
Registered Charity No. CFN 13840 Phone: (02) 281 7933

ADVF596

$250 ☐ $100 ☐ $50 ☐ $150 ☐ $___ ☐

Name: _____

Address: _____

Company: _____

State: _____ P'code: _____ Tel: _____

Mastercard ☐ Visa ☐ Bankcard ☐
Amex ☐ Diners ☐

☐☐☐☐ ☐☐☐☐ ☐☐☐☐ ☐☐☐☐

Signature _____ Exp. date: _____

The Childrens Charity
Barnardos Australia

PORTABLE AMATEUR RADIO REVISITED - 3


To conclude his discussion of the practicalities of portable amateur radio operation on the HF bands, the author here gives details of a heavier-duty, but still compact antenna maching unit. Like the rest of the equipment described in these articles, the unit concerned was built for use on a recent trip to the UK, when he was researching for his book *In Marconi's Footsteps: Early Radio.*

by PETER R. JENSEN, VK2AQJ

Despite the advantages of the bridge antenna matching device as described in one of the earlier articles, it was decided to rely on a heavier duty and more flexible form of Trans-match for the UK visit. This was because of the 100 watts of power available from the Icom IC 725, which had been decided upon as the most appropriate transceiver for the operation. One of the limitations of the antenna tuner and bridge previously described is that its power handling capacity is limited to about 30W PEP for SSB or 10 watts for CW.

To avoid the weight penalty of a fully built up device, it was decided that the new antenna matcher should be constructed in England upon arrival and only the bare minimum of essential parts should taken on the aeroplane. These consisted of a commercial SWR and power meter and a roller inductor, which can be seen in the illustrations.

As it turned out, finding the appropriate capacitors proved quite difficult — annoying, as the home junk box contained exactly what was required and the components were not all that heavy either. Perhaps my XYL (wife) could have been persuaded to put them in her capacious handbag? On second thoughts, perhaps not.



The author's higher-power SPC Transmatch unit, pictured with an SWR/Power Meter on top of the case.

A number of different designs were investigated, but the most recent form of tuner given in the *ARRL Handbook* of 1984, involving a 'T' network, seemed to be the most likely to give good results. Apart from anything else, it is possible to use tuning capacitors from old valve radios in this design and avoid the 'differential' form of capacitor that is essential to the Universal Transmatch of earlier years.

Quite apart from its fundamental purpose of providing the transceiver with a load matched to its output impedance of 50Ω, the Transmatch has a secondary benefit which can be of some significance if interference to




Fig.1: Here is the schematic for the SPC Transmatch, repeated from the first article to refresh your memory. This is the arrangement used in the higher-power matching unit.

nearby television sets may be a problem. This of course is frequently the case in the average motel room.


The last thing the travelling radio amateur wants to do is create an ugly incident because of producing a breakthrough of SSB voice onto the neighbour's late night viewing. Next door, they may well want to watch the antics on *Chances*, and 'herringbone' interference accompanied by garbled voices certainly will not add to the residual charm of the soap opera.

As the *ARRL Handbook* explains, the particular advantage of the 'T' network in a transmatch is its 'bandpass filter' characteristic, which has a major impact on reducing spurious harmonics as compared with the earlier and very well known, Ultimate Transmatch. It says in the text:

The amount of attenuation is dependent upon the loaded Q (QL) of the network after the impedance has been matched. The higher the QL, the greater the attenuation... The 'SPC Transmatch' described here was developed to correct for the sometimes poor harmonic attenuation of the network in the Ultimate Transmatch. The SPC (Series-Parallel Capacitance) circuit maintains a bandpass response under load conditions of less than 25 ohms to more than 1000 ohms (from a 50 ohm transmitter). This is because a substantial amount of capacitance is always in parallel with the rotary inductor (C2B and L1). In comparison with the 'Ultimate' circuit, it can be seen that at a high load impedance, the Ultimate Transmatch will have a minimal effective output capacitance in shunt with the inductor, giving rise to a high-pass response.

The handbook goes on to point out another advantage of the SPC Transmatch, in its significantly greater frequency range as compared with the older Ultimate Transmatch. With the arrangement given in the accompanying schematic and with the component values as listed, one can expect to be able to cover the range from 1.8MHz to 30MHz for most situations and arrangements of wire, end-fed antennae. The addition of a matching balun will allow balanced feeder antennae to be matched as well.

The counterpoint to this, which may be considered a small disadvantage, is that the tuning is significantly sharper than on the Ultimate Transmatch. In practice this has not been found to be a problem, given a considerable apprenticeship tuning up valve type transmitters. Those with only the experience of dealing with solid state transmitters may have marginally more difficulty.




Another view inside the matching unit, showing the general layout.

Simple circuit


As can be seen from the schematic, and despite the apparently complex explanation of the mode of operation of the SPC Transmatch, this is a very simple tuner. The only small practical problem which must be overcome is that the capacitors must be supported above earth on insulated bases.

As is evident from the diagram, this tuner also makes use of a roller inductor. While clearly this is a less than common component these days, in the author's case, a well stocked 'junk box' and visits to the Glebe Market have resulted in the availability of a couple of rotary inductors.

Given the extent to which rotary inductors were used in earlier military radio, finding one may not prove to be an insuperable problem. While a tapped and switched form of inductor can be used, there is no doubt that the rotary inductor is the most satisfactory device. In addition, if you are feeling well heeled and there is no other source, then new rotary inductors are available from



A top view inside the high-power matching unit, showing the roller inductor in the centre and the tuning caps on either side.




The roller inductor unit before fitting into the case.

Emtronics in Sydney — together with capacitors with wide spaced plates, suitable for high voltages.

The Transmatch is put together using a commercial case and, as it turned out, represents a very compact arrangement. There is really very little space around the components and if you are not worried about the cubic volume of the finished unit, then it would be a much easier construction job if a larger case was used.

To some considerable extent what you can get away with for the case will be a function of the components that you can gather together. In the author's version of the Matcher, a reasonably compact form of roller inductor was available. After some hunting around and access to radio amateurs in England, so too was a wide spaced capacitor, courtesy of a World War 2 'Command' aircraft transmitter. This latter component is a very common item at radio amateur field days and auctions, and should be easy enough to obtain.

The double section capacitor was actually made up from a conventional three-section commercial receiver tuning capacitor from the 1950's, with the centre section completely removed. However there are double gang capacitors around with equal capacity sections and they would be even more suitable than the device used. Again, and as compared with the older Universal Transmatch and its differential capacitor, there are no problems with using a simple domestic radio tuning capacitor and as found at many a tip these days.



The modified three-gang tuning capacitor, with the centre section removed. The case must be insulated above ground.

Other matters

Given the availability of a motor car in the UK, prudently hired before departure from Australia, it was possible to rely on the automotive battery as the power supply for field operation in that country, although the engine was kept running, given the heavy drain of 20 amps demanded by the Icom transceiver.

Another essential item of equipment was a vertical antenna for 20 metres, and this was put together using aluminium sections and a secondhand fibreglass fishing rod. With a finished length of just on five metres and driven against ground, it proved very easy to load up through a short length of hook up wire and the Trans-match that had been built.

To give a good connection to the anticipated damp earth, a ground spike was made up using 12mm copper piping. The end of this spike was flattened off and soldered so as to provide a rough point, and then filed to a more suitable shape. At the top end was attached a 'T' shaped Yorkshire fitting, which comes with an internal ring of solder, to provide a handle; then a terminal was bolted on to allow a wire connection to the Trans-match.

To attach the Yorkshire fitting, all one has to do is clean up the copper tubing and then place the fitting in position and heat it on a gas flame. The solder soon flows, making a first class electrical connection.


As anticipated, during my expedition to Poldhu the damp earth made an excellent ground plane for the quarter wave antenna and Bavaria came in at a signal strength of 5 & 9. More to the point, this was also the signal report from the other end, so clearly everything was working as it should.

As became clear from the 'home-brewing' efforts in the United Kingdom, the Australian radio amateur is very much better served than the English counterpart. There are very few commercial outlets such as Jaycar, Davred or Dick Smith, although the ubiquitous Tandy (Radio Shack) is quite well represented.

Making up items of apparatus in England is not terribly easy and the name of the game is 'improvise'. However when one is desperate, it is amazing what can be pressed into service, courtesy of the local DIY (do-it-yourself) store. Tent pegs can also be pressed into service as earth spikes, for example, and bricklayer's twine is almost indispensable for erecting wire antennae.

It is pleasing to be able to report that the long distance portable operation, for which the equipment described in these articles was prepared, proved to be a complete success. No doubt this was due in large measure to careful planning before the event.

The next time that portable operations are undertaken in the United Kingdom, perhaps some form of compact directional beam antenna would be something to consider constructing. The 'Double Cross-bow' is already to the prototype stage, and will be reported upon in due course. ❖



The author's lower-power matching unit, described in the first article, actually used this simpler arrangement. Our apologies for the confusion.

YOUR SEARCH FOR THE ULTIMATE POWER SYSTEM IS FINALLY OVER... DON'T HOLD OFF ANY LONGER!!

rie ROD IRVING ELECTRONICS PTY LTD

RITRON QUAD SYSTEM
8 MEGABYTES RAM MULTIMEDIA READY

POWER COMPUTING IS AFFORDABLE NOW!



- Quad-Speed CD-ROM drive
- 8 MEG RAM
- 850 MEG H.D.D
- 1 MEG PCI Video Card
- 14" SVGA N.I. Mon- 1024 x 768 0.28mm D.P.
- 1.44 3.5" F.D.D.
- Ritron Mouse Pad
- Mouse & Joystick
- 101 Keyboard
- 16-bit Sound Card
- Magnetic Shielded Speakers
- Workgroups for Windows 3.11 or Windows 95

*MS Works will only work with Windows 95

4X QUAD-SPEED CD-ROM DRIVE

- BONUS 7 FREE CD SOFTWARE TITLES: Windows 95: Microsoft- Works/Money/Encarta 96/ Golf & CD Sampler. For DOS/Win 3.11: Dangerous Creatures and Yellow & White Pages Phone Disc.
- 20 Megabytes FREE SHAREWARE GAMES.



CPU CHOICES	TAX EX	TAX INC
Cyrix 5x86-100	$1449	$1695
Pentium™ 75 ...	$1690	$1845
Pentium™ 100 .	$1825	$2095
Pentium™ 120 .	$1890	$2150
Pentium™ 133 ..	$1995	$2285
Pentium™ 150 .	$2150	$2450
Pentium™ 166 .	$2400	$2750

With HEX SPEED CD-ROM DRIVE....$100 extra
*With OCT SPEED CD-ROM DRIVE....$280 extra
All Pentium™ Motherboards come fitted with 256K Pipeline Cache.

FREE HOME DELIVERY & SETUP- MELBOURNE METRO AREA ONLY
4 YEAR PARTS/LABOUR & HARDWARE WARRANTY (FIRST 2 YEAR ON-SITE) MELB MET AREA
3 HOUR FREE TRAINING COURSE

RITRON CLASSIC

The ideal system for today's power-hungry users...



16 MEG RAM NOW!

- ★ BONUS 7 FREE CD SOFTWARE TITLES: Microsoft- Works/Money/ Encarta for 96/Dangerous Creatures/Golf & CD Sampler and Yellow & White Pages Phone Disc.
- ★ 20 Megabytes FREE SHAREWARE GAMES.



- ★ Hex-Speed CD-ROM drive
- ★ 16 MEG RAM
- ★ Latest Triton chipset M.B.
- ★ 2 MEG DRAM Diamond Stealth 64 Video Card PCI bus 64-bit
- ★ 1.6 GIGABYTE HDD
- ★ 15" XGA Digital Mon-1280 x 1024 0.28mm D.P. Low radiation
- ★ 1.44 3.5" F.D.D.
- ★ Ritron Mouse Pad
- ★ Joystick
- ★ 101 Keyboard
- ★ 16-bit Sound Card
- ★ Microsoft Ergonomic Mouse
- ★ Magnetic Shielded Speakers
- ★ Workgroups for Windows 3.11 or Windows 95



CPU CHOICES	TAX EX	TAX INC
Cyrix 5x86-100	$1990	$2290
Cyrix 6x86-100	$2300	$2620
Pentium™ 75 ..	$2200	$2510
Pentium™ 100	$2350	$2670
Pentium™ 120	$2440	$2770
Pentium™ 133	$2540	$2890
Pentium™ 150	$2690	$3045
Pentium™ 166	$2990	$3390

*With OCT SPEED CD-ROM DRIVE....$80 extra
All Pentium™ Motherboards come fitted with 256K Pipeline Cache.

★ NOW COME WITH FREE MS Works CD tutorials

FREE HOME DELIVERY & SETUP- MELBOURNE METRO AREA ONLY
3 HOUR FREE TRAINING COURSE
4 YEAR PARTS & LABOUR WARRANTY (FIRST 2 YEAR ON-SITE) MELB MET AREA
PLEASE NOTE THAT CONDITIONS APPLY

SPECIAL OFFER- OEM 28.8k internal modem for only $299 if bought with these systems. Hot item! X18598

*MS Works will only work with Windows 95

PERIPHERALS & UPGRADES OPTIONS FOR YOUR SYSTEM

SUPA MOTHERBOARD UPGRADES

Cyrix 5x86-100 PCI No Cache	$229
Cyrix 6x86-100 PCI M.B. NEW!	$699
PENTIUM™ 75MHz@/256 C PCI/ISA	$399
PENTIUM™ 100MHz@ PCI/ISA	$649
PENTIUM™ 120MHz@ PCI/ISA	$749
PENTIUM™ 133MHz@ PCI/ISA	$849
PENTIUM™ 150MHz@ PCI/ISA	$999
PENTIUM™ 166MHz@ PCI/ISA	$1299

Come with I/O fitted on motherboard

PCI UPGRADE KITS

Bring your old 386/486 boxes forward into the new powerful PCI technology with these ready-to-go kits, without spending a bundle. Save by reusing your old VGA monitor, & peripherals.

***PCI 1MB Video Card .. $89**
PCI 2MB Video Card ... $149
Cyrix 5x86-100 CPU $119
AMD 586-133 CPU $149

EXTRA 1MEG MEMORY UPGRADE FOR *PCI video card AVAILABLE NOW...

512k SOJ VIDEO DRAM $65 for 2pcs

Note:Two pcs make up 1meg
Also suitable for:•S3 Video Card •Diamond Stealth 64 DRAM, etc.

BARE MOTHERBOARDS

PCI 80486 No Cache $129
PCI 80486 256K Cache Incl. I/O $169
PENTIUM 256K Pipeline Cache .. $239
PENTIUM 512K Standard Cache $279

V.34 DATA/FAX MODEM 28,800BPS

ONLY $345

High performance and reliable *external modem.* Extensive Auto dial features. Extended AT command set. User's manual, installation disks, COMit Lite & WinFax Lite & DosFax Lite

FLOPPY DISKS DRIVES

1.44 F.D.D $49.95
1.2MB F.D.D. $89.00

MEMORY

	1-9	25+	100+
30 PIN SIMM			
1M x 9-70 With Parity	$49	$45	$43
4M x 9-70 With Parity	$179	$169	$159
72 PIN SIMM FOR PENTIUM™		*Processor M.B*	
4M X 8-70 No Parity	$109	$99	$95
4M X 9-70 With Parity	$199	$189	$185
8M X 9-70 No Parity	$229	$219	$209
16M X 8-70 No Parity	$479	$469	$449
32M X 8-70 No Parity	$1199		

NEW EDO RAM

Latest RAM technology RUN SOFTWARE APPLICATIONS 20% FASTER. SUIT ONLY MOTHERBOARDS WITH TRITON CHIPSETS.

	1-9	10+
4M	$139	$129
8M	$279	$269
16M	$699	$659

REUSE 30 PIN SIMM RAM!

4 X 30 PIN TO 72 PIN ADAPTOR

NEW!

Don't throw away your old 30 pin SIMM RAM -Reuse them in new 486DX4 motherboards with this innovative adaptor.

AVAILABLE IN LEFT OR RIGHT FACING MODULE

ONLY $16.95

MONITOR RANGE
All on display at all Stores

- 14" N.I. 1024x768 (0.28mm D.P.)Full Scan $399
- 15" XGA Digital Low Radiation 1280x1024 .. $599
- 15" MITAC MPRII NEW! $649
- 17" XGA Digital MPRII 1280x1024 .. $1049
- 17" XGA Digital MPRII 1600x1280 (0.26mm Dot Pitch) $1395
- 20" XGA Digital MPRII NEW! $2099

15" & 17" Digital Monitor come with Economy Management Software

Removable Cartridge ZIPPY DRIVE

ON DISPLAY AT OUR CITY STORE

NEW! ONLY 3 1/2" SIZE!

SYQUEST EZ135 4MB/SEC DRIVES- EASY TO USE

$369

"zippy" 13.5ms access speed- 135MB cheap storage & backup. As fast as a hard drive. Easy to use.

135MB Cartridges-$44.95

NEW FREE SERVICE!

Buy a modem off our city store and have it installed **for free** (if possible, depending on your computer). You'll have to bring your computer in or onsite service is available for $35 per hour.

HARD DRIVES VOICE COIL IDE HD

Capacity	Av.Access	Tax Ex.	Tax Inc
540M	12ms	$249	$300
640M	12ms	$249	$300
850M	11ms	$250	$305
1.08GB	12ms	$270	$329
1.27GB	10ms	$315	$384
1GB SCSI HD	10ms	$460	$561
1.6GB	10ms	$370	$451
2.1GB IDE HD	10ms	$500	$610

ALL DRIVES COME WITH 3 YEAR WARRANTY
HARD DRIVE BRACKET....$4.95

$79 REMOVABLE HDD CARRIER

Now you can swap as many different HDD as you like. Exchange data between systems.

VERBATIM DISKS

CARDBOARD BOXES DESC.	1-9	10+
3½ DS/DD	$17.95	$16.95
3½ DS/HD	$17.95	$16.95
5¼ DS/DD	$11.95	$10.95
5¼ DS/HD	$14.95	$13.95

MICROSOFT SIDEWINDER 3D PRO



NEW

•Digital tracking joystick •Works with Windows or DOS-based game •Precise & swift response •Bundled with MechWarrior 2 CD- the hottest game in town! Great Value!

C14290 $119

MULTIMEDIA UPGRADE KIT



Quad-Speed $279

Hex-Speed $379

With easy-to-follow installation instructions. All CD-ROM drives are Kodak PhotoCD® compatible. •16-bit Sound Card•Stereo Speakers•Software titles: Microsoft- Encarta'96/Works/Money/Golf/Dangerous Creatures & CD Sampler which previews over 55 MS titles and has 8 Windows games.

CD ROM DRIVES

QUAD-SPEED CD ROM DRIVE IDE INTERFACE $129
HEX-SPEED CD ROM DRIVE $219
NEW OCT-SPEED CD ROM DRIVE $299

DOOR BUSTER ITEM! SAVE HEAPS!
3.5" NO NAME BRAND HIGH DENSITY DISKS IN PACK OF 10: SAVE! SAVE!

1-9	10+
$4.95	$4.75

RITRON COMPUTER SYSTEMS

CPU TYPE	TAX EX	TAX INC
Cyrix 5x86-100 ..... (GREAT VALUE!!)	$999	$1219
Cyrix 5x86-120	$1125	$1372
Pentium™ 75*	$1145	$1395
Pentium™ 100*	$1307	$1595
Pentium™ 120	$1420	$1730
Pentium™ 133	$1490	$1818
Pentium™ 150	$1675	$2043
Pentium™ 166	$1855	$2263

*External 256K Cache

All systems include: 4 MEG RAM•635 MEG H.D.D.-GREAT VALUE!!• 1.44 MEG 3.5 FDD • Mini or Baby AT casing •2 SPG Ports•101 Keyboard • 14" SUPER VGA (1024 X 768) (0.28" DOT PITCH) Colour Monitor •Systems now fitted with PCI video cards - Better performance value for the same price. Wow! -We strongly recommend 8MB RAM minimum for better performance under Windows 3.11 or Windows 95

NOW WITH 635MB H.D.D.

'EE 3 HOUR NING COURSE (MELB.) FOR ALL COMPUTER SYSTEMS INCLUDING MULTIMEDIA SYSTEMS

4 YEAR PARTS & LABOUR WARRANTY

rie ROD IRVING ELECTRONICS PTY LTD

ESTABLISHED SINCE 1977. 100% AUSTRALIAN OWNED A.C.N. 005 428 437

HEAD OFFICE: 56 Renver Rd Clayton, Victoria, 3168 Ph: **(03) 9543 7877**

NORTHCOTE: 423 High St. Ph: **(03) 9489 8866** Fax:(03) 9489 8131

VERMONT: 190 Rooks Rd. Ph: **(03) 9874 8888** Fax:(03) 9874 2288

BLUESTAR COMPUTERS: 271 Maroondah Hwy. Ringwood **Ph: (03) 9870 1800** Fax:(03) 9879 3027

MELB CITY STORE: 48 A'Beckett St. City. Ph:**(03) 9663 6151.** Fax (03) 9639 1641 *Open 9am-8pm on Fridays.*

BOX HILL: 1031 Maroondah Hwy. Ph: **(03) 9899 6033** Fax:(03) 9899 0156 *Open 9am-3pm on Saturdays.*

OAKLEIGH: 240C Huntingdale Rd. Ph: **(03) 9562 8939** Fax:(03) 9562 8940

TRADING HOURS: Mon/Fri 9am - 5.30pm.Sat 9am - 1pm

Tax Exempt sales: **RITRONICS WHOLESALE** Ph.**(03) 9543 2166** Fax.(03)9543 2648
RIE BULLETIN BOARD Ph: (03) 9562 7877 For Specials, info & Shareware
E-MAIL: rie @ ozemail.com.au
MAIL ORDER: Ph:**(03) 9543 7877** Fax:(03) 9543 8295

Mail Order Hotline 1-800 33 5757

Serving Australia Wide

GG25496

ERRORS & OMISSIONS EXCEPTED. PRICING CHANGE WITHOUT NOTICE.

Pentium™, OverDrive™ & Intel486™ are registered trademarks of the Intel Corporation. Microsoft is a registered trademark of the Microsoft Corporation.

rie ROD IRVING ELECTRONICS PTY LTD
ESTABLISHED SINCE 1977
A.C.N. 005 428 473
ROD'S HOTLINE 1-800 33 5757
MAIL ORDER LOCAL CALLS: (03) 9543 7877

ALL BRAND NEW PRODUCTS LINEUP...

US Robotics MODEMS

Courier V.34+
33,600 DATA/FAX MODEM



The World's Fastest Modem!

X18588 **$749**

Sportster®
28,800 DATA/FAX MODEM



X18586

Chosen by millions for small business, home office and personal use.

WAS ~~$549~~ **$499**

512K SOJ VIDEO DRAM 70NS

$35



U20891 25mm (L) x 14 mm(W)

Video memory upgrade RAM. 2 pcs is required to make up 1MB video upgrade

SUITABLE FOR: • Trident 9400 - 9440 • S3 • Cirrus Logic 54xx • Diamond Stealth DRAM

2 for $69

AMP-001 MPC UPGRADE KIT
FULL FUNCTION AMPLIFIER

A20220 **$59.95**




WAS $69.95

This full function amplifier will complement your existing sound card to give precise control over its tonal range, such as treble, bass and volume effects. Will fit in a 3.5" bay. Comes with connecting power wires and earphones. This unit connect to external speakers giving an output of 10 watts per channel.

SAVE HAVING TO RUN YOUR HI FI SPEAKERS OFF A SEPARATE AMPLIFIER

4 X 30 PIN TO 72 PIN

$16.95



Don't throw away your old 4 x 30 pin SIMM just because they cannot be used in new 72 pin motherboards. This adaptor will save you money. Simply slot in all your 30 pin SIMM RAM into the new **SIMM Convertor card** (whether it be 4 x 1 MEG, 4 x 4 MEG, etc) and use it in new 72 pin (486DX4) motherboard. The motherboard will read the 30 pin RAM as 72 pin ones! No need to throw out your old RAM! ***Note:*** *May or may not work in Pentium motherboards. Certain conditions must be met.* ***AVAILABLE AS LEFT OR RIGHT FACING MODULE***

COLOUR DIGITAL CAMERA

At last, an affordable digital camera under a thousand dollars! It's packed with features that above $2,000 digital cameras have and yet cost less! *Wow!!*



- ***PORTABLE***
- ***LOW COST***
- ***VERSATILE***

16.8million colours image capture

The Digicam features:

- Portablility- it can be used on desktop and laptop PC by plugging into the parallel port (no iterface card required).
- Captures still images at 16.8million colours and Digital AVI motion Video (up to 15 fps at 60 x 80).
- Up to 640 x 480 resolution
- Automatic Gain and shutter control with manual override
- Automatic Colour Correction

Can be used for:

- Digital Still Image Capture up to 640 x 480 at 16.8million colours
- Digital AVI Motion Video (up to 15fps at 60 x 80)
- Video conferencing
- Remote site monitoring

ALL NEW

BACK-UPS Pro PnP 650

Gives you 10 minutes to perform backup or exit safely.



$626

With Windows® 95 capability to put the power of server on your PC it has become even more vital to protect your data from power surges/blackouts. Back-UPS Pro PnP Software included provides for safe automatic shut-down, power event recording, real time display of UPS status. From USA.

AVAILABLE TO ORDER

PC DIAGNOSTIC 95

Post diagnostic Card & Diagnostic software for PC compatible computer

ALL NEW



Provide a set of diagnostic tools for PC compatible computers. Includes Post Diagnostic Card, Diagnostic Software and up-to-date POST code data base. Allow technicians to monitor the POST codes generated by the computer BIOS during the pre-boot initialization. If the PC fails to boot the POST error code will be displayed on the seven segment displays. Check this code against the POST code listings supplied and you have identified the faulty component. It's that easy! Areas tested includes: • CPU & NPX • Motherboard chipset • Cache • Base & Extended RAM • Serial and Parallel Ports • Keyboard controller and more!

AVAILABLE TO ORDER

OUR ENTIRE KITS RANGE

PLEASE SEND ALL MAIL ORDERS TO: ***MAIL ORDER DEPT, ROD IRVING ELECTRONICS PTY. LTD., LOCKED BAG 620, ROSEBANK MDC, CLAYTON SOUTH, VIC 3169.***

CAT	Description	R.R.P
K10005	SOLAR VOLTAGE REGULATOR	$13.95
K10040	ETI 480 50W AMP	$27.95
K10045	ETI 480 100W AMP	$34.95
K10050	ETI 480 POWER SUPPLY	$28.95
K10060	BALANCED MICROPHONE AMPLIFIER	$12.95
K10065	GENERAL PURPOSE AMPLIFIER	$14.95
K10070	BALANCED INPUT DIFFERENTIAL PREAMP	$19.95
K10075	FLOAT NICAD CHARGER	$14.95
K10080	TRANSISTOR TESTER	$22.95
K10085	300W PLAYMASTER AMP	$119.00
K10095	2 TONE ALARM	$9.95
K10100	1.5V TO 9V DC CONVERTER	$11.95
K10105	3 DIGIT COUNTER	$22.95
K10110	ELECTRIC FENCE	$23.95
K10115	ELECTRIC FENCE CONTROLLER	$61.95
K10120	TV PATTERN GENERATOR	$94.95
K10125	UNIVERSAL POWER SUPPLY	$12.95
K10135	LED SCANNER	$17.95
K10140	LOW FUEL INDICATOR FOR CAR	$11.95
K10145	SCREECHER CAR ALARM	$36.95
K10150	12/24V LIGHT CHASER	$21.95
K10160	THERMOSTATIC SWITCH FOR RADIATOR FANS	$31.95
K10165	I/O ADAPTOR FOR PC's	$59.95
K10166	240VAC TRIAC TRIGGER (SHORT FORM)	$59.95
K10167	240VAC TRIAC TRIGGER (FULL FORM)	$109.95
K10170	INPUT BUFFER & RELAY DRIVER	$34.95
K10175	LOW COST SIG. TRACER/AMP	$69.95
K10180	STEREO FM TRANSMITTER	$33.95
K10155	LOW VOLTAGE CUTOUT FOR CAR /BOAT	$22.95
K10200	IN-CIRCUIT TRANSISTOR TESTER	$14.95
K10205	VHF POWERMATCH	$88.95
K10215	TEMPERATURE PROBE FOR MULTIMETERS	$19.95
K10225	18V / 1AMP BENCH TOP POWER SUPPLY	$79.95
K10260	INVERTER 2KW (NON ASSEMBLED)	$1,495
K10265	INVERTER 2KW ASSEMBLED & TESTED	$1,895
K10295	LOW OHMS METER	$29.95
K10300	TEMPERATURE ADAPTOR	$24.95
K10305	VOICE OPERATED RELAY	$19.95
K10310	IGNITION KILLER	$22.95
K10315	HEADPHONE AMPLIFIER	$34.95
K10320	VIDEO RF MODULATOR	$17.95
K10325	50W AUDIO AMPLIFIER	$54.95
E10325	PCB 50W AUDIO AMPLIFIER TDA1514A	$19.95
K10330	RS232 FOR COMMODORE 64	$24.95
K10335	RGB TO PAL ENCODER MODULE	$49.95
K10340	CAMCORDER MIXER	$29.95
K10345	KARAOKE BOX	$28.95
K10350	"IMPROVED" REMOTE CONTROLLER EXTENDER	$56.45
K10355	HIGH ENERGY IGNITION	$49.95
K10356	BREAKERLESS IGNITION	$44.95
K10360	LOUDSPEAKER PROTECTOR	$29.95
K10370	PORT. 12V LEAD ACID BATTERY CHARGER	$27.95
K10375	15W 12-240V INVERTER	$49.95
K10380	1GHz DIGITAL FREQUENCY COUNTER	$147.95
K10390	LOW COST QUIZ GAME ADJUDICATOR	$34.95
K10395	16-SECOND MESSAGE RECORDER	$65.95
K10400	WOOFER STOPPER	$55.95
K10405	COLOUR VIDEO FADER	$32.95
K10415	PC-CONTROLLED EPROM PROGRAMMER	$99.95
K10425	DELUXE CAR ALARM	$55.95
K10430	REMOTE CONTROL ELECT. COCKROACH	$69.95
K10440	HIGH EFFICIENCY FLUORO INVERTER KIT	$49.95
K10445	IMPROVED DECODER FOR ACS SIGNALS	$19.95
K10450	A SIMPLE LOW VOLTAGE SPEED CONTROLLER	$13.95
K10455	PRINTER STATUS INDICATOR FOR PRINTERS	$65.95
K10465	LOW COST 25W AMPLIFIER MODULE	$18.95
K10460	VERSATILE 40V / 3A LAB POWER SUPPLY	$165.95
K10470	CHAMP 0.5 WATT AMPLIFIER	$9.95
K10475	90 SECOND MESSAGE HOLDER	$97.95
K10476	75 SECOND MESSAGE HOLDER	$93.95
K10480	CONTROL STEPPER MOTORS WITH YOUR PC	$65.95
K10485	EGO TESTER KIT	$19.95
K10490	LOW COST MIDI BREAK-OUT BOX	$32.95
K10495	200W INVERTER KIT	$199.95
K10500	VOICE OPERATED AUDIO SWITCH	$12.95
K10505	SIMPLE LED CHASER	$19.95
K10510	LEVEL CROSSING DETECTOR FOR MODEL RAILWAYS	$29.95
K10515	SOUNDS & LIGHTS FOR LEVEL CROSSING	$34.95
K10520	AN IMPROVED DSO ADAPTOR FOR PC'S	$158.95
K10521	DSO ADAPTOR (INCLUDES ADC0861)	$168.95
K10525	WEEKLY REMINDER TIMER	$19.95
K10530	L/NOISE UNI. STEREO PREAMP	$19.95
K10535	LIGHT & SOUND TRIGGER	$41.95
K10540	50W AUDIO AMPLIFIER	$37.50
K10545	IND. METAL BALANCE DETECTOR	$58.95
K10550	FAST CHARGER FOR NICAD	$42.95
K10555	DUAL ELECTRONIC DICE	$24.95
K10560	DIGITAL VOLTMETER FOR CARS	$39.95
K10565	DIGITAL TACHOMETER FOR CARS	$49.95
K10570	COOLANT LEVEL ALARM	$29.95
K10575	STEAM TRAIN WHISTLE & DIESEL HORN SIMULATOR	$22.45
K10580	BUDGET PRICED TEMPERATURE CONTROL	$39.95
K10585	HIGH-POWER DIMMER FOR INCANDESCENT LAMPS	$69.95
K10595	NICAD ZAPPER	$29.95
K10600	GO/NO-GO CRYSTAL CHECKER	$18.95
K10605	CHAMP PRE-AMP	$8.95
K10610	MINI-VOX VOICE OPERATED RELAY	$13.95
K10615	LONG-WAVE AM RECEIVER FOR AIRCRAFT WEATHER INFORMATION	$37.50
K10620	AUTO DISCHARGER FOR NICAD BATTERY PACKS	$27.95
K10630	TALKING HEADLIGHTS REMINDER	$62.95
K10635	BEGINNER'S VARIABLE DUAL-RAIL POWER SUPPLY	$39.95
K10640	CLIFFORD-A PESKY LITTLE ELECTRONIC CRICKET	$15.45
K10645	3-SPOT LOW DISTORTION SINEWAVE OSCILLATOR	$49.95
K10650	A BUDGET PRICED "SHOESTRING" STEREO AMP	$99.95
K10655	DIGITAL EFFECTS UNIT FOR MUSICIANS	$138.95
K10660	DIGITAL TRIGGER ADAPTOR FOR SCOPES	$68.95
K10665	A PHOTOGRAPHIC TIMER FOR DARKROOMS	$64.95
K10670	ECONOMY SURROUND SOUND DECODER	$59.95
K10675	LOW COST TRANSISTOR TESTER/MOSFET	$29.95
K10680	PC- DRIVEN ELECTROCARDIOGRAM	$29.95
K10685	IMPROVED FLEXITIMER MK2	$22.95
K10690	LED BATTERY VOLTAGE INDICATOR	$9.95
K10695	JACOB'S LADDER DISPLAY (Without Coil)	$29.95
K10696	JACOB'S LADDER DISPLAY (With Coil)	$59.95
K10700	FAST CHARGER FOR NICAD BATTERIES	$118.95
K10705	MODEL TRAIN CONTROL WITH SIMULATED INERTIA	$34.45
K10710	A MIXTURE DISPLAY FOR FUEL INJECTED CARS	$15.95
K10715	GEIGER COUNETR	$168.95
K10720	ENGINE IMMOBILISER	$33.95
K10725	LOW COST FIVE BAND EQUALISER	$32.95
K10730	**SHORT FORM** Low Cost Micro-Based ESR & Low OHMS Meter	$44.95
K10735	PC DRIVEN EGO SENSOR ANALYSER	$39.45
K10740	SMART DUAL 12V BATTERY CONTROLLER	$49.95
K10755*	LOW COST RF TEST OSCILLATOR	$69.95
K10760*	STROBOSCOPIC TUNER	$47.95
K10770*	STEAM WHISTLE FOR MODEL BOATS & TRAINS	$27.95

*SOON AVAILABLE

EAKIT696-APR 96S

E. & O.E. ERRORS & OMISSIONS EXCEPTED PRICES CHANGE WITHOUT NOTICE


rie ROD IRVING ELECTRONICS PTY LTD ESTABLISHED SINCE 1977 A.C.N. 005 428 473
ROD'S HOTLINE 1-800 33 5757
MAIL ORDER LOCAL CALLS: (03) 9543 7877

ALL NEW PENTIUM 100-BASED KTX NOTEBOOK

POWER COMPUTING FOR THE EXECUTIVE ON THE GO!

With 8MB RAM & 510MB HDD

The KTX notebook computer is an AT compatible notebook with powerful Intel® Pentium P54LM- 100MHZ performance. It provides the power and performance of a desktop system in a lightweight and portable package.



SOUND CARD, SPEAKERS & INTERNAL MICROPHONE INCLUDED IN PACKAGE!

ALL NEW

Features

- **Intel Pentium P54LM-100MHz Processor** with 16KB Internal Cache
- **Removable 510MB Hard Disk Drive**
  - LBA mode support
- **High Performance Video**
  - 32 Bit PCI Bus
  - 1 MB Video DRAM
  - Simultaneous LCD/CRT Display
  - VGA/SVGA on LCD and External CRT
  - Integrated Liquid Crystal Display (LCD)
- **Digital Audio Recording and Playback Support**
  - SoundBlaster 2.01 compatible
  - FM synthesizer (Yamaha YMF3812 register compatible)
  - Internal Microphone and External Condenser
  - Microphone
  - Internal Mono Speaker and External output support for Headphone
- **Supports ECP and EPP parallel port modes Portable Pointing Devices**
  - 19mm Integrated Trackball (PS/2 type)
- **Standard Connectors**
  - 9 Pin Serial Port Connector
  - IR (Infrared) Port
  - 15 Pin Port for Connecting an External CRT
- **Display**
  - 25 Pin Port for a Parallel Device 6 Pin Connector for a PS/2 compatible keyboard, Pointing device or Numeric keypad
  - 200 Pin Expansion Port
- **Security**
  - Removable Hard Disk Drive
  - Keyboard Protection
  - System Password Protection
- **Personal Computer Memory Card International**
- **Association (PCMCIA) PC Card Standard type**
  - 2.0 Slots (1 Type II and 1 Type III)
- 8 MB Dynamic Random Access Memory (EDO Dram), Upgradeable to 40 MB
- Integrated 3.5" Floppy Disk Drive (FDD)
- 84 Key Internal Keyboard Nickel Metal Hydride (NiMH) Battery Pack
- AC Adapter and Power Cord
- Light Emitting Diodes (LED) Indicating Notebook Status

Components

- Notebook computer
- AC Adapter and AC Power Cord
- Carrying Case
- Rechargeable Battery
- User's Guide
- Removal HDD Pack

FREE

MICROSOFT OFFICE UPGRADE FOR WINDOWS 95 VALUE PACK & MICROSOFT PLUS INCLUDED...



MS OFFICE- The next generation of integrated tools and easy access to their full power. Includes Word, Excel, PowerPoint and Schedule & & Access.
MS PLUS- optimize Windows 95 for your 486/Pentium systems.


$3995 *with Quad-Speed CD ROM drive*

LIMITED SPECIAL OFFER- 20 only

Bonus Free Microsoft Works/Money available with the first 20 units ordered!

P51437/250A GREEN MAIN BOARD

THE FIRST MOTHERBOARD THAT WE KNOW OF THAT SUPPORTS TRITON CHIPSET.



P51437/750A Green motherboard provides a highly integrated solution for fully compatible, high performance PC/AT platforms, and supports Intel Pentium and Cyrix 6x86 microprocessor. It features Write-Back Secondary Cache memory for 256KB in size Flexible main memory size can be installed from 8MB up to 128MB DRAMs, so as to give full play to the advantages of the Pentium and Cyrix 6x86 CPU. The main board offers a wide range of interface to support integrated on-board IDE and on-board I/O function. The current Green functions is divided into two phases: Standby and Suspend

Key Features: **CPU** Supports Intel Pentium 75, 90,100,120,133,150, 166 MHz CPUs • Supports P55C and P54CTB in specification • Supports Cyrix 6x86 100, 120 MHz CPU • 2.5V circuit on board, ready for future P55C support **Chipset** Intel's Triton/82430 FX chipset **Main Memory** Supports 4x72pins SIMMs module • 64-bit data path for flexible memory size expanded from 8MB up to 128M DRAMs on board • Supports EDO and Hyper Page mode DRAM (High speed) and also supports Standard Page mode DRAM **Cache Memory** Supports Write-Back Cache policy for 256KB L2 Pipelined Burst Cache **On-board IDE** Supports PIO and Bus Master IDE • Supports up to Mode 4 Timings • Supports transfer rates up to 22 MBytes/s • Supports 2 Fast IDE interfaces for up to 4 IDE devices including IDE hard disks and CD ROMs **Green Functions** Supports 2 Green modes: Standby and Suspend **On-board I/O** 3 x ISA Slots and 4 x PCI Slots • Use NS Plug & Play IC) chip PC87306 • Supports up to two 3.5" or 5.25" floppy drives • 360K/720K/12M/1.44M/2.88M format • All IO ports can be enabled or disabled • Two high speed 16550 compatible UARTs (COM1/COM2/COM3/COM4 selectable) with 16-byte send/receive FIFOs and support MIDI mode • One parallel port at I/O address 378H/278H/3BCH with additional bi-direction I/O capability and multi-mode selection (SPP/EPP/ECP) (IEEE1284 compliant) • Provides protection circuit to prevent damage to the parallel port when a connected printer is powered up or operated at a higher voltage • Real-time clock and keyboard controller built-in I/O Chip • Supports PS/2 mouse • Supports IrDA Infrared **BIOS** Licensed advanced AWARD BIOS. Supports Flash ROM BIOS, Plug and Play ready. Built-in NCR810 and Adaptec 7850 SCSI drivers **Board Size** 220mm x 250mm

LATEST CPU PRICE

Intel CPU		CYRIX CPU	
PENTIUM 75MHz	$189	486DX2-80	$63
PENTIUM 100MHz	$329	5x86-100 *NEW!*	$119
PENTIUM 120MHz	$399	5x86-120 *NEW!*	$219
PENTIUM 133MHz	$525	6x86-100 *NEW!*	$329
PENTIUM 150MHz	$695	6x86-120 *NEW!*	$499
PENTIUM 166MHz	$895	6x86-133 *NEW!*	$799

AMD		IBM CPU	
AMD 486DX4-100 *NEW!*	$105	5x86-100 *NEW!*	$119
AMD 486DX4-120 *NEW!*	$139	6x86-100 *NEW!*	$299
AMD 5X86-133 *NEW!*	$149	6x86-120 *NEW!*	$479
		6x86-133 *NEW!*	$799

AVAILABLE ON ORDER THROUGH OUR STORES OR BY MAIL ORDER

COMPUTER CARDS - HUGE RANGE!!

CAT NO.	DESCRIPTIONS	PRICE
	ISA	
X18075	1Meg 16bit VGA	$159
X18004	IDE/SPG	$39
X18005	High Speed I/O	$59.95
X17072	ADAPTEC SCSI 16bit 1522A	$189
X18165	16bit ETHERNET RJ45 + BNC	$59
X18169	16bit NE2000+	$119
X15810	Ethernet 5-port 10 base T hub	$169.95
X18159	Ethernet 10 base T Connector	$119
X18190	Printer 2-Port Slct Lpt 1-2 Card	$39
X18191	Printer Port Slct Lpt 1-2-3 Card	$49
X18141	High Speed Serial Card 1-Port 16550	$49.95
X18041	High Speed Serial Card 2-Port 16550AFN	$69
X18143	High Speed Serial Card 4-Port 16550AFN	$189
NEW!	Dual Speed 16650 UARTS modem chip	$99
X18019	Games Card	$19
C14260	SMART GAMES Cont	$39.95
X18514	FULL -DUPLEX ISA **ETHERNET**	$99
	VLB	
X18003	ENHANCED VESA MULTI I/O	$49
X18186	VESA IDE Cache Cont	$349
X18047	VESA IDE ENHANCED MULTI I/O	$119
X18050	VESA IDE ENHANCED MULTI I/O- **PROMISE TECH**	$129
	PCI	
X17900	PCI 1M VGA TRIDENT 9440	$149
X18179	PCI IDE CONTROLLER	$39
X18206	PCI VGA DIAMOND STEALTH 1MEG DRAM	$279
X18207	PCI VGA DIAMOND STEALTH 2MEG DRAM	$349
X18208	PCI VGA DIAMOND STEALTH 2MEG VRAM	$529
X18209	PCI VGA DIAMOND STEALTH 4MEG VRAM	$999
X18183	PCI VGA CIRRUS LOGIC 5430 1MEG	$79
X18188	PCI VGA CIRRUS LOGIC 5430 2MEG	$159
X18510	FULL -DUPLEX PCI ETHERNET	$149
X18210	2MB WRAM GrafixStar 700 Video	$499
X17073	PCI SCSI MASTER ADAPTEC	$595
X18212	PCI MGA MILLENNIUM 2MB WRAM	$635
X18214	PCI MGA MILLENNIUM 4MB WRAM	$930
X18216	PCI MGA MILLENNIUM 8MB WRAM	$1530



CPU HEAT SINK/ COOLING FAN

The easy way to cool CPU. Suitable for 486 cpus. Size: 45(D) x 45(W) x 22(H)mm

WAS $12.95

H01611 **$10.95**

CPU COOLING FAN

Cat No. H01616



Suitable for Pentium/ 686 cpus. Fitted with "H" type clip for use with ZIF socket type 7. No more messy glue, just clip on.

WAS $29.95

$15.95

PLEASE SEND ALL MAIL ORDERS TO:
MAIL ORDER DEPARTMENT, ROD IRVING ELECTRONICS PTY. LTD., BAG 620, CLAYTON SOUTH, VIC 3169.

MELBOURNE: 48 A'BECKETT ST, MELBOURNE 3000. • PH: (03) 9663 6151 • FAX: (03) 9639 1641 • Mon-Thurs: 9.00-5.30pm • Fri: 9.00-8.00pm • Sat: 9.00-1.00pm
☐ **VERMONT:** 190 ROOKS RD, VERMONT 3133 • PH: (03) 9874 8888 • FAX: (03) 9874 2288 • Mon-Fri: 9.00-5.30pm • Sat: 9.00-1.00pm
☐ **OAKLEIGH:** 240C HUNTINGDALE RD, OAKLEIGH 3166 • PH: (03) 9562 8939 • FAX: (03) 9562 8940 • Mon-Fri: 9.00-5.30pm • Sat: 9.00-1.00pm
NORTHCOTE: 423 HIGH ST, NORTHCOTE 3070. • PH: (03) 9489 8866 • FAX: (03) 9489 8131 • Mon-Fri: 9.00-5.30pm • Sat: 9.00-1.00pm
☐ **BOX HILL:** 1031 MAROONDAH HWY, BOX HILL 3128. • PH: (03) 9899 6033 • FAX: (03) 9899 0156 • Mon-Fri: 9.00-5.30pm • Sat: 9.00-3.00pm
☐ **CLAYTON:** 56 RENVER RD, CLAYTON 3168. • PH: (03) 9543 7877 • FAX: (03) 9543 8295 • Mon-Fri: 9.00-5.30pm • Sat: 9.00-12.00pm
☐ **BLUESTAR COMPUTERS:** 271 MAROONDAH HWY, RINGWOOD 3134. • PH: (03) 9870 1800 • FAX: (03) 9879 3027 • Mon-Fri: 9.00-5.30pm • Sat: 9.00-1.00pm
☐ **SYDNEY:** 74 PARRAMATTA RD, STANMORE 2048. • PH: (02) 519 3888 • FAX: (02) 516 5024 • Mon-TFri: 9.00-5.30pm • Sat: 9.00-1.00pm
☐ **ADELAIDE:** 241-243 WRIGHT ST, ADELAIDE 5000. • PH: (08) 211 7200 • FAX: (08) 211 7273 • Mon-Thurs: 9.00-5.30pm • Fri: 9.00-8.30pm • Sat: 9.00-5.00pm • **Sun: 10.00-4.00pm**

EACPU696 APR '96S

ERRORS & OMISSION EXCEPTED. PRICES CHANGE WITHOUT NOTICE



INFORMATION CENTRE

by PETER PHILLIPS

Fidonet, audio, timers and all

If your Internet costs are starting to mount up, you might be interested in our first topic this month: Fidonet. There's also more about telling the difference between 50-ohm and 75-ohm BNC connectors, and a reader gives us the lowdown on hydrogen generation in a zinc-carbon cell. And of course there are the usual letters about projects and matters various...

These days most people know about the Internet and the World Wide Web. But unless you cruise computer bulletin boards, you may not have heard about a similar, and much older system called Fidonet. Because it's a facility many readers are likely to be interested in, I'm opening this month's column with a description of Fidonet contained in a file I recently downloaded from a BBS linked to Fidonet.

What *is* Fidonet?

Fidonet is an international electronic messaging network of bulletin board systems that allows users of any bulletin board in the network to communicate with other users on other networked boards. Fidonet has spread across Australia, Papua New Guinea, South East Asia, Western Europe, North and South America. Originally, only systems which used Tom Jenning's 'Fido' Bulletin Board program could be part of Fidonet, but now many other systems are participating in the network.

Fidonet can be used in two different ways. A user can address Fidonet mail to another user on another system in the Fidonet network. The mail will be sent through the network, and delivered to the recipient on his or her local Fidonet bulletin board. It typically takes a couple of days for a message to be delivered to another Australian bulletin board, depending on the distance the message has to travel and the reliability of the telephone system.

The second way is by participating in Echomail conferences. An Echomail conference is a discussion on a particular topic which takes place on a number of bulletin boards almost simultaneously. A message placed in an Echomail Conference on one bulletin board is 'broadcast' to all other boards in the network which are participating in that conference. There are a number of conferences available, including international ones, which cover a wide variety of subjects. Not all conferences are available on all Fidonet bulletin boards.

All Network mail and Echomail messages are sent via local, STD and IDD (for international Echomail and Netmail) telephone calls, so unless sponsored, the sysops involved (particularly the sysops of host systems) bear the cost of this. Users are therefore not charged for mail and messages.

Obviously, if messages are going to travel around the network, then the system needs time to send and receive them. A network 'Mail Time' has been set up, during which all Fidonet bulletin boards disallow calls from users, and spend their time delivering messages to their designated 'host' bulletin boards for forwarding to the rest of the network, and receiving messages which have been delivered to their host bulletin board.


This time is from around 3:00am to 6:00am Australian Eastern Standard Time. A Fidonet bulletin board system is unavailable during this time, but because it's in the early morning, very few users should be affected. If the Fidonet bulletin board also sends and receives mail from zone 1 (North America), there is an additional mail time from approximately 7:00pm to 8:00pm (AEST).

Each bulletin board connected to Fidonet has a unique 'address', allowing the bulletin board to be identified. The address consists of a zone number, network number and node number, and is written in the form zone:net/node. Zone 1 is North America, zone 2 is Europe, zone 3 is Australasia and zone 4 is South America. Zone numbers should only be specified when sending a message to a system outside your own.

So as you can see, the main advantage of Fidonet is cost: it's free. Some boards charge a fee of $30 (or so) per year to be a member, mainly to offset phone call costs to the host board. Others give free Fidonet access, such as the Mt Druitt TAFE College bulletin board run by Peter Harle. The phone number of this board is (02) 839 1310 and its Fidonet address is (3:713\709).

The system was developed by and is run entirely by enthusiasts, and works like this. Let's say you want to ask the world at large a question about electronics. You first dial up a BBS that supports Fidonet and gain entry to the message area relevant to electronics.

There are some 500 possible Fidonet subject areas, which might not all be available on the board you are operating through. As well, it's up to the sysop as to what areas are covered by the board,



and what these areas are called. Typical subject areas include electronics, ham radio, neurology, Windows 3.1, Windows '95 (international or local forums), MIDI music, photography, motor cycles, modems, chess, consumer reports, cooking, dieting, dogs and so on. If the area you want is not listed, ask the sysop to include it.

You then type your message, marking it as a message to ALL. Once the message is complete, do whatever else you

want on the board, then sign off. After a few days, replies (hopefully) will come in, ready for you to download.

Rather than read and write messages while you're on line however, it's better to use a mail reader program (like Blue Wave, which is shareware found on most boards). Using the mail reader, you prepare your message first, then upload it. And instead of reading all the messages while connected to the BBS (and preventing others accessing the board), you download them and read them in the mail reader at your leisure. Most mail readers let you insert a reply into a message, so the message and your reply are sent back to the BBS. Once you get the hang of it, it's easy enough.

I suppose you're wondering if we intend hooking the *EA* BBS to Fidonet. Unfortunately a Fidonet board needs about two hours a day of the sysop's time, and if we spent this time each day, we wouldn't be able to get a magazine out each month. But at least you now know about this system, and I can assure you, it's an excellent way of getting information without the cost of being an Internet user.

But our BBS is still a good way to contact other readers, and to leave messages for me. I've used reader messages from our BBS before, so considering the foregoing, it's appropriate to use some more.


PC scope

I was wondering if could help me. Over the last 12 months I've been looking for a program and hardware to build a single trace oscilloscope for my garage as a tune up scope. It appears your magazine has done such a project, but kit suppliers are having a hard time getting parts. As well, no one could tell me if it would be fast enough.

I need one that will plug into a PC and show me coil and spark patterns. The one I have now is getting very old and is not very reliable. Most of the cars are only idling at around 1000rpm. (Martin Heppenstall, via EA BBS)

I'm surprised you cannot get a kit of parts for the DSO Adaptor Mk2 (May/June 1994), Martin. This has been a popular project, and the last time we checked kits were available from a number of suppliers. This adaptor samples at up to 1MS/s, so it should be fast enough for your needs.

If you want a ready made unit, there are quite a few PC-based oscilloscopes around nowadays. These are external hardware boxes that interface the signal to the computer, which does the rest. That is, it does all the work of displaying



the waveform on the computer screen, calculating measurements and so on. The PicoScope range of PC-based instruments is one I'm familiar with, available through Emona Instruments (phone (02) 519 3933).

The speed of a 'virtual' scope is generally fairly slow (bandwidth of 50kHz or so) and usually depends somewhat on the computer. An advantage of a virtual instrument like the PicoScope is all the other instruments you get into the bargain: spectrum analyser, AC and DC voltmeters and so on. My review of the PicoScope is in the July '95 edition of *EA*.

Bondwell remote control

I recently acquired a pre-programmable remote control unit made by Bondwell, with a slide switch to select one of three possible devices to be controlled: VCR, TV and audio. I've tried unsuccessfully to track down the distributors, so I can get the device number listing to allow me to use the control. Can anyone help? (Phil Lee, EA BBS)

This is pretty specialised, so if anyone can help, either write to me, or leave the information on our BBS (phone (02) 353 0627).

Leclanche cell

In response to a recent reader enquiry about the operation of a Leclanche cell, I boldly pronounced that yes! there is hydrogen generated around the anode of a carbon-zinc dry cell. Double whammy — wrong wrong! As you probably read in last month's column, I got the anode bit wrong. Instead it's the cathode when the cell is discharging, and the anode when it's being charged. But now it seems I also got the hydrogen bit wrong — or have I?

I'm sorry, but I have to say that you are wrong — there is no hydrogen in a normally operating Leclanche cell. Here's a quick rundown according to modern theory. It has been found that for a wide range of conducting electrodes immersed in a variety of electrolytes, a voltage which is characteristic of each electrode system is established between the electrode under test and an internationally agreed reference electrode.

This is known as the electrode potential and is listed in textbooks for certain specified conditions. In practice, variations occur due to departure from these conditions, but the variations are small enough to be ignored if only a general understanding is required. Very roughly, the electrode potentials are: zinc electrode -0.7V, carbon electrode +0.8V, giving a total of 1.5V.

If a cell is constructed using any two electrodes in an electrolyte, the cell voltage can be calculated by taking the difference of the two electrode potentials. The magnitude of the electrode potential depends on the chemical reaction occurring at the electrode face, and for the Leclanche cell the zinc atoms lose electrons which flow through the external circuit.

The zinc atoms then become positively charged zinc ions which pass into the electrolyte. Manganese atoms are involved in a complex reaction with electrons returning from the external circuit, leading to the formation of a lower oxide of manganese, water and ammonia; but no hydrogen.

We can now examine the situation where the depolariser (manganese dioxide) becomes exhausted. In this case a second set of reactions take place, but the continuing passage of current causes a third and different reaction to set in. The electrode potential for this third reaction is close to zero so the cell voltage becomes 0 - (-0.7) = 0.7V, and the cell is described as being polarised and — believe it or not — the third reaction produces hydrogen. (Peter Steel, Mandurah, WA.)

Now Peter, aren't we being the teeniest bit pedantic here? As I see it, the manganese dioxide prevents the formation of hydrogen. Without it hydrogen is formed, which is why the manganese dioxide is put there in the first place, that is to get rid of... Well, you can see my drift. It's like denying it's hot outside, from inside an air-conditioned room. You wait when the air-conditioning breaks down! I guess it's a matter of how you want to look at it. Thanks for your letter Peter, I'm sure readers will

be interested in this rather in depth look at a Leclanche (zinc-carbon) cell.

OC926 transistor

I've noticed over the years that quite a lot of reader letters get direct replies from other readers, providing I include a contact address. This was the case for a recently published letter seeking information about an OC926 transistor, in which a reader has kindly forwarded copies of the required information to us and to our reader making the enquiry. For everyone's information, here's brief details of this now very superseded transistor.

This silicon device was one of a series released by Philips in the 1970s for general industrial applications. Regarding an alternative, I do not know the type of circuit that you are repairing, but there is nothing special about the OC926 and therefore a number of currently available devices should suit.

One that springs to mind which has the same lead connections and similar general characteristics is the 2N4032, but note that this device has a T0-39 case and therefore requires more space. (W. Woods, Glen Iris, Vic.)

Mr Woods included a copy of the OC926 data which shows a Vceo of 60V, a maximum collector current of 600mA, a current gain of greater than 30 (yes, rather vague), and a transition frequency of 360MHz. The important point of course is that it's a silicon device, so there's quite a lot of substitutes, if package style doesn't matter. Thank you, Mr Woods.


50Ω and 75Ω BNC connectors

And still there's more, on a topic I thought we had finished last month. You might remember a reader asked us recently how to tell the difference between a 50Ω and a 75Ω BNC connector. I included letters last month offering ways of distinguishing between the two, and this month I've got another. But this time the contributor actually sent me examples of both types, which at first sight look identical. But they're not, as the letter explains:

In the February 1996 issue, a reader asked about an easy way (besides actually measuring impedances at specified operating frequencies) to distinguish between 50-ohm and 75-ohm BNC connectors. I am writing from a company called Multi Contact Australia that supplies BNC connectors to many industries, including the broadcasting industry. Hopefully I can shed some light on the differences.

My information comes from speaking to a number of engineers in various TV stations around Australia, as well as actually studying these connectors myself. Once you compare the connectors side by side, the one basic and fairly obvious difference is the amount of plastic insulation lining the inner part of the BNC connector itself. Our connectors are Sofim brand and this material is PTFE.

In a 50-ohm connector, this insulation starts from the front (fat end) of the connector right the way up the cylinder which shields the contact pin. In a 75-ohm connector the insulation begins halfway up the shielding cylinder. The extra 'air' insulation provides the difference in impedance. Please note that this is based on a salesman's explanation (albeit relying on various engineers), and is not from an electrical engineer.



In the 50-ohm BNC connector, a thin sleeve of PTFE dielectric material extends out to the end of the plug, inside the metal 'outer' tube, whereas in the 75-ohm connector there is only the PTFE 'bulkhead'...

I have included a 50-ohm and a 75-ohm connector for your perusal. Interestingly these are for the same size cable. You quite rightly pointed out that normally the barrel sizes are different, but here they are exactly the same.

With the advent of serial digital cable technology becoming more prevalent in the broadcast industry, it's now important electrically (not just physically) to use a 75-ohm connector for a 75-ohm cable, to avoid impedance mismatches. Hope this helps. (Peter Williams, Multi Contact Australia, Sydney, NSW.)

There's nothing like having an example to look at and examine. Thank you Peter, for writing and particularly for the samples. I thought of taking a photograph of the two connectors, but I doubt if you would see the difference. Instead, I've drawn them (cross sectional view) to show what Peter means (Fig.1).

Notice that the PTFE insulation in the 50-ohm connector covers the entire surface of the shield around the contact pin, whereas in the 75-ohm type, it's simply a base for this pin. The only other difference I could find was the colour of the plastic sleeving, green in the 50-ohm type and blue in the 75-ohm version.

The pin in both connectors has the same diameter, the diameter for the cable entry in the metal ferrule is the same, everything else is identical. So it would seem it depends on the brand of the connector, as other readers have described differences that don't apply to this brand. Confusing? I'll say!

Flexitimer


Here's a question that I think refers to our March '91 Flexitimer.

I have built the Flexitimer Mk1, and I find that it latches up after about 50 seconds, which I think is OK. But I am finding that it will not reset itself at all, although the circuit checks out properly. I can get it to reset by applying a positive voltage on pin 4 of IC1 (555 timer) or pin 11 of the 4020 counter, but it will not reset itself no matter how long I leave it run. (Eric Larson, Forest Hill, Vic.)

It seems from your letter, Eric, that your Flexitimer Mk1 is operating as it should — pulling the relay in after 50 seconds and then latching up. This leaves the relay energised after the timing period has elapsed, as the circuit is normally reset only when the power to the timer is interrupted. If applying positive voltage to the reset pin of the 4020 causes the relay to release and then pulls in after another 50 seconds, then this would verify that the timer is performing correctly as designed.

I have a feeling that you are expecting the timer to release the relay, and then start timing again — which it won't, at present, because the circuit wasn't designed to this. But if this *is* what you want, I can suggest two options.

One is to cut the track between the collector of the transistor and pin 4 of the 555, then join pin 4 to pin 8; this will prevent the transistor from inhibiting the 555 at the end of the period, and would result in the relay turning on and off every 50 seconds. The other option



To refresh your memory, here's the circuit for the Flexitimer Mk1 — but with two suggested alternative modifications shown, for those who wish to make it cycle continuously. You can either break the link between the collector of Q1 and the reset pin of IC1, or apply an external reset signal to pin 11 of IC2.

is to disconnect C3 and use some external trigger to reset the binary counter when needed, much as you detailed in your letter.

Yet another option is to use the Flexitimer Mk2 (*EA* Aug-Sep 95), which can provide almost any timing configuration imaginable.

Class A amps

The next letter asks quite a few questions, all about audio...

I am considering building myself a tube and/or a class A amplifier. First question, is there a kit available for a class A amplifier? Next, I have noted in a loudspeaker catalog that it has two recommended power ratings. One for transistor and one for valve. What is the idea behind that, and is there a way of working out what power speakers to use? And is a class A amp in the same boat as a tube amplifier?

Another query concerning speakers. Where would I find the formula and schematic for a delay circuit, to delay tweeters and midranges? I have looked through books such as The Loudspeaker Design Cookbook by Vance Dickason, and have found nothing, except a mention of it. Could such a delay circuit be used in your Economy Surround Sound Decoder? Sorry to ask so many questions, but I'm sure your answers will enlighten me in some way. (Leigh Witchard, Prospect, Tas.)

First up Leigh, a class A amplifier can be either tube or solid state. Audio pundits have generally agreed over the years that a class A amplifier (whether tube, MOSFET or transistor) is superior to other classes of amplifier. To my ears, though, the difference between a good quality class A and class AB amplifier is insignificant.

I also don't agree that a 'tube' amplifier is superior to a good solid state amplifier. As I see it, an amplifier should have no 'sound' at all, which I believe is true of most of today's decent quality amplifiers anyway. In practice, an audio amplifier contributes the smallest amount of distortion compared to all the other components in the audio chain. Of course, there are people that can hear the difference (or claim to be able to), but I'm not one of 'em.

I do agree that the characteristics of a valve amplifier (either output or small signal) suit the needs of some guitarists. As well, the overload characteristics of a valve output stage are different, but if you are operating at overload, it seems a higher power amp is needed.

Having made these points, you mightn't be so disappointed when I tell you we have not produced a class A amplifier design in recent times, if at all.

Hot and inefficient

The problem with such an amplifier is its practicality. Although it gives the least distortion of all types of amplifiers, Class A also results in the largest, hottest and most inefficient amps.

So given that you probably can't hear the difference, why not build a more conventional amplifier, such as the Playmaster Pro Series 3 Power Amplifier described in Feb/March '94. If you want a valve amplifier, one was described in Sep/October '92. We've done many others, and more are on their way, but these two are our most recent.

I have not heard of a speaker power rating being defined in terms of the type of amplifier. It could be an instantaneous power rating, which is the peak short-term power the speaker can handle. The instantaneous output power of a transistor amplifier is generally higher than an equivalent valve amplifier, which might explain the two speaker ratings. Most speakers are rated according to the continuous power they can handle, which makes it independent of the type of amplifier.

As for delaying the sound to tweeters and midrange speakers, this can best be done electronically, not with external resistors, inductors and capacitors. Certainly an RLC network (as in a crossover network) can give a phase change, but not a significant delay. The only way to get what amounts to a delay is to place the tweeters and midrange speakers some distance behind the bass drivers.

Delaying a sound electronically is now done digitally, where sound is converted to a digital signal, clocked through various delay circuits, then converted back to analog. ICs that do this are now available, but note Leigh that they are for low level signals only, not the type of power signals needed by a speaker. One of these would suit the Surround Sound decoder you mention.

What??

This month's question comes from Peter Stuart, who has kindly sent me a number of interesting questions which I'll present in forthcoming issues. This question is not really electronic, despite its electronic 'feel', but can be solved with basic maths and a bit of trial and error:

An electronics enthusiast built two timers, each of which emitted a loud short tone to scare birds away from his vegetable garden. He could adjust the timers to produce their tones at regular intervals of a whole number of seconds, with an adjustment range between 60 and 90 seconds. To make the tones seem random, he set the adjustment for timer A differently to timer B.

One day his neighbour noticed that timer A went off four seconds before 9.00am, and timer B sounded at exactly 9.00 o'clock. Later he heard a tone at four seconds past 10.00am and another one four seconds later. Sometime between 10:10am and 10:20am he heard both timers go off simultaneously. From these observations the neighbour was able to calculate the time setting for each timer.

What were the timer settings, and at what time between 10:10 and 10:20 am did they sound together?


Answer to May's What?

By my calculations, the load current is 850.6A, the current from battery A is 303.8A and the current from battery B is 546.8A. These figures are rounded off to one decimal place. This gives a load voltage of around 10.63V.

I used simultaneous equations to solve the problem. ❖

Vintage Radio

by PETER LANKSHEAR



RF gain control and variable-mu valves

This month we take a look at the problems of controlling the gain of an RF amplifier, while not detracting from its ability to handle signals without distortion and other unwanted side effects. This is an ongoing problem with solid state technology, but it was largely solved in the valve era with the development of the variable-mu valve in late 1930.


Tom Moffat's story in the January 1996 issue of *EA* about the Hobart receiving station at Quoin Ridge was of special interest to me, as many years ago I worked in a similar station at Quartz Hill near Wellington. To tune across the spectrum with a good receiver connected to a real aerial at such a location is a memorable experience.

Tom mentions the superior performance of an old GEC BTR400 receiver, when compared to a state of the art Icom R-9000. By an odd coincidence, as my term at Quartz Hill was finishing, we were preparing to make room for some new receivers — GEC BTR400's no less — and more recently I have owned one of these monsters.

The BTR400 is a fine receiver, but many of the final generation of valve communication receivers can provide a similar performance. Two such sets, the Hammarlund SP600 and the Eddystone 940, have been previously described in this column, and there were others, including superb models from Racal and Collins. But can Tom Moffat's claim for superior results from equipment designed 40 years ago be substantiated? The short answer is yes.

Back in the late 1950's as semiconductor diodes and transistors became increasingly available, it became evident that in time, these devices would be able to do anything that valves could do, but better. This has of course proved to be so, and today solid state technology is infinitely more efficient and versatile than that of valves. Modern electronics and integrated circuits especially, would just not be possible with 'hollow state' devices, and there is no equivalent to much solid state technology, such as complimentary PNP/NPN operation.

There is one exception, however. To this writer's knowledge, as yet there is no solid state equivalent device to the variable-mu or 'remote cutoff' valve, and this is what provides the superior valve receiver performance quoted by Tom Moffat. In this column I'll try to explain why this is so.




Variable-mu valves came in a wide range of shapes and sizes. At left rear is an original Arcturus 551, on which the '35 was based; centre rear is a 6U7G, long used in Australian receivers; right rear is a Loctal based WB1/EF22, as used in the GEC BTR400 receivers. The small valve at left front is a 6BA6/EF93, developed in 1945 and a standard type until the end of the valve era, while that at right front is a 6ES8/ECC189, a high performance variable-mu twin triode.

Decades of gain control

This story really starts about 75 years ago. In the earliest multi-valve receivers, gain was controlled simply by switching amplifier stages in or out as required. With the growth of broadcasting however, something a bit more refined was required and a smoother control was found to be possible by varying valve filament voltage. This was fine, especially with thoriated tungsten filaments, but with the advent in 1927 of the UX226 AC heated valves, as described in this column last November, a new method of gain control was required.

The '26 was essentially the standard '01A type with a low voltage high current oxide-coated filament. But with just over an ampere required for each valve, gain control by means of a filament rheostat was no longer practical. Volume control of the first generation of AC receivers was therefore achieved by nothing more sophisticated than a variable aerial attenuator! This was a simple and effective method, but it did mean that the receiver was running at full gain the whole time — which did nothing beneficial for signal to noise ratios.

By the following year, the indirectly heated type '27 had replaced the '26 and with it came a far better method of gain control — that of



The 1929 Atwater Kent model 55 was one of the first receivers to use the mains powered screen grid type '24 valve. In an effort to overcome its sharp-cutoff characteristic, A-K varied screen voltage to control gain; but the real answer came with the development of the 35/51 variable-mu valve in 1930. Although the model 55 had a single tuning knob, the separate tuning capacitors were ganged using phosphor-bronze drive belts — visible at the top of the interior picture at right.



varying the grid bias of the RF stages, usually by means of a simple variable resistor connected between the cathodes of the RF stages and ground.

As an RF amplifier, typical operation of the '27 was at 180 anode volts with around -15 volts grid bias. Increasing this bias progressively up to -30V or more provided reasonably smooth and satisfactory control of receiver gain, although a local/distance switch, generally some sort of aerial attenuator, was usually provided to cope with very strong signals.

Progress in receiver development around this time was very rapid, with each season bringing features that made previous models obsolete. For broadcast band operation, with suitable stabilisation or neutralisation, the general purpose triode was a reasonably satisfactory RF amplifier, but there were significant shortcomings. Stage gain was limited, and the low anode impedance compromised selectivity; stability was often marginal and triodes were unsatisfactory as short-wave RF amplifiers.

The need for neutralisation and stabilisation was due to unavoidable grid to anode capacitance, which enables tuned triode RF amplifiers to become oscillators. The solution was, in retrospect, simple enough. By inserting an electrostatic shield between the grid and anode, inter-electrode capacitance could be sufficiently reduced to achieve stable amplification. Of considerable benefit too was the considerably higher amplification factor of the tetrode.

There were development problems however, and it was early 1929 before a really satisfactory AC heated screen grid valve, the tetrode '24, was produced in the US — to be closely followed in Europe and England by equivalent valves.

The characteristics of the tetrode proved to be considerably different from those of the triode. Whereas the amplification factor of a general purpose triode might be about 10, that of the '24 was more like 400! Although the full potential of this could not be realised in practice, a stage gain of 50 was readily achieved, a very significant improvement over the 10 or so of a stabilised general purpose triode RF stage. Further advantages were short-wave capability and, in a well designed amplifier, better stability.

SHARP CUTOFF	VARIABLE MU
24A	35/51
57	58
77	78
6C6	6D6
6J7	6K7
6J7g	6U7g
6SJ7	6SK7
6SH7	6SG7
KTZ63	KTW63
EF37	EF39
6AU6/EF94	6BA6/EF93

Table 1: RF pentodes were often designed as sharp- and remote-cutoff pairs. Here are some of the more common types.

However, although the screen grid valve may have permitted stable RF amplification, difficulties were experienced once again with *controlling* receiver gain; and this time there were undesirable side effects.

The problem was the large amplification factor of the tetrode valve. A relatively small change in grid bias voltage meant a significant change in anode current. Increasing the grid bias would certainly reduce the gain of an amplifier stage, but the problem was that, although the anode current might be practically cut off, the amplification factor itself was unaffected, so that even quite small signals overloaded the valve. Consequently, the level of signal that could be handled before the onset of serious distortion was very limited.

Several methods tried

Another method of reducing the gain of a tetrode RF amplifier was to control the screen voltage, but the signal handling ability still remained inadequate.

One well known manufacturer's efforts to solve the gain control problem illustrate the ongoing difficulties. For their 1927/28 receivers using filament-type '26 amplifier valves, Atwater Kent used an aerial attenuator. In 1929, they were one of the first to use the new '24 tetrode and settled for a screen voltage gain control in their TRF receivers. This receiver series went rapidly through several developments, culminating in the impressive type L chassis, used in the 1930 model 70, incorporating a dual volume control controlling both aerial and screen

grids. Although an improvement, this method was abandoned for the first A-K superhets. For these, a standard volume control potentiometer was connected between the mixer and the 125kHz IF stage!

It can be said that there was no really satisfactory method of controlling the overall gain of receivers fitted with sharp-cutoff screen grid valves, without creating undesirable side effects.

The problem therefore with the tetrode was that control by grid bias variation certainly reduced stage gain, but in the process crippled its signal handling ability. In one example given at the time, with the transconductance reduced to 10 micromhos, a '24 could deliver only about 0.3 volt of signal without serious distortion.

An ongoing problem

Distortion products from amplification of RF signals have several serious effects, and the problem is not confined to valve receivers. Three of the problems are: modulation rise, cross modulation, and intermodulation — all effects noted in the solid state receivers in Tom Moffat's tale.

Modulation rise is, as its name indicates, an apparent increase in modulation percentage. With signals that have already high levels of modulation, the result is serious audio distortion of the detected signal.

In a crowded band, several signals may be present within the passband of the input circuits of a receiver, but if the amplifying stages are completely distortionless the unwanted signals will be filtered out without any ill effects. However, where there is non-linear amplification, a strong adjacent signal may have damaging effects before being eliminated, and no amount of subsequent selectivity will rectify matters.

By interacting with the wanted signal, the modulation of the unwanted transmission appears in the background of the desired signal. This is cross modulation. Intermodulation is a bit more subtle, and occurs when two transmissions beat together to create spurious signals, and whistles.

Wanted: variable gain

So the situation was that low-mu general purpose triodes could handle strong signals fairly well, but had limitations as RF amplifiers. On the other hand high-mu tetrodes were good RF amplifiers, but could not cope with a wide range of signals.

Basic valve design is simple enough: a fine winding pitch for the control grid provides a high amplification factor or mu, and a coarse pitch a low mu. What was needed therefore was a valve with an adjustable amplification factor — high for weak signals and low for strong transmissions. But how can the effective grid winding pitch be altered in an operational valve?


Like so many good ideas, the solution — although not immediately obvious — was in retrospect quite simple. In November 1930, Stuart Ballantine and H.A. Snow of the Boonton Research Corporation presented a paper to the Institute of Radio Engineers in which they described a *variable-mu* tetrode. What they had done was to take a standard '24 valve and fit it with a control grid having a winding which varied in pitch over its length.


At small values of bias, the entire grid was in control and the valve behaved like a standard screen grid valve. As the grid bias was increased, the electron stream was progressively cut off by the fine pitch portions of the grid; but it required a bias of the order of -30V before the anode current was reduced to something less than 1mA. At this stage only the coarse section of the grid was in operation, and the valve now had the characteristics and signal handling ability of a low amplification factor type. Under high bias conditions, the new valve could handle a signal some 30 times stronger than the '24.

Worked well

The variable-mu grid worked well, and in one stroke the various problems of RF amplifiers using sharp cutoff valves were solved. Indeed, it was so successful that the variable-mu valve rapidly became standard for conventional valve-equipped AM receivers thereafter.

Several major manufacturers produced the variable-mu valve immediately, and exhibited examples early in 1931 at the Chicago Radio Trade Show. For some unexplained reason, two type numbers were selected. One, the '51, was made by Arcturus as type 551 and by DeForest as the 451.





These graphs of the characteristics of the variable-mu 6BA6 (right) and the equivalent sharp-cutoff 6AU6 (above) show clearly how the grid bias needed to cut off a variable-mu type is much greater. Here it is around -20V compared with -3V.

The other type was the '35. RCA made the 235, but with the Cunningham label it became the 335. National Carbon (Eveready/Raytheon) and Sylvania both called their versions type 235. To have several names for the one device was confusing, and within a short time the variable-mu tetrode was listed by most makers as the 35/51.

Receiver manufacturers were quick to make good use of the new valve, and were able to take advantage of its features by incorporating in receivers such refinements as effective automatic gain systems.

Technical progress was rapid during this period, and the RF tetrode's days were numbered. Britain's Cossor had produced an RF pentode, the MS/PenA in 1930, and in the US at the beginning of 1932 the type '39 pentode was released. This was the first American RF pentode and was significantly a variable-mu type. (A very similar valve, the '44, was an alternative offered by some makers and the two types were later combined as the 39/44.)

Popular pentodes

Later in 1932, there appeared a pair of RF pentodes which will be familiar to many collectors as a mainstay of the infant Australian radio industry. These were the sharp-cutoff 57 and its variable-mu partner, the 58. Eventually, given an octal base and 6.3V filament, the 58 became the 6U7G — for many years virtually the standard Australian RF pentode.

It became regular practice to develop sharp-cutoff and variable-mu pentodes as complimentary pairs, and some of the more common examples are listed in Table 1.

Although a feature normally restricted to multi-grid valves, there were triodes intended for VHF RF amplifier service with variable-mu characteristics. One, used by Philips in TV tuners and known in Europe as the ECC189 and in the US as the 6ES8, was a twin triode intended as an AGC controlled cathode coupled 'cascode' low noise amplifier.

With an impressive transconductance of 12.5mA/volt, the ECC189/6ES8 needed a bias control range of about 10 volts. According to the RCA tube manual, it could be biased back to only 125 micromhos conductance, and still cope with a 0.5V signal with negligible distortion.

Although not primarily intended for HF and MF service, this valve proved to be a very successful 'front end' for the Eddystone 940 receiver described in this column for November 1993. Tested alongside an expensive 'state of the art' solid state receiver, the 940 exhibits a similar interference immunity to that of the GEC receiver observed by Tom Moffat. Significantly, unlike modern solid state communication receivers, the Eddystone and its kind have no need for an aerial attenuator — made obsolete by the variable-mu valve 65 years ago!

About valve life


One frequently expressed concern about older type equipment is that of valve mortality. Although valve life is finite, it can be much greater than is generally realised. For non-commercial service, exact figures are hard are hard to come by, but recently I was able to get an indication.

In 1992, I set up a 'MATE' mini transmitter to relay my favourite FM transmission 24 hours a day. With the exception of a couple of holiday breaks, operation has been continuous, and after 3-1/2 years total service, the 12AU7 and 6AV6 valves were tested. In both cases, mutual conductance had dropped to about 2/3 of the new figure and performance was still quite adequate.

This service works out at 30,000 hours, or more than 10 years at eight hours a day. Admittedly, the MATE valves are conservatively run and there can be failures from causes other than wearing out; but the conclusion is that there needs to be no concern about using valve equipment for protracted periods. ❖

Valve Audio

Valves sockets parts audio books. Repairs upgrades & custom construction of valve audio gear. Send $1 stamp for illustrated audio catalogue.



Vintage Wireless Radio Co.

239 Australia St Newtown 2042
P/O Box 467 Newtown 2042
Ph 02 557 2212 Fax 02 516 3981

READER INFO NO. 13

AZTRONICS P/L

END FINANCIAL YEAR CLEARANCE SALE
GENERAL COMPONENTS 20% OFF

BOXES		
Jiffy Boxes Black 2/price one		
HO480 Boxes Altronics		$9 ea
CABLE & LEADS		
2 metre 10A/240V Appliance lead		$3 ea
Computer Leads stocked		$10 ea
W2122 R/BK Fig8 24/.2		$70/200m
Auto Cable 26/.3		$13/100m
CAPS		
Monos Z5U 47 nF 20% 63V		$5/100
G'caps 630v.0010µ		$4/100
CAN/ELECTRO 1500 UF/40V		$3/10
68nf 20% 250V		$3/10
330nf 10% 250V		$3/10
DIODES		
IN 4148	$4/100	$3/1000
IN 4007	$4/100	$30/1000
CONNECTORS		
DB25F Solder		$4/10
4xRCA chassis socket	50c ea	$4/10
9V Battery snaps		$15/100
2 way pcb Term Blocks		$4/10
C & K TOGGLE SWITCH		
ON-OFF SPDT	$1.50 ea	$100/100
TOOLS		
15% off month June		
T2750 Unicraft S'cutters		$10 ea.

SATO KNOB		
Plastic Round Numb 0-9		$3/10
KITS - ALTRONIC		
10% off month June		
M/METER - ALTRONICS Q1075		$89 ea
RELAY - NATIONAL		
NB1-L2-DC24V		$1 ea
RESIST COMPONENTS		
1/4w 5% CARBON		$8/1000
1/4w 1% m/film		$16/1000
IW Carbon 220R		$2/100
PRO 2-220R		$2/100
PRO 3-22K 5%		$2/100
PW5-2K7	$1/10	$6/100
PW10-10K	$2/10	$14/100
TRIMMER BOURNES 3006P-100K	50c ea	RAIL 25/$5
RBLL 1/50V		$7/100
ROTARY POT 500K		$20/100
JAPAN SLIDER POT B 500K		$3/10
SEMI'S		
TCA 280A	$3ea	$20/10 $100/100
BT 151 - 800R		$2ea
V - RIGS - 7905,7805,7812,7824		$6/10, $50/100

ADELAIDE 5000
170 Sturt Street
Ph: (08) 212 6212 Fax: (08) 212 4212
Cash/Trade/Wholesale

Monday - Friday
8.30am - 5.00pm

ENFIELD 5085
4/445 Main North Road
Ph. (08) 349 6340 Fax: (08) 349 5130
Cash/Trade

BANKCARD, VISA & MASTERCARD WELCOME

READER INFO NO. 14

MARKETPLACE



FOR SALE

INVERTERS, UPS: Used UPS's and inverters for computers and solar houses from $200. Also ex computer power boards approx. 500cm². $45 (03) 9598 5775.

UNUSUAL BOOKS: Electronic Devices,Fireworks, Locksmithing, Radar Invisibility, Surveillance, Self-Protection, Unusual Chemistry and More. For a complete catalogue , send 95cents in stamps to: VECTOR PRESS, Dept E, PO Box 434 Brighton SA 5048.

68HC705 Development System: Oztechnics, PO Box 38, Illawong NSW 2234, Phone (02) 541 0310, Fax (02) 541 0734 Email: info@oztechnics.com.au. WWW:http://www.hutch.com.au./~oztech/index.htm

A real bargain: Riston type copper clad laminate. Develop cold, no toxic fumes, easy to use. Excellent results. Single sided 610 x 304 $35; 305 x 304 $17.50; 152 x 305 $9.95; 152 x 152 $6.50. 2 litre developer mix, worth $2.50, free for this month. Add sales tax where applicable. Delivery $6.00. Money back guarantee. Ph 02 743 9235. FAX:02 644 2862.

Educational Electronic Kits: Best prices.Easy to build. Full details. Latest technology. LESSON PLANS FOR TEACHERS--See our web page.Send $2 stamp for catalogue and price list to:DIY Electronics,22 McGregor St, Numurkah, VIC, 3636. Ph/FAX 058 621915. Or Email laurie c@cnl.com.au and let us send details. Go WWW: http://www.cnl.com.au/~laurie.c or BBS 058 623303.Down load details free anytime .

Satellite Dishes: International reception of Intelsat, Panamsat, Gorizont, Rimsat. Warehouse sale – 4.6m Dish & pole $1499, LNB $50, feed $75. All accessories available. Videosat, 2/28 Salisbury Rd. Hornsby. (02) 482 3100 8.30-5.00 M-F.

Universal Battery Eliminator: Power supply for A, B and C, voltages suitable for operating a wide range of battery receivers from the 1920s to the 1950s. For information and specifications send SAE to Phoenix Radio P.O. Box 140 Milang SA 5256. Ph: (085) 370 397.

Oscilloscope Specials
HP 1725A 275MHZ $1000.00
TEK 7704A 200MHZ from $900.00
TEK 7904 500MHZ from $1000.00
plus many more popular brands
Electronic Surplus Store
26 Cardigan St Carlton 3053 VIC.
Tel(03) 9663-6607
Fax(03) 9663 5468

ADVERTISING RATES FOR THIS PAGE

SMALL ADS:
The minimum acceptable size of two centimetres x one column costs only $70. Other sizes up to a maximum of 10 centimetres are rated at $40 per centimetre.

CLASSIFIEDS:
$6 for 40 letters. Just count the letters, divide by 40, and multiply by $6.
ROUND UP TO THE NEAREST MULTIPLE OF $6
MINIMUM CHARGE $12.

CLOSING DATE:
Ads may be accepted up to the 10th of the month, two months prior to issue date.

PAYMENT:
Payment must be in advance by cheque, money order or credit card, include your name, address, and credit card details. Faxes accepted. Payment should be sent with your advertisement, to:

THE ADVERTISING
PRODUCTION MANAGER
ELECTRONICS AUSTRALIA,
P.O. BOX 199,
ALEXANDRIA,
NSW 2015
PHONE (02) 353 0740 • FAX (02) 353 0997

Amidon Ferromagnetic Cores: For all RF applications. Send business size SASE for data/price to RJ&US Imports, Box 431, Kiama NSW 2533. Agencies at Geoff Wood Electronics, Sydney; Webb Electronics, Albury; Assoc TV Service, Hobart; Truscotts Electronic World, Melbourne and Mildura; Alpha Tango Products, Perth; Haven Electronics, Nowra: WIA Equipment Supplies, Adelaide.

C Compilers: Dunfield compilers are now even better value. Everything you need to develop C and ASM software for 68HC08, 6809, 68HC11, 68HC16, 8051/52, 8080/85, 8086 or 8096: $140.00 each. Macro Cross Assemblers for these CPUs. All compilers, XASMs and monitors: $400. 8051/52 or 80C320 Simulator (fast): $70. Demo Disk: Free. All prices +$5 p&p. GRANTRONICS Pty Ltd, PO Box 275, Wentworthville. 2145. Ph/ Fax (02) 631 1236.

Dontronics:
has the world's first PIC Basic Compiler. This is also compatible with the Stamp-1 and makes PIC programming available to everyone with its 'School Boy' instruction set. Designed for the 84's EEPROM, it's easily adapted to others as Assembly and Binary code is generated. $135 plus $5 P&P. VISA-MC-BC. Ask for free Promo Disk. 29 Ellesmere Cres Tullamarine 3043 (03) 9338 6286 Fax (03) 9338 2935.
http://www.labyrinth.net,au/~donmck

TORTECH PTY LTD
TOROIDAL TRANSFORMERS
Design and Manufacture
Approved to AS3108 - 1990 & U.L. Standards
Tel: (02) 642 6003 **Fax: (02) 642 6127**

R.C.S. RADIO PTY. LTD.
Established in 1933, RCS Radio is the only company which manufactures and sells every PCB and front panel published in Electronics Australia and ETI/SC.
651 Forest Road, Bexley, NSW 2207
Ring (02) 587 3491 for instant prices.





FOR SALE

Classic Radio & Electronics: Repair or restoration of any valve based electronic equipment. Radios, Hi Fi Audio Amps, professional service at very moderate rates. Phone Brisbane (07) 3862 8081 Anytime.

Mobile phone batteries.
Competitive Importer direct prices. 12 month warranty.Top quality cells Panasonic, Sanyo & Toshiba. Nicads & Nickel metal hydride.

Nokia	$ 38	Motorola	$ 38
Audiovox	$ 35	NEC	$ 38
Ericsson	$ 38	Novatel	$ 38
Nokia 2110i Vibrator			$ 99

Most Others. $ 38
Credit Card Orders 1-3 day Express Post Delivery.
ph 09 349 9413 fax 09 344 5905

KIT REPAIRS - R & D, prototyping, repairs to electronic equipment, all kits repaired
CAMPAD ELECTRONICS
26 KEITH STREET CAPALABA, Q. 4157
Phone (07) 3245 2008

Printed Circuit Board Manufacture
48-Hour service • High quality • Low prices
1 offs to any quantity
Artwork designed if required
Call for obligation free quote...
INSTANT PCB'S PO BOX 448 AVALON 2107

ELECTRONIC DESIGN-MANUFACTURE
Complete Electronic Design to Production Service
PCB Assembly and Product Asesembly.
Prototypping, PCB Design
Redesign/Modify Existing Equipment.
Service to Electronic Equipment.
ELECTRONIC FORMATION SERVICES
PO BOX 1407, WEST MELTON, VIC 3337
PH/FAX (03) 9747 0800

PCB Prototype Service
Tooling from Disk. $30 + Tax.
- Double sided
- Solder resist
- 8 thou. min. track
- Component legend
- Through hole plate
- 8 thou. min. clearance
- Unlimited hole sizes
- Odd shapes possible

Forget Bread Boarding!
CAD S/W and Info. Kits Available.
Don Alan Pty Ltd
ACN 072 641 564
107A Burbridge Rd
Hilton SA 5033 Australia
Ph. (08) 433957 Fax. (08) 2345339

$159 Tiny 2/3 Matchbox Size Video Camera Modules. Over 30 types from 32x32x15mm Low Light & IR Sensitive. IR LEDs 50mW fr 50c. UNIQUE Vid/Audio TV MODULATOR/ MIXER/ANT AMPLIFIER plug in series with coax. Display/Record on TV/VCR $30.
SENSITIVE 0.05 lux Cameras $299. Also large range of CCTV equip, ask for our C.C.V.E. Info & Price List.
ph 09 349 9413 fax 09 344 5905

CLEARANCE SALE
Be Quick! Limited Quantities
* **New Items**
Miniscan X-Ray bomb inspection System for letters & parcels Manufactured in USA by G.E.& E.

Astrophysics research Aug 1994		$5000
Motors 18-30 VDC 2/3 HP		$50
Infra-red 50mW Leds	pkt 30	$15
40 Watt 12-230 vac Inverters		$40
Cordless Stereo Headphones		$30
Video intercom 2 wire		$400
Japanese Sharp VHF modulators		$10
HP Chart Paper, Rolls & Ink		
Satellite receiver 120ch NTSC-PAL on-screen display R/C H/V Sw		$300

* **Used Items**

Video Cameras B&W & Colour	$20
Camcorders Vid8 VHSC BETA	$200
YEW X-Y Plotter	$200
OHP Data Panel IBM Comp	$400
16 Camera Computer Surveillance Alarm Access System with 640 movement zones/camera.	$500

Also Transformers, Lenses, Panel Meters, 16mm Projectors, Splicers plus lots more. Ask for our list.
ph 09 349 9413 fax 09 344 5905

Tektronix 7904 oscilloscope $1500
Tektronix 7603 oscilloscope $700
Plus a wide range of plug-ins
H.P. 1725A oscilloscope $1200
H.P. 1740A oscilloscope $900
Plus many more popular brands
ELECTRONIC SURPLUS STORE
26 Cardigan St, Carlton. 3053
Ph: (03) 9663 6607 Fax: (03) 9663 5468

FREE DESIGN SOFTWARE
Schematics & PCB - **WinBoard/WinDraft*
Circuit Sumulation - *ICAP/4 Evaluation*

Dowload from *EA Bulletin Board OR http://www.midcoast.com.au/bus/me
ME Technologies
PO Box 50
Dyers Crossing
NSW 2429
Ph: 065 502200
Fax: 065 502341

HAM LOG v.3.1: Acclaimed internationally as the best IBM logging program for Amateurs & CB. Reviews.A.R.:"Recommend it to anyone", The Canadian Amateur: "Beyond this reviewer's abillity to do it justice. I cannot find anything to improve on. A breakthrough of computer technology." A.R.A.: "Brilliant". Simple to use with full help, 90 page manual, the professional HAM LOG is immensely popular (now in its 5th year). Many useful, superb features. JUST $59 (+$5 P&P). Demos, brochures available. Robin Gandevia VK2VN (02) 369 2008 BH Fax (02) 369 3069.

2SJ162 & 25K1058 FET's: also Toroid transformers to suit EA PRO-Series Amps. FETS $5 ea. (03) 9704 2960

WANTED

Circuit diagram for Jupiter MFB Model CSM-40 Audio Amp. Phone (08) 8948 0685

SKIN & CANCER FOUNDATION AUSTRALIA

50 and 25 years ago...

'Electronics Australia' is one of the longest running technical publications in the world. We started as 'Wireless Weekly' in August 1922 and became 'Radio and Hobbies in Australia' in April 1939. The title was changed to 'Radio, Television and Hobbies' in February 1955 and finally, to 'Electronics Australia' in April 1965. Here we feature some items from past issues.

June 1946

Machine that thinks: United Kingdom scientists are hoping to produce what will be the most wonderful calculator in the world, a machine that can 'think'. Experiments are now being carried out by the newly formed Mathematics Division of the United Kingdom Department of Scientific and Industrial Research. If the experiments are successful — and Mr Wormsley, the Superintendent, is confident that they will be — the machine will not only be able to add, subtract, multiply and divide, but from instructions previously put into it, will be able to decide what it should do in different circumstances without any external help.

British Aid for the Deaf: At a cost of less than a penny an hour for running off batteries, deaf people can now have a new aural aid produced by the British Government as a result of radio research during the war.

The aid is as compact as a cigarette case. It measures three inches by two inches by one inch, and contains three tiny amplifying valves. The cost is £10.

June 1971

Time signal service: Since September 1964, the Australian Post Office has provided a standard frequency and time service using the short-wave station VNG situated at Lyndhurst in Victoria. The equipment now in use was built by PMG engineers and technicians over a period of two years at a cost of nearly $47,000. Similar commercially built equipment would have cost about $300,000. The service continually provides readings of the time, accurate to within 0.1ms. Tone bursts of varying lengths signify the second, the minute,, and the quarter hours. The equipment consists of two systems that function independently, each maintaining a check on the other.

Semiconductor progress: Two US semiconductor companies have announced new manufacturing processes for low cost high speed IC transistors. Fairchild has developed a new bipolar process which it says could be price competitive with MOS devices and still retain the speed of bipolar ICs. RCA has overcome the speed disadvantages of the cheaper MOS devices by using a silicon on sapphire technique.

The new Fairchild structure, called Isoplanar, is essentially a dielectric isolation technique which reduces transistor size by 40%, to give densities comparable with MOS devices.

RCA has developed silicon-gate CMOS devices which switch in less than 1ns and dissipate only a small fraction of the power consumed by bipolar devices. The circuits give nanosecond switching delays when operated at bipolar voltages, eliminating the need for buffers between the two. ❖


EA CROSSWORD

ACROSS

1 Control voltage, etc, to set limits. (8)
5 Relative position or condition. (6)
10 Adjusting device. (7)
11 Having even distribution. (7)
12 Word of phonetic alphabet. (4)
13 Power supply. (5)
14 Sheet. (4)
17 Device for switching AC. (5)
18 Low frequency noise. (6)
21 Information passing through a system. (6)
22 Picture formed on a screen. (5)
26 Part of R.M.S. (4)
27 A memory. (5)
28 Indistinct picture. (4)
31 Group of allied transmitters. (7)
32 Reproduction of radio, etc. (7)
33 Small computer. (6)
34 Listening devices. (8)

DOWN

1 Source of titanium. (6)
2 Small amount of light. (7)
3 Emitter of visible radiation. (4)
4 Location of special microphone. (6)
6 Said of 14 across. (4)
7 Colour and sound of police car? (3-4)
8 Make a substitute system. (8)
9 Discrete amount of energy. (7)
15 Measure of wire. (5)
16 Exothermic device based on fusion. (1-4)
19 Contact point in circuit. (8)
20 Sing-along system. (7)
21 Beginning phase of an operation. (5-2)
23 Military action locatable by radar. (7)
24 Physical quantity with unit named after a Frenchman. (6)
25 Performs a soldering process. (6)
29 Non-stereophonic (abbr). (4)
30 Moved at high velocity. (4)



SOLUTION TO APRIL 1996:

	E	L	E	C	T	R	O	C	U	T	I	O	N	
C		O		U	E			U		N		C		
A	L	G	E	B	R	A		S	U	B	Z	E	R	O
B		B		E		D		C		E		Y		U
L	O	O	P		M	E	T	R	E		N	E	O	N
I		O		C		R		O		D		A		T
N	I	K	O	L	A		B	L	O	W	D	R	Y	
G				O		P	A	L		A				R
	P	R	I	N	T	E	R		T	R	I	O	D	E
L		E		E		A		P		F		V		C
O	H	M	S		S	K	I	L	L		Z	E	R	O
C		O		D		E		I		E		R		R
U	N	D	R	I	E	D		E	N	C	O	D	E	D
S		E		S				R		H		U		S
	E	L	E	C	T	R	O	S	C	O	P	E	S	

Electronics Australia's


Professional Electronics

S ◆ U ◆ P ◆ P ◆ L ◆ E ◆ M ◆ E ◆ N ◆ T

QUALITY SEMICONDUCTOR'S UPGRADED & 'REINVIGORATED' HOMEBUSH CHIP FOUNDRY IS OFFICIALLY REOPENED

REVIEW OF DRAGONDICTATE FOR WINDOWS VERSION 2.0: TALK TO YOUR PC IN ALMOST NORMAL CONTINUOUS SPEECH!

FEATURE ON THE LATEST TEST AND MEASUREMENT PRODUCTS



LATEST ADDITION TO THE GROWING LIST OF HEWLETT-PACKARD MIDRANGE SCOPES: THE HP 54616B — OFFERING SAMPLING TO 2GS/s, A BANDWIDTH OF 500MHz, SELECTABLE 1MΩ/50Ω INPUT IMPEDANCE AND SWEEP SPEEDS UP TO 1ns/DIV — PLUS *FAST* SCREEN UPDATE, ANALOG 'LOOK & FEEL'...

NEWS HIGHLIGHTS

FORMAL OPENING FOR UPGRADED CHIP FOUNDRY

Australia's most advanced silicon chip manufacturing facility, the former AWA Microelectronics plant in Homebush NSW, has been formally re-opened following its recent upgrading by new owner Quality Semiconductor Australia. QSA is a wholly owned subsidiary of Quality Semiconductor Inc. (QSI), of Santa Clara in California.

The AWAM facility was purchased by QSA from AWA in February, for around US$13 million. QSI is a small but very innovative Silicon Valley semiconductor maker, which previously had no wafer fab facilities of its own. Founded in January 1989 by Mr Chun P. Chui, a co-founder of Integrated Device Technology (IDT) and pioneer of CMOS technology, and Dr Manohar L. Malwah, formerly head of technology development at IDT, the company went public in November 1994. It currently employs more than 150 people at its 50,000 square foot facility in Santa Clara, and has an annual turnover of around US$50 million.

Present at the recent opening were QSA's Chairman Mr Paul Gupta (President and CEO of QSI) and directors Chun Chui and John Dougall (MD of AWA), along with local MP Paul Zammit. Mr Gupta and Mr Zammit jointly cut the ceremonial ribbon. Also present as guests were former AWA Chief Scientist and director Professor Lou Davies, previous AWAM general managers Professor Graham Rigby and Dr Bob McCluskey, QSI Director of Business Development Jake Foraker, QSA General Manager Phil Cavanagh and most of the Homebush plant staff, including Process Engineering Manager Vladimir Svoboda — who supervised the initial design and commissioning of the plant when it was built in 1988.

Since its purchase by QSA, the Homebush facility has been provided with upgraded fabrication plant, design and manufacturing control systems worth approximately $11 million — including a Lam Research 'Rainbow' Oxide Polyetcher. This is part of a plan, now well advanced, to achieve CMOS fab technology down to the 0.6 micron feature size by the end of 1996. As the plant was at the 1.2um level late last year, this is a formidable task — one that has traditionally taken as long as three years. However as QSI's Jake Foraker said at the QSA opening ceremony, his company has been most impressed by the high level of engineering expertise and dedication displayed by the staff of the Homebush plant, and from the results achieved so far it has every confidence that the 0.6um goal will be reached.

As well as being upgraded, the QSA plant is also likely to be expanded with the addition of a complete second fab line. Around 50% of the plant's output will be dedicated to supplying QSI's requirements, with the remainder available to its existing customers and export business. The plant is currently operating 24 hours per day and seven days a week.

In his speech at the opening, QSA Chairman Paul Gupta said that the Homebush plant was an integral part of QSI's plan to establish itself as a leader in the market areas of high performance logic and specialty memory semiconductors. He added that although it was the company's first foundry, QSI saw it as much more than a low cost in-house fab; the aim was to make use of its human and equipment resources fully, as a foothold in the important and growing Australian and South Pacific markets.





Above (L to R): MP Paul Zammit, QSA Chairman Paul Gupta and QSI Chairman Chun Chou cutting the ribbon to officially open the upgraded Homebush facility. Below shows Mr Gupta speaking at the opening ceremony.

Mr Gupta added that the potential rewards of the strategic alliance between QSI and QSA were great, but that because of the increasing competition and accelerating pace of product life in the global semiconductor industry, it would involve a lot of hard work for all concerned. However he noted that the synergy between Santa Clara and Homebush was already well established, with the local facility now fully involved in the design and development of new products as well as wafer fabrication.

MARCONI MOON BOUNCE AT UNI OF CANBERRA

The University of Canberra's Advanced Telecommunications Research Centre has celebrated the Centenary of the invention of radio and the anniversary of the first trans-Atlantic radio transmission by Guglielmo Marconi (in 1901) with the opening of the Joint DCA/University of Canberra/Satellite Communications Facility, and commemorative EME (Earth-Moon-Earth) radio contacts using the facility's Scientific Atlanta fast tracking 10m diameter F/0.4 dish, with wideband prime focus feeds.

At the facility opening Centre Director Professor Edwards pointed out that it was just 100 years since Marconi had first demonstrated the concept and importance of an antenna in radiocommunication over distances of a few kilometres, and that antennas like the 10m dish were now used routinely in aperture synthesis arrays such as the Australia Telescope, to identify radio sources at distances of tens of billions of light years. It was therefore particularly appropriate to have in the audience Professor 'Chris' Christiansen, the pioneer of the earth rotation aperture synthesis technique used in radio astronomy.



Dr Wayne Pallit and Dr William Cheung at the Centre's 10m F/0.4 fast tracking dish, used for the EME contacts.

The opening of the facility by UC Vice Chancellor Don Aitkin marked the beginning of 'Marconi Week', officially launched at the opening ceremony by His Excellency the Ambassador of Italy Dr Spatafora. Marconi Week culminated in a successful EME communications experiment on IREE 'Marconi Day', December 12, on which worldwide radio contacts were made from the 10m dish of the Joint DCA/UC facility using the moon as a passive reflector.

The Marconi Centennial Station operated at a frequency of 432MHz with linear polarisation, an antenna gain of 27dB, a system temperature of 160K, and a maximum effective isotropic power of 400,000 watts. Strong signals were received in Europe, Asia, North America and Australia, and 11 two-way Morse code contacts were made on the day. A highlight was an unexpected high quality voice contact with a station in Germany. Another was the reception (with the 2.6 second delay expected for the 780,000km round trip) of the historic letter 'S', transmitted with low power (100W) from the 10m dish by Faculty and senior engineering students at the University of Canberra, while setting up the system.

Annual Marconi Moon Bounce and related communications events are being planned to coincide with 1996 IREE Marconi Day, leading up to the Centenary of the trans-Atlantic transmission in 2001.

'ELECTRONICS AT WORK' EXPO IS EXPANDED

The 1996 'Electronics At Work' Expo, which will debut this month (June 5 and 6) at the Sydney Olympics site in Homebush, is being promoted as a 'four in one' event, due to support from industry bodies such as the Spectrum Management Agency (SMA), the Australian Electronics Development Centre (AEDC) and the Australian Electrical and Electronic Manufacturers Association (AEEMA). The Expo is planned to be the Pacific Rim's most comprehensive event for the electronics industry, according to David Kyle, managing director of promoter Practical Marketing.

The event encompasses an exhibition and seminar program dedicated to electronics products and services, and is being staged in conjunction with an international workshop and conference program on electromagnetic compatibility organised by the AEDC and SMA, responsible for implementing the EMC framework. The EMC conference is being held at the Gazebo Hotel in Parramatta, and will include a presentation by Don White, a world authority on EMC and author of 13 books on the subject. Dr Ken Joyner, the head of the EMC section at Telstra Research Laboratories, will be co-presenting with Mike Flood of the Therapeutic Goods Administration on mobile phone interference with medical devices.

Further information is available from Practical Marketing on (02) 9958 1811 or fax (02) 9958 2579.

WORLD'S LONGEST RADIO RELAY LINK

Russia's President Boris Yeltsin recently put the world's longest radio relay link into service, in Moscow. Constructed by consortium partners Siemens and NEC in a record time of only 18 months, the 7600km link runs from Moscow to Chabarovsk.

Siemens constructed the western half, from Moscow to Novosibirsk, while NEC contructed the remainder.

The radio link forms the most important terrestrial East-West long distance telecommunications channel in Russia.

It links western Europe via Russia to Japan and Korea, and operates at transmission speeds reaching 155Mb/s, to permit simultaneous use of up to 12,600 connections. The Siemens portion of the link contract was valued at A$146 million.

Following the commissioning of the link, Siemens was awarded a further order worth A$27.7 million by Russian long-haul carrier Rostelekom, for link extensions.

Siemens has been involved in building Russian telecommunications links since 1852, five years after the company was founded.

WORLD RADIOSPORT TEAM CHAMPIONSHIPS

Contests to see who can log the largest number of radio contacts in a given time are a popular feature of amateur radio around the world. Since 1990 the World Radiosport Team Championships has served as a kind of 'Olympic Games' to bring together the top operators from around the world, to compete on a 'level playing field'. WRTC-90 was held in Seattle, but Australia did not qualify.

WTRC-96 is planned as a much larger event, with 52 two-person teams from approximately 30 countries competing. The USA has 10 teams, Japan four, Germany three, Spain two, Poland two, Canada two and one team each from the remaining countries — including, this time, Australia. The local team consists of Martin Luther VK5GN, selected for his SSB success, and David Pilley VK2AYD for his CW results.

WRTC-96 has been organised and administered by an international committee and is being hosted by the PVRC and the Northern California DX Club in San Francisco, on July 10-15. The teams will operate matched stations in the 1996 IARU HF World Championship contest, to determine 'the best of the best'.

Sponsors of WRTC-96 include Icom, Yaesu, the Shell Oil Company, *CQ Magazine*, Ham Radio Outlet and the Northern California DX Foundation.

OPTUS USING S-A 'MM CABLE TAPS'

Optus Vision is using new Multimedia Taps from Scientific-Atlanta to provide telephony and other interactive services over its broadband cable networks. To date, orders for almost 300,000 multimedia taps and power distribution units (PDUs) have been placed.

Taps are devices which split a signal from street cables and provide services into individual homes. PDUs allow power for telephony and interactive services to be supplied along with signals on a coax cable.

Optus Vision is the first local service provider to install Scientific-Atlanta's new Multimedia Taps. Full-scale production of these units recently began at a custom-built assembly line in Taiwan. Optus Vision has also ordered twisted-pair PDUs, which pass signals and power along composite drop cable. This cable consists of two parts: a coax cable for video, data and telephony signals, plus a twisted-pair wire for carrying power. Scientific-Atlanta's PDU is also available in a version that supports power down the coax drop.

According to Steve Dean, Managing Director for Scientific-Atlanta in Australia, Optus Vision is one of the first service providers in the world to deploy this technology in a full-scale commercial application. "The arrival of cable pay-TV has revolutionised the local telecommunications industry", said Mr Dean. "We believe that within two years, multimedia functionality is likely to be the minimum standard worldwide for service providers. Optus Vision's committment to multimedia technology surpasses traditional network design and helps to put Australia at the cutting edge of telecommunications."

SYDNEY PLANT FOR US SUPPLY FIRM

US based cable television and telecommunications power supply manufacturer Alpha Technologies has opened a new facility in Sydney. The 15,000 square foot facility houses manufacturing and final assembly operations as well as sales offices and a complete customer service centre, and began operating in January.

"Obviously there's a lot of activity in Australia, and the move made strategic sense for both the company and its customers", said Alpha spokesperson Eric Wentz. "This new facility will allow Alpha to fully support the important customer base in the region as well as better serve a growing international industry."

The announcement came soon after Alpha signed a US$20 million three-year contract to supply Optus Vision with power supply products.

Alpha Technologies is headquartered in Bellingham, Washington. In addition to the new plant in Australia, the company operates facilities in Canada, the United Kingdom, Germany and Cyprus. The new Australian facility is located at 8 Anella Ave, Unit 6, Castle Hill, NSW 2154; phone (02) 894 7866, or fax (02) 894 0234.

FIRST INMARSAT-3 LAUNCH SUCCESSFUL

The first Inmarsat-3 satellite, the world's most advanced commercial mobile communications spacecraft, has been launched successfully from Cape Canaveral, Florida aboard a Lockheed Martin Atlas IIA. This was the third launch attempt. The first two attempts had to be delayed due to adverse weather conditions.

Inmarsat's third generation, which will eventually comprise five satellites, will expand the availability and usefulness of global mobile satellite communications by making possible lower cost communications services operating with even smaller, more economical mobile and transportable terminals.

PHILIPS OPENS NEW CLEAN ROOM FOR SATELLITE SWITCH ASSEMBLY

A 'Super Clean Room' for the manufacture of highly sophisticated telecommunications satellite switching systems has been commissioned at Philips Electronics' plant at Moorebank, NSW. The room will boost the Satellite Components Facility's manufacturing capability and help ensure it continues to be a critical international supplier of microwave switches for Hughes, the American space and communications company which has built more than 40% of the world's commercial communications satellites.

Chairman and CEO of Philips, Justus Veeneklaas says that the Satellite Components Facility is part of Philips' committment to the Australian Government's Partnership for Development programme, in which the company has undertaken to develop activities designed to enhance Australia's competitive advantage in advanced information and telecommunication technologies to the extent of $713 million over seven years.


Eight years ago, Philips sent a team of top engineers and technicians to the United States, where they were trained by Hughes in building high precision components for the new generation telecommunications satellites. The team returned to Australia and under sub-contract to Hughes, established the manufacturing centre at Moorebank.

Since 1989, Philips has built over 2000 devices for Hughes. Not one has failed.



Assembling satellite switches in the Super Clean Room.

BIG CHIP PLANT FOR EASTERN GERMANY



Germany's Siemens electrical and electronics company has built one of the world's most modern microchip factories in the record time of 16 months at Dresden, capital of the east German federal state of Saxony. 16Mb memory chips are now being manufactured in a dust-free environment covering 25,000 square metres.

Until now better known as a European cultural mecca with its castles and art treasures, Dresden is now earning a reputation as a centre of high technology. The new Siemens plant initially provided jobs for 1000 people, and will eventually employ 1500 as the company invests a total of almost DM3000 million.

Siemens could have placed its new production unit almost anywhere in Europe, but the new federal state's government came up with an enticing offer — more than 250,000 square metres of land on what used to be a Soviet armed forces training area.

Saxony's state Premier Kurt Biedenkopf, an industrial manager for many years in West Germany, is dedicated to giving East Germany a secure future by developing it as a centre of high technology. "With the Siemens microchip factory in Dresden," said Biedenkopf, "we have established an important milestone in that direction". (iN-Press)

US STUDY SAYS MOBILE PHONES SAFE

The Australian Mobile Telecommunications Association has welcomed the release of a recent significant United States report which refutes claims of adverse health effects from the use of mobile phones. The Study, by the Wireless Technology Research Institute (WTRI), indicates that presumed differences in RF radiation exposure do not appear to have an influence on mortality.The study, based on the analysis of the records of 250,000 portable and mobile cellular telephone customers in the US over a three year period (using telephone company billing data), indicated little difference in mortality rates between users of portable cellular telephones and users of mobile, mostly car mounted, phones.

Epidemiology Resources Inc (ERI) conducted the study for the WTRI. ERI investigators used the Social Security Administration's computerised file of US deaths to compare mortality rates of the two groups.

The AMTA claims that the ERA research is yet another major international study indicating that there is no apparent correlation between the use of mobile phones and adverse health effects such as brain cancer. It says that Wireless Technology Research is an independent research group based in Washington DC and organised to address issues of potential public health risks from wireless communications technologies and develop a scientific database upon which public health decisions can be made.

OPTUS CHOOSES RADIO FOR TAS DIGITAL LINK

In what it claims is an Australian first, Optus Communications has installed a $6 million synchronous data hierachy (SDH) microwave link in its Tasmanian telecommunications network. The new digital link allows vast amounts of traffic to be passed between Hobart and Launceston.

The decision to use SDH radio for this major trunk route, rather than fibre-optic cable, was made after assessing the difficulties of ploughing cable across Tasmania's rocky terrain. The technology, said to be the first of its kind in the world, has resulted in a high level of interest from overseas and is proving a showcase for prime contractor Fujitsu Australia.

NEW VEHICLE DETECTION SYSTEM

Philips have acquired the Australian distribution rights for a leading 'non-intrusive' vehicle detection system, the Smartsonic, and are soon to begin local trials and demonstrations.


Most traffic authorities currently use inductive loops in area traffic control systems. But with loop installation and maintenance the surface of the road has to be cut and lanes of traffic closed. The Smartsonic Vehicle Detection System, developed by International Roads Dynamics Inc (IRD) of Canada, is a non-intrusive acoustic vehicle detector which literally 'listens' for the presence of vehicles via an overhead or side mounted sensor. This sensor 'talks' to a controller card, which is compatible with existing traffic controller cabinets. Installation and maintenance are simplified as the road surface never needs to be cut and lanes of traffic do not need to be closed.

IRD has had great success with Smartsonic throughout North America, where it is operating in diverse climatic conditions from Alaska to Florida without a single failure reported. ❖

NEWS BRIEFS

- A two day seminar on ***The Internet and Business*** will be held at the Golden Gate Hotel, Sydney, June 24-25 1996. Enquiries on (02) 9929 5366.
- ***Motorola*** has announced that Phillip Haas, Director of Operations and General Manager of Motorola Cellular, has been appointed to a senior position at Motorola's headquarters in Chicago. He will be replaced by Mr Glenn McCluskey, who is currently based in Chicago.
- ***SMPTE '97*** will be held at the Sydney Convention and Exhibition Centre, Darling Harbour July 1-4 1997. Enquiries on (02) 9977 0888.
- ***TDK*** has announced several changes to its management. Mr Ted Shibazaki has been appointed Managing Director, Mr Dennis O'Sullivan becomes General Manager Sales and Marketing, and Mr Richard Nelson has been promoted to General Manager Finance and Administration.

Solid State Update



KEEPING YOU INFORMED ON THE LATEST DEVELOPMENTS IN SEMICONDUCTOR TECHNOLOGY

AMD claims micro outperforms Pentium 75

Advanced Micro Devices has begun sampling the Am5x86 microprocessor, claimed to outperform a Pentium 75 device. It is also claimed to deliver fifth-generation performance while taking advantage of existing 486 system designs and infrastructure, including motherboards and chipsets.

The device is based on AMD's enhanced Am486 microprocessor and runs at 133MHz. It has a 16KB write-back cache and an integrated floating point unit (FPU). Benchmark tests show the Am5x86 microprocessor provides up to 9% better performance than a Pentium 75-based system.

The processor includes power management and stop clock for reduced power consumption. Chipset and BIOS support for the device is available through AMD's third-part Fusion Partner program.

For further information circle 275 on the reader service coupon or contact Avnet VSI Electronics, Unit C, 6-8 Lyon Park Road, North Ryde, 2113; phone (02) 878 1299.




Digital audio subsystem in an IC

Analog Devices has introduced what it claims as the industry's most functionally complete 16/18-bit stereo digital audio playback subsystem on a single chip. It comprises a variable rate digital interpolation filter, a multibit sigma-delta modulator with dither, a jitter tolerant digital to analog converter, switched-capacitor and continuous-time analog filters, and analog output drive circuitry, all in a 28-lead surface mount package.


Other on-chip features include a stereo attenuator and mute, programmed entirely through an SPI compatible serial control port. Interface to the device is via a serial data input port that accepts 16 or 18-bit audio data in MSB-first, two's complement format. It operates from a single 5V power supply and is packaged in a 28-pin SOIC and SSOP.

For further information circle 277 on the reader service coupon or contact Analog Devices, PO Box 98, West Rosebud 3940; phone (059) 86 7755.



PLDs come in very tiny package

ICT is now producing a range of its programmable logic products in thin super small outline packages (TSSOP). This package style has a footprint about one third the area of an equivalent pin count small outline integrated circuit (SOIC). It also has a low profile, allowing programmable logic to be fitted on small boards such as DRAM SIMM modules.



The TSSOP package has about the same height as most surface mount resistors and capacitors, and can be mounted on the track side of most PCBs. Its low profile meets most PCMCIA height requirements. The company is currently shipping its programmable electrically erasable logic (PEEL) 18CV8 and the 22CV10A in the TSSOP package.

For further information circle 272 on the reader service coupon or contact Reptechnic, 3/36 Bydown Street, Neutral Bay,2089;phone(02)9953 9844

2GHz power transistor

Motorola has announced a new RF power NPN silicon transistor characterised with series equivalent large-signal parameters suitable for PCN base station applications. The MRF6404 device operates at 26V and is designed for microwave large signal, common emitter, class AB linear amplifiers oper-


ating in the range of 1.8 - 2GHz.

The transistor has a minimum gain of 7.5dB, and a minimum efficiency of 38% at an output power of 30W. Specific applications include use in DCS1800 and PCS1900 cellular radio.

For further information circle 273 on the reader service coupon or contact Motorola Australia, 673 Boronia Road, Wantirna 3152; phone (03) 9887 0711.

Op-amp has 1500V/us slew rate

National Semiconductor has introduced three new 5V op-amps with specifications typically found only with 15V devices. The LM6310 has a bandwidth of 90MHz and a slew rate of 350V/us, the LM6311 a BW of 130MHz and a 400V/us slew rate, and the LM6317 features a slew rate of 1500V/us with a BW of 120MHz.




All devices are suited for use in video and imaging equipment, or for driving flash ADC or buffering DACs. The LM6311 and the LM6317 feature low noise and low offset, and the LM6311 is specified for a single 5V supply. The devices are currently available in 8-pin plastic DIP or SOIC packages.

For further information circle 271 on the reader service coupon or contact National Semiconductor (Aust), Business Park Drive, Monash Business Park, Notting Hill, 3168; phone (03) 558 9999.

8MHz BW FET input op-amps

Burr-Brown has released a range of FET input op-amps that feature a bandwidth of 8MHz. Called the OPA132 series, it includes a single package (OPA132), a dual (OPA2132) and a quad package (OPA4132). The series is claimed to be easy to use, and free from phase inversion and the overload problems often found in FET input op-amps.

Key specifications include 500uV offset voltage, 130dB open loop gain, 50pA input bias current, supply voltage of +/-2.5V to +/-18V, 8MHz BW, a slew rate of 20V/us and noise of 8nV/√Hz at



1kHz. The devices come in 8-pin (14-pin for the quad pack) DIP and SO-8 (SO-14) surface mount packages.

For further information circle 274 on the reader service coupon or contact Kenelec, 2 Apollo Court, Blackburn 3130;phone(03)9878 2700.

High voltage switching regulator

Motorola has released the MC33363DW high voltage switching regulator. It contains a 700V, 1A FET power switch as well as a 450V off-line startup FET, a duty cycle controlled oscillator, current limiting comparator with programmable threshold and latching pulse width modulator for double pulse suppression.

Other features include a bandgap reference, cycle-by-cycle current limiting, input under-voltage lockout, over-voltage protection and thermal shutdown. The device is packaged in a 16-pin surface mount pack.

For further information circle 278 on the reader service coupon or contact Veltek Australia, 9 Bastow Place, Mulgrave 3170; phone (03) 9574 9300.

Charger IC for alkaline batteries

Benchmarq has announced the bq2902 rechargeable alkaline charge ICwhich charges two rechargeable alkaline batteries such as Renewal batteries from Rayovac.

The 8-pin IC manages two AAA, AA, C or D size cells, and is designed for use in subnotebook computers, personal digital assistants, cordless telephones, personal audio, flashlights, games and standby power.

The chip manages charge and discharge cycles by monitoring each cell individually to ensure full-charge detection without overcharge, and to extend cycle life by not allowing deep discharges. It uses a current-limited supply to generate the proper charge pulses; a LED status output indicates charge in progress, charge complete and a fault condition.

For further information circle 276 on



the reader service coupon or contact Reptechnic, 3/36 Bydown Street, Neutral Bay, 2089; phone (02) 9953 9844.

Microwave mixers

US-based Miteq has released a range of high isolation microwave double balanced mixers. The devices feature 40dB midband LO-RF and IF-RF isolation, double tuned RF baluns with 5dB typical conversion loss, and IF coverage of DC to 80GHz.

The RF/LO frequencies are between 0.5 and 20GHz with LO power 10-13dBm, and a conversion loss of 5.5 to 6dB. LO/RF isolation is between 35/30 and 40/30dB and IF-RF isolation is between 40/25 and 40/30dB (typical minimums).

For further information circle 279 on the reader service coupon or contact Electronic Development Sales, PO Box 822, Lane Cove 2066; phone (02) 418 6999. ❖

WANTED
SCRAP PCB's
We will pay CASH for your scrap/obsolete PCB's containing soldered/socketted DRAM, EPROMs or CPUs
SURPLUS STOCK
all semicon's considered
Memory International
Voice: (61 2) 452 6100
Fax: (61 2) 452 6102
READER INFO NO. 15

NEW PRODUCTS

Video tape rejuvenator

The RTI TapeChek Pro Line 4100 is a cleaning, evaluating and erasing tape conditioning and rejuvenating system for Betcam SP and Digital Betacam format video cassettes. Claimed to offer significant savings for broadcasters and other professional Betacam users, the system effectively recycles expensive Betacam cassettes.

GTV9 recently installed the system in its Melbourne television facility, to condition and recycle Betacam SP tapes for its news and current affairs requirements. Each tape is processed with the system prior to use, and tapes returned from the field are erased, conditioned and evaluated before being returned to service. This allows contaminated tapes to be discarded, and good tapes to be reused. Operating at 30 times PAL speed, the system cleans, evaluates and rewinds a one-hour cassette in two minutes.



For further information circle 241 on the reader service coupon or contact Amber Technology, Unit B, 5 Skyline Place, Frenchs Forest 2086; phone (02) 9975 1211.

3-phase EMC filter

Schaffner has launched the FN258 series of filters that feature a voltage rating of 480V, meeting the requirements of variable-speed motor drive manufacturers and users around the world.

The family has nine models that cover a current range of 7A to 180A, allowing variable frequency drives to meet EMC regulations. The filter has two-stage circuitry which allows the filter to be located up to 75m from the load, giving increased flexibility. The housing size is 50 x 126 x 255mm for the 7A version, and 110 x 240 x 490mm for the 180A version.



For further information circle 243 on the reader service coupon or contact Westinghouse Industrial Products, Locked Bag 66, South Melbourne 3205; phone (03) 9676 8888.

3-in-1 car antenna

Sirtel has produced a multifunctional antenna that can be used with a mobile phone, CB or a car radio. Called the Unika antenna, it comes with a specially designed triplexer that connects all these devices to the one antenna.

The antenna can be mounted on the roof (front or back) or on the boot. It is made from a soft, shockproof material and has a removable whip with a total height of 40cm.



For further information circle 244 on the reader service coupon or contact Telaware, 7/245 Springvale Road, Glen Waverley 3150; phone (03) 9802 0599.

High capacitance, tiny size caps

A range of micro-miniature axial leaded MLC capacitors has been annouced by AVX. Designated the MCO2 series, it is expected to supplement higher capacitance value tantalum capacitors in many applications requiring miniaturisation.

The series has a 16V X7R dielectric with capacitance values ranging from 1nF to 0.1uF, with 10% or 20% tolerance. The case measures 2.5 x 1.3 x 1mm, making it a drop-in replacement for lower value tantalum devices in the W moulded case size. Leads are solder coated pure nickel wire suitable for either soldering or welding.

The capacitors are especially suited for general filtering, decoupling, bypassing and RC timing applications. Their size makes them particularly suited for use in hearing aids. Pricing is comparable to equivalent size tantalum capacitors.

For further information circle 245 on the reader service coupon or contact Veltek Australia, 9 Bastow Place, Mulgrave 3170; phone (03) 9574 9300.

Miniature power relays

DGE Systems now has available the Omron range of LY and MY miniature power relays, with a withstand voltage of 2000V AC.

The MY series has many types for sequence control and power applications. Variations include one, two, three or four poles, operation indicators, high capacity capability, built-in diodes and an arc barrier on the three and four pole devices.

The LY series has the same features as the MY range, with AgCdO contacts for a longer service life. It is also available with single or birfurcated contacts, push-to-test button and a built-in RC circuit. Both the MY and LY series are available with plug-in/solder or PCB terminals. Mounting sockets are also available.

For further information circle 246 on the reader service coupon or contact


DGE Systems, 103 Broadmeadow Road, Broadmeadow 2292; phone (049) 61 3311.

Optical link for CATV system

Optical Systems Design has announced the release of its Australian designed and manufactured OSD481/OSD483 CATV fibre optic transmitter/receiver pair. It is intended for applications where a number of television signals must be transported over distances up to 20km.The units can be configured either as point to point links, or as a star network with one transmitter feeding several remote receivers via an optical splitter. The system allows a laser of three grades, giving 20, 40 or 60 channels.

The transmitter accepts a combined AM-VSB spectrum signal at about 90 to 100dBuV/channel, with a carrier frequency in the range of 40 to 860MHz. This spectrum can be created by standard CATV/MATV type VSB modulators or channel translators.

The receiver has a wideband PIN photodiode, and outputs the combined FDM spectrum at a level of about 100dBuV/channel.




The devices are packaged as stand-alone, and operate from 120V/240V AC. Applications include multichannel CCTV systems, campus audio/visual reticulation networks, CATV/MATV networks in resorts and other large sites.

For further information circle 247 on the reader service coupon or contact Optical Systems Design, PO Box 891, Mona Vale 2103; phone (02) 9913 8540.

TCXO is tiny

AVX has announced its KT11 range of temperature compensated crystal oscillators (TCXO). Claimed as the smallest in the industry, the devices measure 11 x 9 x 4mm. A key feature is compatibility with reflow solder equipment.




The series offers a frequency range of between 12.8MHz and 19.2MHz, with a tolerance down to 2.0ppm. The supply voltage can be either 3V or 5V. An optional automatic frequency control (AFC) function can be specified which allows the centre frequency to be 'tweaked' with an external voltage.

The devices are suited to digital and analog mobile communications systems, in particular GSM, high specification cordless phones and global positioning systems (GPS).

Audio precision

Digital & Analogue Audio Testing









New System 2

- Comprehensive PC-controlled signal generator and analyser for digital and analogue audio
- True dual domain architecture – separate analogue and digital hardware (no performance limiting converters)
- Complete facilities for measurement to AES3 – jitter, FFT of jitter, pulse amplitude, eye patterns, delay etc
- Simulate real-world degradation, inject variable jitter, vary rise/fall times etc
- Locks to virtually any house signals including PAL video etc
- Residual noise of 1μV, THD+N of -110dB, FFT after notch filter to -140dB
- APWIN software for keyboard macros, printing and plotting interface etc

System 1

- Fast and easy to use – measure and display up to 3 parameters at once
- All procedures under software control
- Digital (AES/EBU), Analogue and FFT audio analysis
- *Fast*Trig DSP network measurements
- ***NEW*AutoChek' – Automatic Alignment & Testing of Professional Video Recorders**


Portable 1+

- Powerful – swept frequency and phase response, 1/3 active spectrum analysis, distortion v. frequency
- True 2-channel (stereo) architecture
- Real time balance, cross-talk, phase, gain/loss, wow/flutter, THD+N, IMD
- Easy to use – single button selections
- Print out of graphs, data and settings


ATS 1

- Economical yet with high performance and easy to use
- GPIB interface
- LabWindows and LabView
- Large bargraph displays with setable end points
- Print out of graphs, data and settings

APWIN® Windows Software for System 1 & 2



- True Windows-based control, manipulating and exporting of data
- Assemble 'virtual test benches' – ideal for automated testing
- Display 5 different pages – panels, bargraphs, X-Y graphs of 6 variables
- Keyboard macro's for writing test procedures
- Windows printing and plotting interface



IRT

IRT Electronics Pty Ltd

26 Hotham Parade, Artarmon, N S W 2064. Tel : (02) 439 3744 Fax : (02) 439 7439
Victoria : 3/395 Nepean Highway, Frankston 3199. Tel : (03) 9770 1965 Fax : (03) 9769 6044

For further information circle 248 on the reader service coupon or contact Veltek Australia, 9 Bastow Place, Mulgrave 3170; phone (03) 9574 9300.

Security clips

South Australian based Monaad Corporation has released an innovative electronic security product known as Smart Clips. These are proximity sensitive devices designed to safeguard against the loss of almost any item.

Sold in pairs, one Smart Clip is worn by the user while the other is attached to the item or valuable to be protected. When the two Clips are separated by around 7-10 metres, an audible alarm will sound to alert the user. The Clips also have a 'paging' facility, allowing them to 'find' one another even when one is concealed from sight.

Manufactured in South Australia by Gerard Industries to ISO-9002 quality standards, Smart Clips are expected to become an important export item.

The technology used in the devices has taken over three years to develop, and is a closely guarded secret. Monaad has also worked in close association with Zenon Car Security to develop an innovative range of car security products.

Retailing for $157, Smart Clips can only be purchased directly from Monaad Corporation by phoning toll free on 1800 069 669. Each pair carries a 14-day money back satisfaction guarantee and a 12-month warranty, and comes in a quality 'snap close' case with easy to use instructions and a variety of attachments.



For further information circle 242 on the reader service card or contact Monaad Corporation on (08) 377 2000.

DIL crystal oscillators

C-MAC Quartz Crystals has introduced the CMT3000 series of DIL-packaged temperature compensated crystal oscillators. The series is designed for use in applications which demand high frequency stability over a wide temperature range with low power, small volume and low cost.


The oscillators are particularly suitable for use in remote telecomms links, hand-held portables or GPS applications where size and portability is important. The series is packaged in a 14-pin DIL package. The enclosure is hermetically sealed by a welding process.

The series covers the frequency range of 2MHz to 50MHz, and requires a 5V 20mA supply, producing either sinewave or HCMOS output.

For further information contact C-MAC Quartz Crystals, Edinburgh Way, Harlow, Essex CM20 2DE England; phone +44 (0) 1279 626 626. ❖

Point-and-click data logging

Simply point and click to set up a data logging schedule using DeLogger, the new Windows™ programming and display software for Datataker.



DeLogger will not only program your logger, but give you real-time trend plots and tables.

Data logging with Datataker really is this simple.

Just connect thermocouples, RTDs, strain gauges, load, flow, level, pressure, meteorological,... in fact, any sensor you like. No add-on cards. No signal conditioning. No complex programming.

Datataker does it all in a stand-alone logger that's compatible with all computers. Notebooks to mainframes.


Datatakers are available with one to hundreds of channels. Alarms, calculations and a full range of statistical functions are standard.

To find out how simple data logging can be, call the data acquisition experts...

DATA ELECTRONICS
Phone (03) 9764 8600
(02) 9971 7994

ACN 006 134 863 AD-038-A0

READER INFO NO. 17



Your Computer is Australia's only computer magazine written for small business and home users.

Our editorial is locally written and is slanted with a 'hands on' approach for those who believe in PCs as a tool to increase business efficiency and productivity. As it says on our cover we've been Helping PC users since 1981.

ON SALE AT YOUR NEWSAGENTS NOW
or phone 1800 800 933

The latest innovation in electronics...

Electronics Australia is Australia's top selling electronics magazine. Why? Because it covers the total bandwidth of electronics information *every month* - from groundbreaking innovations in video and audio to the projects happening in homes just like your own. And now there's another great reason to buy our magazine.

When you subscribe, renew or extend your existing subscription to *Electronics Australia*, you'll receive the next 12 issues delivered to your home or office door for just $49. That's a saving of 25% off the cover price.

As a subscriber to *Electronics Australia* you will:

- Receive your copy *before* it goes on sale at newsstands
- *Save* $17 - a 25% discount off the cover price
- Be guaranteed a copy of *every* issue
- Enjoy the convenience of having each issue delivered FREE to your door
- Be *protected* from any cover price increases for a whole year

To subscribe to *Electronics Australia* phone TOLL FREE 1800 800 933 - Sydney Residents phone (02) 353 9992 - and have your credit card details ready. Alternatively, simply fill in the subscription card attached and send it with your payment (cheque, credit card details or money order) to:

Federal Publishing
Subscriptions Department
Reply Paid No. 3
PO Box 199
Alexandria NSW 2015 (no stamp required)
or fax us on (02) 353 0967.

Any queries about your subscription? Call our customer service line: (02) 353 9992.

25% off the cover price when you subscribe to Electronics Australia

$49

12 ISSUES

HURRY! OFFER ENDS 25TH JUNE, 1996.

ELT/05 3,4,5,6'96

SPOTLIGHT ON SOFTWARE



DragonDictate for Windows V2.0

Dragon Systems, arguably the world leader in speech recognition technology, has recently released version 2.0 of its package DragonDictate for Windows. Available in three editions, which differ mainly in terms of their 'active vocabulary' held in RAM, the new version has improved straight-out-of-the-box recognition performance and also adapts to the user more rapidly.

by JIM ROWE

Ever since computers moved out of their original glass-enclosed ivory towers and onto the desks of we ordinary mortals, there's been a constant request for systems capable of recognising human speech. Mainly, I suppose, because so many people find it either difficult or inconvenient to use a conventional keyboard. (Frankly, I've never found it much of a problem — my thought processes are sufficiently slow that they're easily recorded using a single finger on each hand!)

Despite this potential interest, though, the development of these systems has been relatively slow and tortuous — basically because for a computer, recognising human speech patterns is an exceptionally difficult task. Even reliably recognising the speech of one particular person is hard enough, with all the variations due to emotional state, inflections, etc. — let alone trying to recognise the variations *between* people. When you consider the additional complications due to different ages, genders, accents and dialects, the task becomes truly horrendous.

All of which makes the recent development of PC-based speech recognition systems all the more impressive, I believe. Some people criticised the first generation of these products as slow, and were irritated by their inability to cope with 'normal speech' with its high proportion of joined-together words and phrases. But when you consider the huge amount of crunching needed even to recognise words with small pauses between them, these programs were surely analogous to the classic dog walking upright — they may not have done the job perfectly, but it was a minor miracle that they did it at all!




Although DragonDictate for Windows V2.0 is basically a software package, it comes complete with a high quality Shure noise-cancelling microphone.

Probably the most impressive speech recognition products are those produced by Dragon Systems, a company based in Newton, Massachusetts (USA). Founded in 1982 by Drs James and Janet Baker, two pioneering speech recognition researchers at Carnegie-Mellon University, Dragon has been at the forefront of the technology even since its inception. Both James and Janet Baker also worked at IBM's Thomas J. Watson Research Centre on the Continuous Speech Research project, and James Baker developed the use of stochastic processing and Hidden Markov Models, both regarded as key components of modern speech recognition. Janet Baker contributed an important method of time-domain acoustic processing based on neural phase-locking.

Both Drs Baker are still very active in Dragon Systems, James as its Chairman-/CEO and head of research, and Janet as its President.

In 1990, the company released DragonDictate-30K, the first commercial large-vocabulary (30,000 words) speech recognition system enabling general purpose free-text translation. Then in mid 1994 came a version for Windows. Even in their initial forms



A screen dump showing a correction taking place during a dictation session with DD for Windows and Write. The horizontal window shows the recent word history, while the vertical list provides DD's suggested alternatives for the word that was misrecognised. They appear when you say "Oops!" after noticing the error. Note the 'Voice bar' at lower right, present when DD is in operation.

practical, but they tended to require a fairly long time to adapt to a particular user and their working vocabulary. They also tended to need a significant pause between words, which steepened the 'user learning curve' and limited the dictation speed.

These restrictions have been largely (although not totally) overcome in the latest versions of the programs, which are DragonDictate for DOS V3.0 and DragonDictate for Windows V2.0, which we're reviewing here.

Released in the US late last year, DragonDictate for Windows V2.0 is basically a high-powered software package which runs on a PC running either Windows 3.X or Windows 95, and fitted with a standard Windows compatible 16-bit sound card. However as undistorted and low-noise audio is very important for reliable speech recognition, the package also comes complete with a high quality Shure noise-cancelling headset microphone.

Version 2.0 incorporates a completely new recognition 'engine', which is claimed to greatly boost accuracy and enable natural continuous speech recognition of numbers and commands. Part of the new engine is a feature called QuickTalk, which is described as providing 'semi-connected speech recognition', to allow significantly shorter pauses between words in normal dictation.


In addition, the new engine is said to be the first in a general purpose PC dictation product to allow recognition of truly continuous phrases, such as naturally spoken numbers like "four-hundred-and-fifty-three", or commands like "move-down-three-paragraphs" or "Bring-Up-Write". You can even customise the program by adding further such phrases to its dictionary as you go along.

The new version also uses new speaker-independent models, which are claimed to give a relatively high accuracy 'out of the box' with most users, without a lengthy training session. There is an optional Quick Training feature which can get you off to an even better start, however.

Like the earlier version, it automatically adapts to user speech patterns as you use it, so that the more you do so the faster and more accurate it tends to get. However this relies on you consistently correcting its errors, and saving your 'User File' after each session.

Included in DD for Windows V2.0 is the ability to direct the computer's cursor around the screen and control the mouse buttons entirely by spoken commands like "Mouse-Up" or "Right-Click". However there's now also a feature called MouseGrid, which allows faster mouse navigation by dividing the screen on command into an array of nine sectors, into which the cursor can be directed quickly and simply by specifying the sector's ID number.

WAVETEK



LANTEK PRO Series

Cat.5 Testing

FEATURES	LANTEK PRO XL	LANTEK PRO
AUTOTEST TIME	40seconds	40 seconds
FREQUENCY RANGE	1-100MHz	1-100MHz
DUAL NEXT	Yes	Yes
MAJOR TEST SUITES (REPORTING PASS/ FAIL FOR EACH)	Line Mapping Length DC Loop Capacitance Attenuation Dual NEXT	Line Mapping Length DC Loop Capacitance Attenuation Dual NEXT
ACR	Yes	Yes
CABLE EXPERT	Yes	Yes
CABLE LENGTH	Yes	Yes
TDR (IMPEDANCE VS. LENGTH	Yes	No
AVERAGE NOISE	Yes	No
(FOR EMI, RFI)	Yes	No
TEST STORAGE	500	500
GRAPHICAL DISPLAY	Yes	Yes
FLASH ROM	Yes	Yes
CABLE TYPES SUPPORTED	>200	> 200
BATTERY LIFE	10-12 hours	10-12 hours

NEW: FIBRE OPTIC KIT

Scientific Devices Australia Pty Ltd

SCIENTIFIC DEVICES

MELBOURNE (03) 9579 3622
Fax (03) 9579 0971

SYDNEY (02) 344 5200
Fax (02) 349 2602

ADELAIDE (08) 281 3788
Fax (08) 281 4194

READER INFO NO. 18

Compatible applications

As well as being compatible with both Windows 3.X and Windows 95, DD for Windows V2.0 is also compatible with many existing Windows applications programs — even those that are fairly specialised, according to Dragon Systems. In addition the Company has tested and certified its compatibility with many of the more commonly used applications, including:

- Microsoft Office 4.2 and 4.3: Word 6.0, Excel 5.0, Powerpoint 4.0 and Access 2.0.
- Lotus Smartsuite 3.1: AmiPro 3.1, Lotus 1-2-3 5.0, Approach 3.0, Organiser 2.0 and Freelance 2.1.
- Novell PerfectOffice 3.0: WordPerfect 6.1, QuattroPro 6.0 and Presentations 3.0.
- Microsoft Office 95: Word 7.0, Excel 7.0 and Powerpoint 7.0.
- Windows Applets: Write 3.1, Wordpad 1.0, Calculator, Solitaire, Minesweeper, Calendar and Cardfile.
- Other applications, including Adobe Acrobat Reader 2.0.

In fact DD for Windows 2.0 is said to contain over 4500 predefined speech macros for the three leading office suites, and for numerous Windows Applets. It also has limited compatibility with a wide range of DOS applications, if they're run in a DOS window.

Hardware requirements

As mentioned earlier, DD for Windows 2.0 comes in three editions which differ mainly in terms of the size of the 'active vocabulary' they maintain in RAM while running. In the Personal Edition this vocabulary is of 10,000 words, which expands to 30,000 words for the Classic Edition and 60,000 words for the Power Edition. All three editions maintain a further 'backup wordlist' of 120,000 words on your hard disk.

Needless to say, the differing RAM vocabulary sizes mean that the three editions have different requirements in terms of computer memory. The Personal Edition needs at least 12MB (16MB recommended); while the other two editions need at least 16MB (20MB recommended for the Power Edition). The hard disk space requirements also vary, depending on both the edition and the number of users — from 28MB for the Personal Edition with one user, up to 36MB for the Power Edition (plus 14MB per additional user).

Dragon Systems' Australian distributor Auscript (a division of the Commonwealth Attorney-General's department) recommends the use of a 90MHz Pentium system, with 24MB of RAM when running under Windows 3.11 and 32MB of RAM with Windows 95.

As a suitable microphone is supplied in the DD for Windows 2.0 package, the only other hardware compatibility consideration is the sound card. In general the package seems to be compatibile with most Windows-compatible multimedia sound cards, with Dragon listing the Sound Blaster 16, Value Edition SB16 and Microsoft Windows Sound System (WSS) cards as being 'certified'. The company also certifies the M-ACPA card, which they say gives faster operation because its onboard DSP processor offloads some of the speech recognition work from the CPU.

Trying one out

Thanks to Dragon Systems and Auscript, I was able to try out the Classic Edition of DD for Windows 2.0 for myself. I installed it on a 90MHz Pentium machine with 16MB of RAM, running Windows 3.11.

Although the sample package had only floppy disks to install from (a CD-ROM version is apparently available), the installation went smoothly and without any hassles.


After installation an initial setup box appeared, asking which mike was being used. As it wasn't entirely clear which model of Shure mike we'd been provided with, I clicked on 'Don't Know' — which brought up a Microphone Test Box, and I was led through a sequence to set up the correct settings for the sound card volume settings, etc. This also went quite smoothly.

I noticed that a tutorial program had been installed along with the main program, so I gave this a try. It turned out to provide an easy to follow demo sequence introducing the package and how it's used, with a friendly graphic character called 'Alex the Dragon' guiding us with a combination of images and audio (via the sound card output). At various points you're prompted to try various functions yourself, step by step, to get you going.


Next I tried using DD with Windows Write, to dictate a letter. However at this stage DD seemed to have quite a lot of difficulty recognising much of what I

DGE SYSTEMS PTY LTD
Free Call
1800 818 736
Fax (049) 69 5067

Omron G5V-2 PCB Relay
Minature, high sensitivity, DPDT relay with wide range switching
♣ 150mW sensitivity
♣ 20.5x10x11.5mm
♣ 10μA to 2 Amp
♣ Sealed case
♣ DIP footprint



Omron G6A-2 PCB Relay
Minature, DPDT relay for use in telecommunications equipment
♣ 200mW sensitivity
♣ 20x10x8.5mm
♣ Low magnetic interference
♣ Sealed case
♣ Latch Models



READER INFO NO. 19

NEW! Micro G™ Miniature Controller
Z-WORLD

Z-World's Micro G™ is an extremely compact and powerful minature controller. At 80mm x 50mm it is slightly smaller than a credit card. Its small size, low cost and versatility, make it ideal for a wide range of embedded control applications. The Micro G™ is configured with 14 digital I/O, 1 analog input, RS232 & RS485 comms, real time clock & watchdog. Programming is easy with Z-World's Dynamic C development environment including a powerful editor, compiler, debugger to quickly write your applications. Prices start at $149.00.



Phone NOW for a FREE Catalog & Demo Disc.

Authorised Distributor: Dominion Electronics
Suite 201, 82 Christie Street, St Leonards, NSW 2065
Phone: (02) 9906 6988 Fax: (02) 9906 7145

READER INFO NO. 20

said (including Windows commands), and it was all very frustrating. Perhaps it was my Australian accent and intonation; after all, it's an American program!

Anyway, I decided to defer using it 'in anger' for a while, and instead fired up the optional program Quick Training — a kind of 'fast track' way to get DD more familiar with your speech patterns. Quick Training presents you with four groups of words (Correction Words, Common Commands, Dictation Words and Additional Words), and you have to speak them into the mike as they're displayed on screen. There are potentially over 700 words in all, but as Quick Training constantly adapts to your speech as you proceed, you normally don't need to run through the lot. In fact my training session seemed to involve only about 150 words or so, and took less than 15 minutes.

After saving my User File, so that DD would 'remember' what it had learned so far about my speech patterns, I tried firing up Windows Write again. This time things were a lot smoother. Telling Windows to "BringUpWrite" immediately brought Write into action, and "BeginDocument" changed the message in DD's little VoiceBar icon to indicate that we were now in Dictate mode. I could then begin dictating the letter, including punctuation and formatting commands like "Period", "Dash", "Comma" and "NewParagraph".

DragonDictate still tended to make a few recognition errors, but these were much less frequent than before. As recommended in the manual I also made a point of mastering the correction procedure, so that it would be able to keep adapting and improving.

Whenever you notice that it has made an error, you merely say "Oops!", and it brings up a dialog box showing the last few words it has registered. If the error involves the second last word, you then say "WordTwo", and it offers a list of other possible words for that sound pattern. If the correct interpretation is listed, say third in the list, you only need to say "ChooseThree" and the correct word is substituted in the text.

What if the list doesn't include the correct word? In this case, you simply begin typing it yourself. As each letter is keyed in, DD changes the words listed; often by the time you've type in a couple of letters, the correct word appears in the list and you can choose it.

This all sounds rather involved, and the first few times it certainly slows you down. But after a while things go surprisingly smoothly — partly because DD is getting more and more used to your speech patterns and making fewer errors, and partly because the correction procedure becomes more intuitive and 'automatic'. After dictating a couple of sample letters, I found that the program and I were getting along much more happily and efficiently...

It certainly takes a while to get used to the 'almost, but not quite continuous speech' dictation technique that the program needs, and I can't say I have mastered this fully as yet. However my impression is that achieving this level is entirely feasible, and should result in a very respectable dictation speed.

In short, then, my impression of DragonDictate for Windows V2.0 is that the Classic Edition in particular is a very powerful and practical PC-based speech recognition package, and one that should be suitable for day to day use by a wide range of people.

The quoted RRPs for the package are $699 for the Personal Edition, $1299 for the Classic Edition and $2999 for the Power Edition.

Dragon products are now available in Australia through a network of resellers. For further information, including details of dealers in your area, contact distributor Auscript on (02) 238 6565, or fax (02) 638 6566. ❖

HAMEG

Oscilloscopes


setting new standards



Analog Oscilloscope HM303

- 2 Channel DC-30MHz, sensitivity 1mV - 20V/div.
- Timebase 0.2s-10ns/div., triggering 0-100MHz
- Component Tester, Probe-Calibrator 1kHz/1MHz
- Overscan indicator, switching power supply 90-260V

Includes 2 probes and 2 year warranty.



Analog/Digital Oscilloscope HM305

- 2 Channel DC-30MHz, sensitivity 1mV - 20V/div.
- Timebase 0.2s-10ns/div., triggering 0-100MHz
- Component Tester, Probe-Calibrator 1kHz/1MHz
- Sampling rate 2x40MS/s, memory 2x2048x8bit
- Refresh, single and roll mode, Pre-Trigger 50%

Includes 2 probes and 2 year warranty.

HAMEG® Instruments

Made in Germany

CALL NOW

KENELEC

ESTABLISHED IN 1962

TEL: (03) 9878 2700
FAX: (03) 9878 0824


READER INFO NO. 26

Listed below, everything most Australians know about MS

Special Feature:

The latest test and measuring instruments

DMMs use new chip set



The DMM800 multimeter series recently announced by Tektronix is the company's new flagship family of handheld true-RMS digital multimeters (DMMs). The series is claimed to provide up to twice the accuracy and up to 10 times the resolution of competing handheld DMMs. Measurement functions include voltage, current, resistance, capacitance, frequency and temperature. The range comprises the entry-level DMM830, the mid-range DMM850, and the high-end DMM870.

Features include a dual numeric display (DMM850 and DMM870), which lets you read two measurements at once. For example, amplitude and frequency of a current or a voltage, without switching between signal displays.

The DMM850 and DMM870 measure temperature, in Fahrenheit and Celsius, and have a time stamp facility to label minimum and maximum values as they occur. The DMM870 includes high/low limit testing, in which a beep indicator sounds when measurements exceed user-set limits.

The meters are based on the TelCom 8129/8131 chip set, for which Tektronix has exclusive rights. These ICs are claimed as the industry's first full-featured, autoranging, autocalibrated DMM analog-to-digital converter. They have a resolution of 4-3/4 digits (40,000 counts) and 0.06% basic DC volts accuracy.

All three models feature adjustable auto power-off, memory store/recall and a durable, water and dust resistant casing and are backed by a Tektronix three-year warranty. Available through authorised Tektronix distributors, the DMM870 costs $499, the DMM850 is $449, and the DMM830 is priced at $399.

For further information circle 206 on the reader service coupon or contact Tektronix Australia, 80 Waterloo Road, North Ryde; phone (02) 888 7066.

Multimeter has 1GΩ input resistance



The Thurlby Thandar model 1906 is a true RMS 5-1/2 digit computing multimeter with standard RS-232 and optional GPIB interface, auto and manual ranging. It has an effective scale length of +/-210,000 counts, and provides true RMS measurements regardless of waveshape. It has maximum sensitivities of 1uV, 1mΩ, 1nA and can measure to 750V AC and 10A AC. At high sensitivity ranges, the input impedance is 1GΩ, making the instrument suitable for measurements on high impedance circuitry.

The meter is suitable for AC and DC measurements, contact resistance and resistance measurement (two and four terminal method), capacitor leakage and high impedance measurements. Calibration constants are stored in EEPROM, allowing 'closed case' case calibration and up to six front panel set-ups can be stored, including active computing or logging functions. Computing functions include Ax + B, limits comparison, percentage deviation, min/max storage, logarithmic (dB) measurements and automatic data logging.

For further information circle 207 on the reader service coupon or contact Nilsen Technologies, PO Box 930, Collingwood 3066; phone (03) 9419 9999.

DMM computer interface card

The DMM-100 digital multimeter interface card for PC/AT and compatibles can measure DC and AC voltage and current, resistance, and perform diode/continuity tests. It has a 3-3/4 digit resolution and a sampling rate variable from 10 samples per second to one sample per hour.The card has an on-board microcontroller that performs a range of tasks, including auto calibration and auto ranging. All connections to the card are through four standard banana jacks.The card comes with menu-driven software for Windows and DOS. Also included are software drivers to simplify development of custom applications in C, Turbo Pascal, Quick or compiled BASIC, Visual BASIC and dynamic link library (DLL) for Windows application development.

For further information circle 203 on the reader service coupon or contact Interworld Electronics and Computer Industries, 1000 Glenhuntley Road, Caulfield South 3162; phone (03) 9563 5011.

Measures RF radiation

The EMR-30 field analyser from Wandel & Goltermann measures electrical fields from 100kHz to 3GHz simultaneously and isotropically (non-directional). The device has internal memory and a built-in real time clock for long term unmanned measurements. The memory contents can be downloaded to a computer for subsequent evaluation.

Device functions include averaging over time as well as spatial averaging (e.g., quadratic averaging of multiple measurements at different points in a given space). The instrument is calibrated and includes an auto-zeroing function that works under exposure to electromagnetic fields.

For further information circle 204 on the reader service coupon or contact Wandell & Goltermann, 42 Clarendon Street, South Melbourne 3205; phone (03) 9690 6700.



Measures moisture in building materials

The MicroLance from UK company Hydramotion is a portable, battery-powered probe that measures moisture content and temperature of building materials and minerals such as sand, aggregates, mixes and other minerals.



It consists of a tough sensor at the end of a variable length shaft (0.9 to 1.8m), with a computer control and readout unit mounted at the other end. Measurements are taken by inserting the probe into the material, and the meter gives an instant readout of moisture content and temperature. The meter can also average any number of moisture readings, so overall moisture for complete stockpiles or truck loads of material can be determined quickly and easily.

The instrument comes with standard calibrations, and recalibration for any material is easily done. It is powered by four 1.5V batteries that give up to 50 hours of use. Battery failure, or any other fault, is identified by an alarm display. The instrument is claimed to be largely immune to the salts and chlorides typically found in building materials.

For further information circle 208 on the reader service coupon or contact Production Supplies, PO Box 101, Noble Park 3174; phone (03) 9795 6011.


Optical power meters



Wandel & Goltermann has released its latest generation of optical power meters, the OLP-15A, OLP-16A and OLP-18A. Their main applications are in installing, maintaining and repairing fibre optical networks (LANs, complex optical distribution networks, etc).

The devices measure power and attenuation (ABS and REL) in the wavelength

Besides Oscilloscopes... we have much more to offer!



Spectrum Analyser HM5010

Features:

- Frequency Range 0.15MHz - 1050MHz
- 4 1/2 Digit Display (Centre & Marker Frequency, 0.1MHz resolution)
- -100 to +13dBm Amplitude Range, 20kHz, 400kHz and Video-Filter

OPTIONAL ACCESSORIES:

- **EMI Near Field Sniffer Probe Set HZ530**
- **50Ω–feedthrough termination HZ22**
- **Carrying Case HZ96-2**

HAMEG® Instruments

Made in Germany

CALL NOW

KENELEC

ESTABLISHED IN 1982

TEL: (03) 9878 2700
FAX: (03) 9878 0824

The latest test and measuring instruments...

range from 800 to 1700nm and offer an extended measurement range and more functions compared to their predecessors.

They cover all test requirements in the fields of data communications and telecommunications.

The OLP-15A has a display range from -70 to +20dBm and suits all telecommunications applications. This meter is also available with 150 internal memory locations and data access/remote control via an RS-232 interface.

The OLP-16A is for measuring very low input power levels. It has a display range from -80 to +15dBm, and its InGaAs photodiode makes it most sensitive in the second and third optical windows at 1300 and 1550nm.

The OPL-18A has a display range from -60 to +26dBm, for measuring high power levels such as those found on eridium-doped fibre amplifiers (EDFA) and in CATV systems.

All instruments feature audible signalling to help identify a given fibre in a fibre bundle, and include a 'twintest' function, which allows automatic measurement of two wavelengths simultaneously.

For further information circle 205 on the reader service coupon or contact Wandell & Goltermann, 42 Clarendon Street, South Melbourne 3205; phone (03) 9690 6700.

Non-contact thermometer



TASCO (Japan) has recently released the THI-400N/THI-400S series of non-contact thermometers. The devices cover the range -30 to +400°C, with a choice of twin laser sighting for accurate targeting (THI-400N) or a single LED spot marker for small targets — 2.5mm at 30mm distance (THI-400S).


Both models have adjustable emissivity, an audible alarm with upper and lower limit adjustment, and a reading hold feature. Applications include preventative maintenance in areas such as electrical hot spots, bearing failures, conveyors and any application where a quick response without contact is needed.

For further information circle 202 on the reader service coupon or contact W & B Instruments, PO Box 189, Carlton 3053; phone (03) 9347 0866.

READER INFO NO. 23

9020 DIGITAL STORAGE OSCILLOSCOPE 40MS/20MHz

The Best Cost/Performance Instrument in the Business



L.E. BOUGHEN & CO.
33 Railway Tce, Milton. Qld 4064.
Phone (07) 3369 1277
Fax (07) 3368 3193
FREE CALL 1800 068 663

READER INFO NO. 24

SoundEasy V1.1 Windows 3.1(c)
"END OF FINANCIAL YEAR" SALE - 40% OFF.

* Passive & active, up to 5-way, complete system modelling.
* Imports amplitude/impedance from IMP, CLIO & LMS.
* Two user editable impedance models.
* 7 enclosure types (1,2 and 3 chambers) & variations.
* CAD system for compensation/crossover modelling.
* Time Delay filters.
* Frequency AND time analysis for box & circuits.
* Thermal, polar, driver XYZ mounting analysis.
* Nine built-in calculators.
* 3 optimizers: box, filter & system with 'Lock' function.
* All three room resonant modes, box placement analysis.
* And much more !.

BoxCad V1.0 Windows 3.1(c)

* Scientific analysis of multi-chamber (up to 10) boxes.
* 7 Acoustic & 7 electrical impedance models built-in.
* Powered Subwoofer Design.

SoundEasy V1.1 + BoxCad V1.0....now only.....$199.00

Bodzio Software
P.O. Box 3176, Wheelers Hill, 3150 Vic.
Fax: (03) 9-561-3575, Tel: (03) 9-562-1224

READER INFO NO. 25

ACN 009 892 031

WHOLESALE RETAIL


HEWLETT PACKARD
OMNIGO Organizer Plus



☆ SPECIAL PRICES THIS MONTH

• PEN BASED OR KEYBOARD ENTRY
• HANDWRITING TEXT RECOGNITION
• IBM WINDOWS CONNECTIVITY
• SERIAL PRINTER OUTPUT
• 512K MEMORY + PCMCIA PORT

TOA JEIL



• PUBLIC ADDRESS AMPS
• WIRED & WIRELESS MICROPHONES
• COLUMN, CEILING & HORN SPEAKERS
• PORTABLE AMPLIFIERS
• MEGAPHONES

DELSOUND
1 Wickham Terrace.,
Cnr Ann & Wharf Sts,
Brisbane. Q 4000.
Phone (07) 3839 6155
Fax (07) 3832 5278

• ELECTRONIC COMPONENTS
• CABLE, LEADS, CONNECTORS
• COMPUTER ACCESSORIES
• AUDIO, VIDEO, TELEPHONE
• FULL RANGE OF PLUG PACKS
• SPEAKERS • KITS

FAX ORDER PHONE ORDER OVERNIGHT DEL AVAIL

ICOM AIPHONE DENON AKG ALTRONICS

CUSTOMER PARKING AT REAR

Ultrasonic condition monitor




The Type 1000 portable, single-channel ultrasonic receiver from British company Karousel is an industrial quality handheld instrument that provides condition monitoring and fault diagnosis of plant and equipment. Because of its internal memory, the instrument can be linked to a PC to download information. It does not require an external power supply. Unlike traditional listening techniques, in which the condition of machinery and plant is identified from audible sounds, the Type 1000 uses controlled ultrasonic frequencies, claimed to ensure more accurate and effective fault diagnosis and condition monitoring. The instrument has a high sensitivity and can be used to locate and monitor many types of faults. It is particularly effective as a leak detector. Test results are presented instantly by meter, audio, oscilloscope or chart recorder. The touch-control panel is user friendly, and the instrument can be operated with minimal training. A wide range of probes, including airborne, contact and spring-loaded is available. Accessories include transducers for a wide variety of applications. The instrument is supplied with airborne probe, contact probe, headset and mains charging unit.

Karousel is seeking an Australian agent for the instrument. For more information contact Steve Ahern or Susan Redden, British Consulate-General, Sydney; phone (02) 247 7521. ❖

25% Discount for AUTOTRAX Users

Protel Design System for Windows



- Schematic Entry
- PCB Design
- Autorouting
- Autoplace
- Simulation interfaces
- FPGA and EPLD support

Protel Technology

For more information phone
Toll Free
1800 030 949

Protel Technology
Technopark Dowsings Point 7010 Tasmania

READER INFO NO. 28

Analog & Digital **A2-D**
Audio Measurement System

The affordable instrument
Designed to meet the challenges of tomorrow's testing needs



- *Analog & Digital Generator and Analyzer*
- *User friendly front panel*
- *Stand-alone or remote control via RS-232 or IEEE-488*
- *Portable*

We set the standard in making audio testing AFFORDABLE

READER INFO NO. 27

Distributed by **Amber Technology** A.C.N. 003 231 187
Sydney: (02) 9975 1211 Melbourne: (03) 9699 1955 Brisbane: (07) 3831 8444

NEUTRIK ®
CONNECTING THE WORLD

Silicon Valley NEWSLETTER



Possible bust for chip market

Unless the current problems in the semiconductor industry turn out to be a minor speed bump on the way to reaching a trillion dollar business, the chip industry may be about to renew its reputation as a boom-bust business. A second major chip company in Silicon Valley has announced a layoff, while another has implemented a hiring freeze.

National Semiconductor in Santa Clara said it will issue pink slips for some 400 of its 21,000 workers, while Advanced Micro Devices in Sunnyvale announced it has put the brakes on hiring new employees. The latter announcement followed a warning AMD sent to financial analysts, that earnings in the current quarter are not likely to meet Wall Street expectations.

The latest moves came two weeks after Cirrus Logic in Fremont laid off several hundred people due to slowing demand for some of its chip product lines.

Only three months previously, the semiconductor industry was considered to be in a boom mode characterised by a manufacturing equipment boom, hiring frenzies, product shortages, and stable chip prices at almost unprecedented high levels.

However a glut of memory chips has caused DRAM prices to fall by 75% or more, forcing the cancellation or delay of a number of chip fab projects. This appears to be causing the first of what could result in a new wave of layoffs in the chip industry.

Some industry analysts and executives believe the downturn is a short-term phenomenon, caused by an unexpected oversupply of 4Mb DRAMs which developed during December.

Apple engineer gave Amelio a big ear

Apple Computer's new chief Gilbert Amelio got more than he bargained for when he gathered a dozen or so randomly-chosen employees for an informal meeting in his office. During the talk he spoke candidly about Apple's problems and his thoughts on the steps he may take to remedy the company's woes.

One of the chosen employees, an engineer, wrote a detailed account of the meeting, and forwarded it to Guy Kawasaki, a key member of the original Macintosh development team and now Apple's 'evangelist' in charge of drumming up support for the beleaguered company and its computer line.

Kawasaki, figuring the report would help boost morale among both Apple employees, suppliers, and users, decided — apparently without clearance from the top — to broadcast the report over an electronic mailing list that included more than 10,000 addresses both inside and outside of Apple, including news organisations. The next day, Apple scrambled for damage control as major newspapers began reporting on and interpreting the report.

The unidentified engineer's memo should not be confused with a policy announcement, one spokesman said. "It's important to note that the forum in which these remarks were made by Gil Amelio was a very informal session", said spokeswoman Nancy Paxton. "This was an example of Gil expressing his thoughts. It was not any sort of statement of strategy."

Israel moves on Intel chip plant

Despite a critical internal government report and concerns that the country cannot afford it, Israel's government has given the go-ahead to Intel's plan to build a US$1.6 billion chip plant — the largest foreign investment to date in Israel, and one that will cost the country US$600 million in grants over a 10-year period.

The Treasure Ministry's Investment Centre approved the deal after Intel promised it would purchase more local goods and services. The previous month, the project's prospect had turned sour after a government audit had suggested that Israel would not see sufficient returns on its $600 million investment. Israel's Finance Minister Abraham Shohat approved the deal after reviewing the revised proposal.

Another obstacle for Intel to overcome, however, is Israel's Parliament — where the Finance Committee would have to approve changes in the budget to free up funds for the fab, which will be built in the southern Israeli town of Kiryat Gat.



Motorola Semiconductors and Microsemi Corporation have announced that Motorola is providing a second source for Microsemi's patented 'Powermite' SMD diode package, under an exclusive licensing agreement. Powermite is a microminiature package, slightly larger than the SOT-23 package, designed to house Schottky and ultrafast rectifiers as well as TVS, zener and RF PIN diodes.

The plant is scheduled to come on line in 1998, and will employ some 2500 workers at full production. Intel expects to realise more than a billion dollars in annual revenues from the facility, with virtually all of the output being exported.

Intel phases out its i860 micro line

Intel is phasing out its line of Paragon massively parallel processing supercomputers, replacing the i860 RISC processors with machines built around its new PentiumPro chips.

The company has informed its installed base of some 100 Paragon users that it won't take new orders for the Paragon system after September.

"We will try to ship all of those orders by the end of this year, and continue to support the product through the year 2001", said Intel spokesman Howard High.

The new line of PentiumPro-based supercomputers will be smaller versions of the massive US$45 million teraflop-capable supercomputer Intel is building for the US Department of Energy's Sandia National Laboratory. That machine links more than 9000 Intel PentiumPro processors and will process data at the rate of 1.8 trillion operations per second. It will be used in simulating nuclear weapons tests, eliminating the need for underground testing.

Sun buying Britain's IMP

Sun Microsystems has entered into an agreement to acquire United Kingdom-based Integrated Micro Products, for US$96.1 million. IMP makes fault-tolerant computers for telecommunications companies. Sun will operate IMP as a new business unit.

Mark L'Anson, IMP's chief executive officer, will become vice president and general manager of the new business unit, according to Sun president Edward Zander. "With the acquisition of IMP, Sun can further expand our role in the telco market."

Added L'Anson, "After years of working side by side as technology partners, IMP and Sun now have the opportunity to create a single product family with features that offer unparalleled value to the telecom industry."

Java bug reported

Sun Microsystems has discovered a significant flaw in its Java internet programming language — one that could allow a hacker to take control of Web pages, booby-trap, read, or delete files, and subsequently invade other Web sites connected to the initial site.

Sun said a team of high-level engineers was currently working almost around the clock to fix the bug. The company hopes to deliver the software patch to NetScape Communications which uses Java, as well as post the fix on Sun's own websites for concerned internet users to download it to their own systems.

The Java bug was originally discovered by a computer science professor at Princeton University, and two of his graduate students.

Sun Microsystems Chief Executive Scott McNealy said the company takes any security issues seriously. "We'll make mistakes and application vendors will make mistakes. We'll have to correct them."

The Princeton research team said the flaw in question was the latest of three separate security faults in Java that they have discovered.

AMD finally ships its Pentium clone

'Better late than never' was the operative phrase from Sunnyvale when Advanced Micro Devices announced it had begun delivering volume orders for its AMD5K86 Pentium-compatible processor, a chip the company has invested US$100 million to develop.

The K5 chip was originally scheduled to ship last August, at the height of the chip boom market. Now AMD will sell its 75MHz version of the K5 for $75, about $30 less than Intel's charge for a 75MHz Pentium.

AMD projects it will deliver a K5 processor with the performance of a 150MHz Pentium by the end of the year.

The chip was developed at AMD's facilities in Austin and is in production at Fab 25, a US$1.4 billion state-of-the-art wafer fab that began operating last fall. The plant, which currently produces 486 chips, was built to make the 5K86 and its more advanced successors.

"At least they have a product now", said analyst Dean McCarron of Mercury Research in Scottsdale, Arizona. "This is a very important first step. Late-to-market is better than never-to-market."

AMD acknowledges that it set a too-aggressive schedule for a 'ground-up' chip design of this complexity. The chip has 4.3 million transistors. AMD projects it will make five million of the new chips over the next 12 months, generating several hundred million dollars in revenues.

Analysts believe that while critical, AMD is merely warming up the Fab 25 facility for the PentiumPro-compatible NexGen-based processor that AMD acquired last year. K6 is expected to be in production at Fab 25 early next year.

C-Cube feels pinch from IBM

C-Cube Microsystems, the leading supplier of video compression ICs for products ranging from PCs to digital satellite TV systems, saw its shares plunge $12 to US$42.75 recently, as IBM announced its semiconductor business unit has set its sights on the fast-growing video compression niche market.

IBM has launched a set of six chips that would allow digital video signals to be more easily transmitted over computer networks.

At C-Cube, marketing head David Taylor called Wall Street's reaction to the IBM announcement "laughable", saying that IBM's planned move into video compression had been known about for 18 months, and only covered a small group of products. ❖

Foreign marketshare soars in Japan's chip market...


Surging Japanese demand for semiconductor products made by non-Japanese chip makers sent the foreign market share soaring to nearly 30% during the fourth quarter of 1995, more than three times the 8.4% level at the time the first US-Japan Chip Trade Agreement went into effect 10 years ago.

During the fourth quarter, foreign chipmakers' share of the Japanese semiconductor market increased by more than 3% for the second consecutive quarter, reaching 29.6% in the quarter, and boosting the 1995 average foreign share of the Japanese chip market to a record 25.4%, up from 22.4% in 1994.

"These numbers reflect that the trade agreement is working to ensure greater access for foreign suppliers to Japanese customers", said SIA President Thomas Armstrong. "Without the agreement, in fact, we wouldn't even have these numbers to look at. This new milestone of progress also serves as an ideal stage to launch cooperative negotiations on a new trade pact between the US and Japan. The agreement not only benefits foreign manufacturers and Japanese consumers, but also US-Japan relations."

The current trade agreement with Japan is set to expire on July 31. Japanese industry and government officials have indicated they are not interested in renewing the agreement, arguing that the agreements have met their objectives and that it is time to let market forces determine progress.

Computer News and New Products





Free CD-ROM on instrumentation

National Instruments has announced a free new CD-ROM containing instrumentation information for engineers and scientists building test and measurement, and process monitoring and control applications. The Windows-compatible Instrupedia features more than 60 tutorial and 'how-to' application notes to help users learn how to combine hardware and software to build computer-based systems for instrument control and data acquisition, analysis and presentation.

It includes more than 20 user solutions that describe how scientists and engineers used instrumentation hardware and software to build custom, computer-based systems for real-world applications in electronics testing, fibre manufacturing, aerospace, automotive, electric power, transportation, environmental control and education. It also describes more than 500 hardware and software products that can be used to build instrumentation systems on more than 20 industry-standard computer platforms and more than 25 operating systems.


For further information circle 161 on the reader service coupon or contact National Instruments Australia, PO Box 466, Ringwood 3134; phone (03) 9879 9422.

PC-based audio analyser

LinearX Systems is now shipping the new RTAjr PC-based Real Time Analyzer, a 1/3 octave real time analyser for PC computers. The complete system consists of an ISA half-length PC slot card, a 3.5mm to XLR mic adapter cable, and Windows based operating software. There are four different, calibrated LinearX microphones (M31, M51, M52, or M53) with maximum SPL capabilities ranging from 125dB to 170dB.

Included are built-in scoring systems popular with car stereo enthusiasts for both IASCA and USAC, as well as a host of different post processing and display capabilities, only possible in a PC-based analyser. In addition to measuring maximum SPL and 1/3-octave RTA response, the RTAjr also includes built-in ANSI A, B and C weighting filters, and an impedance measurement capability for checking speakers and crossovers for defective components or connections. The curve data can be viewed in various ways including bar graph mode, line graph mode and text chart mode. The analyser is priced at $1095.

For further information circle 163 on the reader service coupon or contact ME Technologies, PO Box 50, Dyers Crossing 2429; phone (065) 50 2200. ME can also be contacted by email at **me@midcoast.com.au**; or on the internet at URL **http://www.midcoast.com.au/bus/me**.



Amateur radio log program

Ham Log is a logging program specifically designed for ham radio operators. Version 3.1 has just been released, which according to its developer contains all the features that 'heavy' log users said they wanted.

The program keeps statistics on log contacts such as the number of countries worked, versus the mode and frequency. The same statistics are kept for confirming contact.The program requires about 1.35MB hard disk space, comes with a manual and has the usual F1 help screens. The program is priced at $59.

For further information circle 162 on the reader service coupon or contact Dr HiFi, 74 Carrington Road, Waverley 2024; phone (02) 369 2008.

Industrial panel mount 486DX computer

The Lucas Deeco range of 486DX series panel mount industrial computers incorporate a flat panel display. Designed for use in harsh environments, these industrial computers are powered by a 486DX/2 at 66MHz or a 486DX at 33MHz, and include a patented Lucas Deeco SealTouch infrared touch system, with an integrated touch mouse and/or membrane keypad.



There is a choice of an active matrix colour LCD or mono electroluminescent display. The sealed front panel meets NEMA 4 and 12 (IP-65) Standards with the floppy drive access and reset switch covered by a sealed door. Input/output is available through a serial port, a parallel port and a sealable keyboard port. Four full sized expansion slots are provided.

For further information circle 164 on the reader service coupon or contact Amtex Electronics, 13 Avon Road, North Ryde 2113; phone (02) 805 0844.

DC powered computer systems

Intecolor Corporation has developed a range of 24V and 48V DC power options that lets critical work stations and monitors run from batteries, independently of commercial mains. This option is available on several Intecolor product lines including Intecolor's stand alone rackmount PCs, fully integrated PC workstations with 14" or 20" display, and 14", 20" and 21" computer monitors. This compares to standard monitors powered by inverters. The option doesn't require any extra rack or panel space.


For further information circle 165 on the reader service coupon or contact Intelligent Systems Australia, PO Box 118, Berwick 3806; phone: (03) 9796 2290.

Transformer design software

Magnetics Designer is a new program for Windows that helps you design all types of transformers and inductors. Typical design applications include high frequency switching regulator transformers and output chokes for off-line full wave and forward converters, 60Hz single phase line transformers, AC inductors, planar magnetics, and 400Hz aircraft transformers. Virtually any single phase, layer wound, inductor or transformer from 10Hz to over 1MHz can be synthesized with the program.

The software produces a complete transformer or inductor design based on electrical specifications. An extendable database with thousands of cores and a wide variety of materials is included. Core and material information can be added using a supplied Excel spreadsheet template. A variety of core families are represented from vendors like TDK Magnetics, Philips, Thomson, Micrometals and Ferrite International, each with its respective magnetic and geometric properties. The program predicts magnetising and leakage inductance, interwinding capacitance, peak flux density, DC winding resistance, high frequency AC resistance, copper loss (both

Be an expert !!




These are some of the books that can help you

√ Complete Guide to High End Audio
√ Loudspeaker Design Cookbook (V)
√ Killer Car Stereo on a Budget
√ Principles of Electron Tubes
√ Vacuum Tube Logic Book
√ Loudspeaker Recipes: 1
√ Audio Dictionary
√ Test CD's

Call us for a full list!






ME Technologies

Come & have a Browse
http://www.midcoast.com.au/bus/me

Post Office Box 50, Dyers Crossing NSW 2429
Phone: (065) 50 2200 Fax: (065) 50 2341
Email: me@midcoast.com.au

READER INFO NO. 21



Red Shield Appeal Sunday May 24

THE SALVATION ARMY


AC and DC), core loss, weight, temperature rise, layer fill, and window fill percentage. As an introductory offer Magnetics Designer is priced at $1570, valid until June 28, 1996. Thereafter the price is $2355.

For further information circle 163 on the reader service coupon or contact ME Technologies, PO Box 50, Dyers Crossing 2429 phone (065) 50 2200. (email **me@midcoast.com.au**; internet **http://www.midcoast.com.au/bus/me**).

High speed cable modem

Scientific-Atlanta has announced a stand-alone cable modem for hybrid fibre/coax (HFC) networks. Operating at data rates of up to 27 megabits per second (Mb/s), the modem will significantly outperform current modems that provide access to the Internet and online services.

Scientific-Atlanta has already demonstrated a high-speed data communications



system running over a hybrid/coax fibre network. The demonstration system delivered rates up to 27Mb/s using a modified version of Scientific-Atlanta's current digital home communications terminal and digital headend equipment.

For further information circle 167 on the reader service coupon or contact Scientific-Atlanta 2/2 Aquatic Drive, Frenchs Forest 2086; phone (02)452 3388.

New class of colour lasers

Hewlett-Packard has announced its next-generation color laser printers, the HP Color LaserJet 5 and 5M printers. Both printers feature image resolution enhancement technology (Image REt) 1200, an HP-developed technology that gives 1200dpi equivalent image quality — resulting in colorful graphics, sharp text and millions of solid colors. Through more efficient toner placement, HP claim a colour page from the Color LaserJet 5 printer costs less than a page from some monochrome laser printers.

The printers are part of a new class of colour laser printers that produce smooth, 'continuous tone' image quality through advanced colour-control techniques. With this new type of colour laser printer, dots per inch alone is no longer an accurate indicator of print quality.

Many printers in this new category can produce continuous tone output by controlling precisely how colour toner is placed on the page. These printers, known for their detailed, smooth image quality, are a step above traditional colour laser printers, which use simple dot patterning or 'dithering' techniques to reproduce non-primary colors such as orange or purple.

The HP Color LaserJet 5 printer, designed for Windows 3.1, Windows 95, Windows NT, DOS and IBM 0S/2 computing environments, comes with enhanced HP PCL 5 with Color, 20MB RAM and an HP Bi-Tronics bidirectional parallel port.


The RRP (including sales tax) for the HP Color LaserJet 5 is $14,040, and $17,309 for the HP Color LaserJet 5M. For further information contact HP Customer Service on 13 1347.

29" monitor for industry

Intecolor's 29" computer monitor is the newest addition to the company's line of industrial displays.

The new monitor is suitable for training facilities, large control rooms and in specialised areas such as ship board control and telecommunication.


The monitor supports resolutions from VGA up to 1600x1280. Features include high bandwidth differential video inputs, dynamic focus, a unique 'VGA boot mode' and a high contrast invar shadow mask CRT.



With a high temperature limit of 55°C tested for 1000 hours at 70°C and a MTBF of over 45,000 hours at 25°C the Intecolor unit is one of the most robust of any display on the market.

For further information circle 168 on the reader service coupon or contact Intelligent Systems, PO Box 118, Berwick 3806; phone (03) 9796 2290.

Australian Computers & Peripherals from JED... Call for data sheets.




Australia's own PC/104 computers.

The photo to the left shows the JED PC540 single board computer for embedded scientific and industrial applications. This 3.6" by 3.8" board uses Intel's 80C188EB processor. A second board, the PC541 has a V51 processor for full XT PC compatibility, with F/Disk, IDE & LPT. Each board has two serial ports (one RS485), a Xilinx gate array with lots of digital I/O, RTC, EEPROM. Program them with the $179 Pacific C. Both support ROMDOS in FLASH. **They cost $350 to $450 each.**

$125 PROM Eraser, complete with timer

$300 PC PROM Programmer.



(Sales tax exempt prices)

Need to programme PROMs from your PC?

This little box simply plugs into your PC or Laptop's parallel printer port and reads, writes and edits PROMs from 64Kb to 8Mb. It does it quickly without needing any plug in cards.

JED Microprocessors Pty. Ltd

Office 7, 5/7 Chandler Road, Boronia, Vic., 3155. Phone: (03)9 762 3588 Fax: (03)9 762 5499

READER INFO NO. 40

R CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...

WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...WOOD FOR CHIPS...

EA DIRECTORY OF SUPPLIERS

Which of our many advertisers are most likely to be able to sell you that special component, instrument, kit or tool? It's not always easy to decide, because they can't advertise all of their product lines each month. Also, some are wholesalers and don't sell to the public. The table below is published as a special service to EA readers, as a guide to the main products sold by our retail advertisers. For address information see the advertisements in this or other recent issues.

Supplier	State	A	B	C	D	E	F	G
Altronics	WA	•	•	•	•	•	•	•
Dick Smith Electronics	ALL	•	•	•	•	•	•	•
Emona Instruments	NSW						•	
Geoff Wood Electronics	NSW	•	•	•	•	•	•	
Jaycar Electronics	Eastern	•	•	•	•	•	•	•
Kalex	VIC			•				
RCS Radio	NSW			•				
Rod Irving Electronics	Eastern	•	•	•	•	•	•	•
Scientific Devices	VIC						•	
TECS	VIC	•	•	•	•	•	•	•

KEY TO CODING

A	Kits and modules	D	Components
B	Tools	E	IC chips and semiconductors
C	PC boards and supplies	F	Test and measuring instruments
		G	Reference books

Note that the above list is based on our understanding of the products sold by the firms concerned. If there are any errors or omissions, please let us know.

Electronics Australia Reader Services

SUBSCRIPTIONS: All subscription enquiries should be directed to: Subscriptions Department, Federal Publishing Company, P.O. Box 199, Alexandria 2015; phone (02) 353 9992.

BACK ISSUES: Available only until stocks are exhausted. Price A$7.50 which includes postage within Australia only. **OVERSEAS READERS SHOULD ADD A FURTHER A$2.50 FOR EVERY BACK ISSUE REQUIRED.**

PHOTOCOPIES: When back issues are exhausted, photocopies of articles can be supplied. Price $7.50 per project or $15 where a project spreads over several issues.

PCB PATTERNS: High contrast, actual size transparencies for PCBs and front panels are available. Price is $5 for boards up to 100sq.cm, $10 for larger boards. Please specify negatives or positives.

PROJECT QUERIES: Advice on projects is limited to postal correspondence only and to projects less than five years old. Price $7.50. Please note that we cannot undertake special research or advise on project modifications. **Members of our technical staff are not available to discuss technical problems by telephone.**

OTHER QUERIES: Technical queries outside the scope of 'Replies by Post', or submitted without fee, may be answered in the 'Information Centre' pages at the discretion of the Editor.

READER SERVICES BULLETIN BOARD: (02) 353 0627, 24 hour access.

PAYMENT: Must be negotiable in Australia and payable to Electronics Australia. Send cheque, money order or credit card number (American Express, Bankcard, Mastercard or Visa card), name and address (see form).

ADDRESS: Send all correspondence to: The Secretary, Electronics Australia, P.O. Box 199, Alexandria NSW 2015; phone (02) 353 0620.

PLEASE NOTE THAT WE ARE UNABLE TO SUPPLY BACK ISSUES, PHOTOCOPIES OR PCB ARTWORK OVER THE COUNTER.

Name:.....

Address:.....

.....State:.....Postcode:.....

.....

Back issues:.....

.....

.....

Photocopies:.....

.....

.....

Amount: A$.....

Signature:.....(Unsigned orders cannot be accepted.)

Method of Payment: (Please circle correct method.) Credit card / Cheque / Money order.

Credit cards accepted:

Mastercard, American Express, Visa Bankcard (please circle applicable card).

Expiry date:.....

....


ADVERTISING INDEX


Active Electronics 75
Allthings Sales & Services 86
Altronics 76-79
Amber Technology 123
AV-COMM 45
Aztronics 101
Bodzio Software 122
Campad Electronics .....102/3?
Data Electronics 114
Delsound 122
DGE Systems 118
Dick Smith Electronics .....7,52-53, Cat.
Dominion Electronics 118
Don Alan Electronics .....102/3?
EA subscriptions offer 115
Force Electronics 41
FPC Marketing 67,114
Geoff Wood Electronics 129
Hewlett-Packard Australia IFC,105
Hinton Information 75
Instant PCBs .....102/3?
IRT Electronics 113
Jaycar Electronics 68-71
JED Microprocessors 128
Kenelec 119,121
L.E. Boughen 122
Leprechaun Software 127
Memory International 111
ME Technologies 127
Obiat 83
Peter Lacey Services 46
Procon Technology .....IBC
Protel Technology 123
Randmere .....102/3?
RCS Radio 102/3
Robert Bosch Australia 87
Rocom Elect. Components 49
Rod Irving Electronics 91-93
Scientific Devices 117
Solar Corporation 75
TECS Wholesale 59
Tektronix Australia .....OBC
Vintage Wireless Radio Co. 101


This index is provided as an additional service. The publisher does not assume any liability for errors or omissions.

fischertechnik®

ROBOTIC KITS FOR COMPUTERS







This new construction kit is now available for all computer fanatics who want to build fascinating models from the world of computers. Anything goes - a robotic arm, a mobile turtle and even a 'CD Player'. The fischertechnik interface unit (also sold separately) plugs into the printer port on any IBM-PC computer. With example software available in BASIC, C, Pascal and programmable control languages (Sequential flow chart and relay ladder logic) your models really come to life. The full range of Profi kits is now available in Australia including the new pneumatics kit and a variety of other computer controlled kits from $399.

AVAILABLE FROM: PROCON TECHNOLOGY

TEL: (03) 9807 5660 FAX: (03) 9807 8220

P.O. BOX 655, MT WAVERLEY, 3149 *DEALER ENQUIRIES WELCOME

READER INFO NO. 42

The new Tektronix meters are a generation ahead of Fluke.

Measure for yourself.

30-Day Money Back Guarantee Program
Proof of Our Product Quality.









Feature	Tek DMM830	Typical DMM
Display count	40,000	4,000
True RMS	Yes	No
Basic DC volts accuracy	0.2%	0.3%
RRP*	$399	$470

Feature	Tek DMM850	Typical DMM
Display count	40,000	4,000
True RMS	Yes	No
Basic DC volts accuracy	0.1%	0.1%
RRP*	$449	$520

Feature	Tek DMM870	Typical DMM
Display count	40,000	4,000/20,000
True RMS	Yes	Yes
Basic DC volts accuracy	0.06%	0.1%
RRP*	$499	$652

You've used the same old meters for years. Perhaps it's time you had a better alternative.

Tektronix, the world leader in precision measurement, has used state-of-the-art design and engineering to bring you a quantum leap in handheld meters.

A line of products that are a generation more precise, a generation more versatile and a generation more cost-efficient than anything else today.

Look at the specifications here for proof. Or look at a more comprehensive comparison on our Web site by going to www.tek.com/mbd/meters.

Even better, look at the meters themselves at your nearest Tektronix distributor.

And make a measured decision.

NSW
Emona Instruments (02) 519 3933

QLD
St Lucia Electronics (07) 3252 7466
Emona Instruments (07) 3367 1744

VIC
Emona Instruments (03) 9889 0427

SA
Emona through
Wavecom Instruments (08) 331 8892

NT
DataComm Australia (089) 471 600

WA
Control Dynamics (09) 275 9700
Emona Instruments (09) 361 4200

NZ
Datamatic Networks 9 415 6928

Tektronix

READER INFO NO. 43

*Manufacturer's suggested retail price. Contact your Tektronix distributor for current pricing information. ©1996, Tektronix, Inc. All rights reserved. Tektronix is a registered trademark of Tektronix, Inc.